EXPORT CATALOGUE 2024/2025 **GEMAS**

GEMAS was established on 23.09.1993 by the iniative of Mr. İBRAHİM ÜSTÜNES who is currently the general manager of the company. In our region, GEMAS is a leader manufacturing company; having 1500 m² office, 20000 m² indoor production facility + warehouse and over 400 employees. The company has a continuous tendency of growth by means of the deep experience of engineering and manufacturing in the swimming pool sector.

GEMAS has a very wide range of products, manufactured under ISO 9001-2000 quality management system approved by TUV Sud; namely:

Roto-Molded, Injected and Blow Molded Thermoplastic, Bobbin Wound and FRP Sand Filters, Multiport Valves, Self-priming Pumps, Skimmers, Underwater Lights, Transformers, Inlets, Main Drains, Ladders, Diving Boards, Overflow Gratings, Automatic pH and Redox Controllers, Salt Chlorinators, Cleaners and Cleaning Accessories, UPVC Fittings and Valves, Olympic Pool Accessories, Heaters and Fountain Nozzles,

GEMAS Group has structured GEMPAS Pazarlama Lojistik A.S. company, based in Izmir, oppointed to run all sales, marketing and distribution activities of the group national and international. GEMPAS operates with 3000 sqm central warehouse in ITOB, same industrial zone with GEMAS factory, 3 sales shops around Turkey and 2 international subsidiaries Bulgaria and Dubai.

Group also includes another production company STAR Water Technology. Star is dedicated to produce high quality PVC pressure fittings and valves with FITVALF brand.

GEMAS Group with its production and distribution companies; are ready to provide high quality swimming pool products with competitive prices and very high customer satisfaction.



01	Pumps	12
02	Sand Filters	31
03	Poolside Equipment	77
04	In-Pool Materials	99
	Electrical Equipment	118
06	Disinfection Systems	166
	Let 1	4
07	Pool Chemicals	192
08	Test Kits	201
09	Cleaning Equipment	206
10	Heating Equipment	227
11	Water Attractions	239
12	Winter Pool Covers	256
13	Valves, Unions and Fittings	260
14	Olympic Pool Accessories	279
	Spa Equipment &	294
	Steam Room	300
16	Fountain Nozzles &	310
	Submersible Pumps	336
17	Concrete and Liner Pools &	349
1 /	Pool Building Materials	UT /

WE HAVE EXPANDED OUR IZMIR FACTORY!... We are at your service with our new sales organization...

We have optimised our production by increasing capacity at our Izmir Factory with 20000 m² production area and 1500 m² office area on 15 acres of land.

Our factory is located in ITOB Organized Industrial Zone between Menderes and Torbal in zmir.

Our new sales organization "GEMPAS PAZARLAMA" started its operations in Izmir ITOB with a 3000 m² main warehouse.

All our domestic branches and international subsidiaries operate within the new sales organization with a total of 3500 m² closed warehouse space.



Production Video



Istanbul Head Office





Izmir Factory



Istanbul Warehouse



Antalya Branch Office



Gempas Pazarlama - Izmir Center



Gemas MEA, Dubai





GEMPAS PAZARLAMA LOJISTIK TICARET A.S. BANK ACCOUNT

HALKBANK IBAN No:

TR29 0001 2009 7290 0058 0001 94 (€)


TR21 0001 2009 7290 0053 0001 82 (\$) SWIFT CODE: TRHBTR2AXXX

• GARANTI BANK IBAN No:

TR73 0006 2000 4480 0009 0719 05 (€)

TR03 0006 2000 4480 0009 0719 04 (\$)

SWIFT CODE: TGBATRISXXX



New Products.





GEMAS "Seljuk" BL

High Rate Sand Filter
•Ø900 mm w/2" Multiport Valve



31 GEMAS "Monocon L-LH"

Pool Sand Filters •Ø500 •Ø630 • Ø710 mm (Ø500 & Ø710 mm in 2025)



3" Multiport Valve (in 2025)



Automatic Multiport Valve

1½" & 2" in 2025 w/Optional Wifi Control



Disabled Lift Rechargeable



70 Twister
U/W LED Light

123

73









Dosing Pumps (in 2025) 67

GEMAS Selenoid Dosing Pumps

Analogue Control

Digital pH Control

Digital ORP Control





197



GEMAS "Heavy-Duty Flex" Pool Cleaners

w/or w/o Brush





GEMAS Heatrone

233-234

Heatrone PRO - Heatrone PRO - Ti / 316 Heatrone - Heatrone - Ti / 316







GEMAS Heatrone MINI

233-234

Heatrone MINI PRO - Heatrone MINI PRO Ti / 316 Heatrone MINI - Heatrone MINI Ti / 316

New Products.




261

262



Ball Valves

d.25 - d.32 - d.40 UPVC Ball Valves



Ø63 mm

UPVC Automatic Ball w/Actuator Valves

260

263

Ø50 - Ø63 mm with optional wifi control



UPVC Three Way Valve 262 Ø63 mm

Wide demper opening distance Demper closure with spring



Butterfly Valves

Ø200 - Ø225 mm Butterfly Valve Ø75 - Ø90 mm Butterfly Valve (in 2025)



UPVC Swing Type Check Valve Ø63 mm

Transparent top lid for open view UPVC Body Ø63 mm socket connection



UPVC Fittings

266



Track-Start Platform

Height: 700 mm





SPAs with/Different dimensional 11 models





Self-priming Pool Pumps

GEMAS "DRIFTER"

Self-priming, thermoplastic body pump with monoblock pre-filter. Connections are with slip unions (Ø50 or Ø63) or female threaded (2"). Pump shaft is stainless steel.

Easy opening lid with 40° rotation. Transparent "Xylex" cover option for high chemical resistance against cracks. 3 I pre-filter basket much larger than its equivalents.

Co-axial pump connections offer convenience for replacing various pumps from different brands available in the market.






2" Female connection

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• DRF-50M 0,5 HP, Monophase	0111DRF50M	1	12,195	0,038
• DRF-80M 0,75 HP, Monophase	0111DRF75M	1	13,081	0,038
• DRF-80T 0,75 HP, Triphase	0111DRF75T	1	12,485	0,038
• DRF-100M 1 HP, Monophase	0111DRF100M	1	13,765	0,038
• DRF-100T 1 HP, Triphase	0111DRF100T	1	13,100	0,038
• DRF-150M 1,5 HP, Monophase	0111DRF150M	1	16,680	0,038
• DRF-150T 1,5 HP, Triphase	0111DRF150T	1	15,460	0,038
• DRF-200M 2,0 HP, Monophase	0111DRF200M	1	18,530	0,038
• DRF-200T 2,0 HP, Triphase	0111DRF200T	1	16,760	0,038
• DRF-300M 3,0 HP, Monophase	0111DRF300M	1	18,530	0,038
• DRF-300T 3,0 HP, Triphase	0111DRF300T	1	16,760	0,038



Ø50 or Ø63 Slip connection self coupling



CON-DEN-

SER (µF)

14 2.60

14 3.50

20

25 6,40

30

0,50

AMPERES

|| || ||| |220 V | 220 V | 380 V


2.60

4,70 2,70

3 50

4.60 3.30 1.90

8.70 6.00



8.00

24.60 21.76

HEAD mwh

12 14

6.00

10.44

14,73 11,39

1.00

6.95


1,00


FLOW m3/h

5.00 | 1.00

9.00

13 33





Wide and clear view on pre-filter lid

PUMP TYPE		DIMENSIONS											Net W (K	/eight g)	Gross Weight (Kg)	
	K	K	M	Α	В	С	D	Е	F	G	Н	L	Mo.	Tri.	Mo.	Tri.
DRF-50M	Ø50	Ø50	2"	550	206	307	105	271	262	236	205	313	11,245	-	12,195	-
DRF-80T/M	Ø50	Ø50	2"	550	206	307	105	271	262	236	205	313	12,331	11,535	13,081	12,485
DRF-100T/M	Ø50	Ø50	2"	550	206	307	105	271	262	236	205	313	12,815	12,151	13,765	13,100
DRF-150T/M	Ø 63	Ø63	2"	580	206	307	105	271	262	236	205	313	15,729	14,509	16,680	15,460
DRF-200T/M	Ø 63	Ø63	2"	580	206	307	105	271	262	236	205	313	17,579	15,811	18,530	16,760
DRF-300T/M	Ø 63	Ø63	2"	580	206	307	105	271	262	236	205	313	17,579	15,811	18,530	16,760

14.00 | 12.00 | 10.00

1,45 16,00 15,00 13,00 11,00

31.48 30.13

36,35 35,61

22.00 20.33 18.30 15.80

27,26 | 26,00 | 23,50 | 21,00 | 18,00



Stainless steel motor shaft

SUCTION PIPE DIMENSIONS

PUMP TYPE

DRF-50M

DRF-80T/M

DRF-100T/M

DRF-150T/M

DRF-200T/M

DRF-300T/M

PUMP TYPE	DRF-50M	DRF-80T/M	DRF-100T/M	DRF-150T/M	DRF-200T/M	DRF-300T/M
SUCTION PIPE Ø	1,5" (Ø50 mm)	2" (Ø63 mm)	2,5" (Ø75 mm)	2,5" (Ø75 mm)	3" (Ø90 mm)	3" (Ø90 mm)

PS: It is recommended to use a conical reducer at the suction line of the pump.



2850 rpm



Self-priming Pool Pumps

GEMAS "STREAMER 2010" Self-priming, thermoplastic body Monoblock Pool Pump; complete with pre-filter. Models of 1 HP and below - suction Ø is 1,5" and discharge Ø is 2". Models of 1,5 HP and above - both suction and discharge Ø are 2". Connection unions are compatible with Fitvalf d50 ball valve handle. Easy opening lid with 40° rotation. Optional "Xylex" lid for enhanced chemical resistance. Large pre-filter basket. 2850 rpm - IP55 motor. Pump shaft is stainless steel.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
•STRN-50M 0,5 HP, Monophase	0111STRN50M	1	11,514	0,051
•STRN-80M 0,75 HP, Monophase	0111STRN75M	1	12,484	0,051
•STRN-80T 0,75 HP, Triphase	0111STRN75T	1	11,750	0,051
•STRN-100M 1 HP, Monophase	0111STRN100M	1	13,609	0,051
•STRN-100T 1 HP, Triphase	0111STRN100T	1	12,244	0,051
•STRN-150M 1,5 HP, Monophase	0111STRN150M	1	16,344	0,051
•STRN-150T 1,5 HP, Triphase	0111STRN150T	1	15,669	0,051
•STRN-200M 2,0 HP, Monophase	0111STRN200M	1	18,404	0,051
•STRN-200T 2,0 HP, Triphase	0111STRN200T	1	17,534	0,051
•STRN-300M 3,0 HP, Monophase	0111STRN300M	1	18,404	0,051
•STRN-300T 3,0 HP, Triphase	0111STRN300T	1	17,534	0,051
•STRN-350M 3,5 HP, Monophase	0111STRN350M	1	21,704	0,054
•STRN-350T 3,5 HP, Triphase	0111STRN350T	1	20,384	0,054
DEDECOMANICE CUIDVEC				




Easy access lid



Wide and clear view on pre-filter lid Made of polycarbonate





Coupling compatible with d50 Fitvalf ball valve handle

	CON- DEN-	A	MPERES	3	HEAD mwh									
PUMP TYPE	HP	DEN- SER	l 11	III		4	6	8	10	12	14	16	18	20
		(μF)	220 V	220 V					FLO	OW m³/h				
STRN-50T/M	0,50	14	2,60	-	-	20,50	18,00	14,30	10,00	4,00	-	-	-	-
STRN-80T/M	0,75	14	3,50	2,50	1,45	21,70	19,50	17,00	13,00	6,00	-	-	-	-
STRN-100T/M	1	20	4,60	3,30	1,90	28,00	25,70	22,50	18,00	13,90	6,00	-	-	-
STRN-150T/M	1,5	25	6,40	4,70	2,70	32,00	29,70	26,50	24,00	20,00	15,50	8,00	-	-
STRN-200T/M	2	30	8,70	6,00	3,50	35,00	33,00	30,00	27,50	23,80	19,50	12,00	-	-
STRN-300T/M	3	30	8,70	6,00	3,50	40,00	38,00	36,00	32,40	27,60	23,20	18,50	13,00	-
STRN-350T/M	3,5	65	12,30	7,65	4,40	42,00	41,00	40,00	38,00	35,50	32,00	26,40	18,50	7,10



Large volume basket

PUMP TYPE		DIMENSIONS											Net W (K			Gross Weight (Kg)	
7 51111 7 17 2	DNA	DNI	Α	K	В	С	D	Е	F	G	Н	L	Mo.	Tri.	Mo.	Tri.	
STRN-50T/M	1,5"	1,5"	610	80	215	310	160	275	320	292	245	355	10,290	-	11,514	-	
STRN-80T/M	2"	1,5"	610	80	215	310	145	275	320	292	245	355	11,234	-	12,484	-	
STRN-100T/M	2"	1,5"	610	80	215	310	145	275	320	292	245	355	12,360	11,000	13,609	12,244	
STRN-150T/M	2"	2"	630	80	215	310	160	275	320	292	245	355	15,095	14,420	16,344	15,669	
STRN-200T/M	2"	2"	630	80	215	310	145	275	320	292	245	355	17,150	16,280	18,404	17,534	
STRN-300T/M	2"	2"	630	80	215	310	145	275	320	292	245	355	17,150	16,280	18,404	17,534	
STRN-350T/M	2"	2"	670	80	215	310	145	275	320	292	245	355	20,450	19,130	21,704	20,384	



Stainless steel motor shaft

SUCTION PIPE DIMENSIONS

PUMP TYPE	STRN-50T/M	STRN-80T/M	STRN-100T/M	STRN-150T/M	STRN-200T/M	STRN-300T/M	STRN-350T/M
SUCTION PIPE Ø	1,5" (Ø50 mm)	2" (Ø63 mm)	2,5" (Ø75 mm)	2,5" (Ø75 mm)	3" (Ø90 mm)	3" (Ø90 mm)	4" (Ø110 mm)

PS: It is recommended to use a conical reducer at the suction line of the pump.

2850 rpm

Self-priming Pool Pumps

GEMAS "STREAMER MINI"

Self-priming, thermoplastic body Monoblock Pool Pump; complete with pre-filter. Pump shaft in stainless steel. Suction & Discharge 1,5". 2850 rpm - IP55 Motor. Easy opening lid with 40° rotation. "Xylex" lid option for resistance against aggressive chemicals.





Easy access lid











Noryl impeller



Stainless steel motor shaft

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•STRM-33M 0,33 HP, Monophase	0111STRM33M	1	10,980	0,037
• STRM-50M 0,5 HP, Monophase	0111STRM50M	1	11,140	0,037
• STRM-80M 0,75 HP, Monophase	0111STRM80M	1	13,200	0,037
•STRM-80T 0,75 HP, Triphase	0111STRM80T	1	13,000	0,037
•STRM-100M 1 HP, Monophase	0111STRM100M	1	12,800	0,037
•STRM-100T 1 HP, Triphase	0111STRM100T	1	11,620	0,037
•STRM-150M 1,5 HP, Monophase	0111STRM150M	1	12,800	0,037
•STRM-150T 1,5 HP, Triphase	0111STRM150T	1	11,620	0,037





		CON-	А	MPERES	3				HE	AD mwh				
PUMP TYPE	HP	DEN- SER	l 11			4	6	8	10	11	12	14	16	17
		(μF)	220 V	220 V	380 V				FLC	OW m³/h				
STRM-0,33M	0,33	12,50	2,70	-	-	14,10	11,60	8,30	4,00	-	-	-	-	-
STRM-0,50M	0,50	14,00	2,60	-	-	17,20	14,90	11,40	7,90	4,80	-	-	-	-
STRM-0,80T/M	0,75	14,00	3,50	2,50	1,45	18,90	16,70	13,50	10,80	9,00	6,80	-	-	-
STRM-1,00T/M	1,00	14,00	3,50	2,50	1,45	20,80	19,30	17,10	14,90	13,20	10,50	6,00	-	-
STRM-1,50T/M	1,50	20,00	4,60	3,30	1,90	26,00	24,80	22,00	19,50	18,00	16,50	12,50	15,00	-

PUMP TYPE		DIMENSIONS												Net Weight (Kg)		Weight (g)
1000 1112	DNA	DNI	Α	K	В	С	D	Е	F	G	Н	L	Mo.	Tri.	Mo.	Tri.
STRM-0,33M	1,5"	1,5"	510	70	175	265	140	240	255	210	210	315	9,980	-	10,980	-
STRM-0,50M	1,5"	1,5"	540	70	175	265	140	240	255	210	210	315	10,140	-	11,140	-
STRM-0,80T/M	1,5"	1,5"	540	70	175	265	140	240	255	210	210	315	12,200	-	13,200	13,000
STRM-1,00T/M	1,5"	1,5"	540	70	175	265	140	240	255	210	210	315	11,800	10,620	12,800	11,620
STRM-1,50T/M	1,5"	1,5"	540	70	175	265	140	240	255	210	210	315	11,800	10,620	12,800	11,620

SUCTION PIPE DIMENSIONS

PUMP TYPE	STRM-33M	STRM-50M	STRM-80T/M	STRM-100T/M	STRM-150T/M
SUCTION PIPE Ø	1,5" (Ø50 mm) 1,5" (Ø50 mm)		2" (Ø63 mm)	2" (Ø63 mm)	2,5" (Ø75 mm)

PS: It is recommended to use a conical reducer at the suction line of the pump.



"Saving Energy",

Weight

Kg

14,000

19,050

Volume

 m^3

0,051

0,051

Self-priming - Variable **Speed Pumps**

GEMAS "RANGER" Self-priming, thermoplastic body pump with monoblock pre-filter. Connections are with unions; 1,5 HP model - suction Ø is 1,5" and discharge Ø is 2". 3 HP Model both suction and discharge Ø are 2". Pump shaft is stainless steel. Easy opening lid with 40° rotation. "Transparent "Xylex" cover option for high chemical resistance against cracks.

4,5 I pre-filter basket much larger than its equivalents. Pump connection fittings can be tightened and opened with 50 mm Fitvalf ball valve handle. Three cycles, allowing to choose between 1400-2850 cycles.

Code

0111RN150M

Factory settings: 1st cycle - 2100 rpm, 2nd cycle - 2400 rpm, 3rd cycle - 2850 rpm. Permanent Magnet - IP55 motor. Cable connection is available for speed control from the external panel. Motors are single-phase input. It has soft start and stop features.

Pieces/


hox



•RN-300M	• RN-300M 3,0 HP, Monophase								
VARIA	BLE SPEED MOTOR PERFORMANCE CU	RVES							
20		K K							
15		3 HP 2 2850 did							
10		3 HP 2400 d/d							
5	1.5 HP 1.5 2400 d/d 1.5 1.5 HP 2500 d/d	HP D did							

Description

• RN-150M 1,5 HP, Monophase



									HEAD) mwh						
PUMP TYPE		4	5	6	7	8	9	10	11	12	13	14	15	16	17	17,5
RN-150M	-150M 1,5 FLOW m³/h															
2100 rpm		18,25	15,85	13,35	10,11	3,43	-	-	-	-	-	-	-	-	-	-
2400 rpm		-	-	19,06	17,05	14,40	11,88	5,55	-	-	-	-	-	-	-	-
2850 rpm		-	-	24,15	23,30	22,00	20,90	19,50	17,37	15,30	11,50	6,40	2,40	-	-	-
								А	MPERE:	S II 220	V					
2100 rpm		2,50	2,40	2,20	2,20	1,60	1,30	-	-	-	-	-	-	-	-	-
2400 rpm		-	-	3,50	3,50	3,40	3,00	2,40	1,70	-	-	-	-	-	-	-
2850 rpm		_	_	6.00	5 90	5 90	5.80	5 90	5 60	5 40	4 90	4 10	3 30	2 90	_	-

			HEAD mwh												
PUMP TYPE		7	8	9	10	11	12	14	15	15,5	16	18	20	21	21,5
RN-300M	3,0		FLOW m³/h												
2100 rpm		22,50	19,50	17,50	15,00	11,00	6,50	-	-	-	-	-	-	-	-
2400 rpm		-	-	25,00	22,00	19,00	17,50	11,00	2,00	-	-	-	-	-	-
2850 rpm		-	-	-	30,00	28,50	28,00	24,00	-	-	21,00	19,00	7,50	4,00	-
								AMPE	RES II 2	20 V					
2100 rpm		7,00	6,70	6,50	5,90	5,20	4,40	-	-	-	-	-	-	-	-
2400 rpm		-	-	10,30	9,30	-	8,50	7,00	5,30	5,00	-	-	-	-	-
2850 rpm		-	-	-	14,60	-	14,60	14,60	-	-	14,60	13,20	9,90	8,40	8,00

PUMP TYPE						DIMEN	ISIONS						Net Weight (Kg)	Gross Weight (Kg)
TOWN THE	DNA	DNI	Α	К	В	С	D	E	F	G	Н	L	Monophase	Monophase
RN-150M	2"	1,5"	615	80	215	310	160	275	320	292	245	355	11,650	14,000
RN-300M	2"	2"	730	80	205	310	160	275	320	292	245	355	17.400	19.050

SUCTION PIPE DIMENSIONS

PUMP TYPE	RN-150M	RN-300M
SUCTION PIPE Ø	2,5" (Ø75 mm)	3" (Ø90 mm)

PS: It is recommended to use a conical minimize at the suction line of the pump.

We reserve our right to change all or part of the features of the articles or contents of this document, without prior notice.

Example: A 3 HP pump running at 2000 rpm saves approximately €50 per month.



2100/2400/2850 rpm

Speed controlled



Easy access lid



Wide and clear view on pre-filter lid Made of polycarbonate



Coupling compatible with d50 Fitvalf ball valve handle



Stainless steel motor shaft



ISAVER - Pool Pump Frequency Inverter


"New Inverter Technology"






GEMAS "ISAVER" is the first "Touch Screen" frequency-inverter manufactured in the pool industry. By adjusting the running speed of the pool pump, it provides significant energy savings and operates silently. Additionally, it allows for automatic operation adjustment with different cycles within four time intervals throughout the day. The screen displays power consumption values corresponding to the set revolutions. It also offers the ability to adjust the speed during operation. Different models of the device are available for three-phase and single-phase motors (refer to the table for details). Max. capacity is 2,2 kW. The device includes dry contacts for various types of external controls. **PROVIDES SUBSTANTIAL ENERGY SAVINGS.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• ISAVER 1100	0111INV1100	1		
• ISAVER 1100C	0111INV1100C	1		
• ISAVER 2200	0111INV2200	1		
• ISAVER 2200C	0111INV2200C	1		





TECHNICAL SPECIFICATIONS

MODEL	ISAVER 1100	ISAVER 2200	ISAVER 1100C	ISAVER 2200C						
Operating Temp.	-10 ~ 40°C	-10 ~ 40°C	-10 ~ 40°C	-10 ~ 40°C						
Input Power	1ph AC	1ph AC	1ph AC	1ph AC						
Input Voltage	220V~240V	220V~240V	220V~240V	220V~240V						
Frequency	50 Hz	50 Hz	50 Hz	50 Hz						
Output Voltage	Mono, 0~240V	Mono, 0~240V	Tri, 0~240V	Tri, 0~240V						
Output Power	Max 1.1kW	Max 2.2kW	Max 1.1kW	Max 2.2kW						
Output Current	Max 6A	Max 12A	Max 4.5A	Max 8A						
Pump Type	Monophase	Monophase	Triphase	Triphase						
Speed Range	1200 ~ 2900 rpm									

GEMAS

2850 rpm

Self-priming Pumps

GEMAS "PUMPEX 2010"

Self-priming, thermoplastic body monoblock pool pump, complete with a pre-filter. Suction size is 1,5", and discharge size is 2", both suction and discharge sizes are 2" on larger models.

The connections are made with unions. The pump has an easy-opening lid with a 40° rotation. An optional "Xylex" lid is available for protection against aggressive chemicals. Larger basket.

2850 rpm - IP55 Motor. The pump shaft is made of stainless steel.





Wide and clear view on pre-filter lid Made of polycarbonate



Large volume basket





Stainless steel motor shaft




Noryl impeller

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• PUMPEX-50M 0,50 HP, Monophase	0111PX50M	1	18,120	0,096
• PUMPEX-75M 0,75 HP, Monophase	0111PX75M	1	20,320	0,096
• PUMPEX-75T 0,75 HP, Triphase	0111PX75T	1	19,120	0,096
• PUMPEX-100M 1 HP, Monophase	0111PX100M	1	20,320	0,096
• PUMPEX-100T 1 HP, Triphase	0111PX100T	1	19,120	0,096
• PUMPEX-150M 1,5 HP, Monophase	0111PX150M	1	20,120	0,096
• PUMPEX-150T 1,5 HP, Triphase	0111PX150T	1	21,120	0,096
• PUMPEX-200M 2 HP, Monophase	0111PX200M	1	25,120	0,096
• PUMPEX-200T 2 HP, Triphase	0111PX200T	1	23,120	0,096
• PUMPEX-300M 3 HP, Monophase	0111PX300M	1	26,120	0,096
• PUMPEX-300T 3 HP, Triphase	0111PX300T	1	26,120	0,096







			AMPERES		HEAD mwh									
PUMP TYPE	HP	DEN- SER	l 11	II III		8	10	12	14	15	16	18	20	
		(μF)	220 V											
PX-50M	0,50	13	2,60	-	-	11,14	7,25	-	-	-	-	-		
PX-75T/M	0,75	20	3,80	3,70	-	15,33	12,64	10,00	-	-	-	-	-	
PX-100T/M	1	25	4,95	3,11	1,80	19,43	17,00	14,84	11,00	8,89	-	-	-	
PX-150T/M	1,5	30	7,80	4,41	2,55	21,65	19,47	17,12	14,57	13,30	11,36	-	-	
PX-200T/M	2	40	9,90	5,88	3,40	24,80	22,90	20,90	18,40	17,50	16,40	13,60	9,60	
PX-300T/M	3	40	-	8,00	4,90	32,00	30,00	28,00	26,00	25,00	23,50	21,00	17,00	

PUMP TYPE						DIN	/IENSI	ONS							Net Weight (Kg)		Weight (g)
TOWN THE	DNA	DNI	Α	В	С	D	Е	F	G	Ι	Н	J	K	Mo.	Tri.	Mo.	Tri.
PX-50M	2"	2"	730	375	295	384	185	355	390	490	292	315	225	16,500	-	18,120	-
PX-75T/M	2"	2"	730	375	295	384	185	355	390	490	292	315	225	17,420	-	20,320	19,120
PX-100T/M	2"	2"	730	375	295	384	185	355	390	490	292	315	225	18,620	17,420	20,320	19,120
PX-150T/M	2"	2"	750	395	295	384	185	355	390	490	292	315	225	18,520	19,420	20,120	21,120
PX-200T/M	2"	2"	750	395	295	384	185	355	390	490	292	315	225	23,420	21,420	25,120	23,120
PX-300T/M	2"	2"	750	395	295	384	185	355	390	490	292	315	225	24,120	24,420	26,120	26,120

SUCTION PIPE DIMENSIONS

PUMP TYPE	PX-75T/M	PX-100T/M	PX-150T/M	PX-200T/M	PX-300T/M
SUCTION PIPE Ø	1,5" (Ø50 mm)	2" (Ø63 mm)	2" (Ø63 mm)	2,5" (Ø75 mm	3" (Ø90 mm)

PS: It is recommended to use a conical reducer at the suction line of the pump.



2850 rpm

Self-priming Pumps

GEMAS "STREAMER MICRO"

Self-priming, thermoplastic body monoblock pool pump; complete with pre-filter. Both suction and discharge sizes are 1,5". Connections are made with unions. 2850 rpm - IP55 Motor.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• STR-250MIC 0,33 HP, Monophase	0111STRMIC30	1	11,880	0,051
•STR-370MIC 0,5 HP, Monophase	0111STRMIC40	1	12,850	0,051

		CONDENSER	AMPERES				HEAD mwh				
PUMP TYPE HP	(μF)		6	7	8	9	10	13	14		
		V ,	220 V	FLOW m ³ /h							
STR-250MIC	0,33	-	1,20	5,70	5,10	4,30	3,50	1,50	-	-	
STR-370MIC	0,50	-	2,20	7,50	7,00	6,50	5,90	5,20	2,10	-	




With union connection


GEMAS "PUMPEX-JET".


Counter current pump. Suction size is 2", discharge size is 1,5". Connections are made with unions. The pump shaft is made of stainless steel. IP55 motor.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• PUMPEXJ-50M 0,50 HP, Monophase	0111PXJ50M	1	16,000	0,066
• PUMPEXJ-75M 0,75 HP, Monophase	0111PXJ75M	1	17,000	0,066
• PUMPEXJ-75T 0,75 HP, Triphase	0111PXJ75T	1	16,000	0,066
• PUMPEXJ-100M 1 HP, Monophase	0111PXJ100M	1	17,000	0,066
• PUMPEXJ-100T 1 HP, Triphase	0111PXJ100T	1	16,000	0,066
• PUMPEXJ-150M 1,5 HP, Monophase	0111PXJ150M	1	17,000	0,066
• PUMPEXJ-150T 1,5 HP, Triphase	0111PXJ150T	1	18,000	0,066
• PUMPEXJ-200M 2 HP, Monophase	0111PXJ200M	1	22,000	0,066
• PUMPEXJ-200T 2 HP, Triphase	0111PXJ200T	1	21,000	0,066
• PUMPEXJ-300M 3 HP, Monophase	0111PXJ300M	1	22,000	0,066
• PUMPEXJ-300T 3 HP, Triphase	0111PXJ300T	1	21,000	0,066









		CON-	l A	MPERES	3				HEAD) mwh			
PUMP TYPE	HP	DEN- SER	'	<u>-</u>		8	10	12	14	15	16	18	20
		(μF)	220 V		380 V				FLOW	m³/h			
PXJ-50M	0,50	13	2,60	-	-	11,14	7,25	-	-	-	-	-	-
PXJ-75T/M	0,75	20	3,80	3,70	-	15,33	12,64	10,00	-	-	-	-	-
PXJ-100T/M	1	25	4,95	3,11	1,80	19,43	17,00	14,84	11,00	8,89	-	-	-
PXJ-150T/M	1,5	30	7,80	4,41	2,55	21,65	19,47	17,12	14,57	13,30	11,36	-	-
PXJ-200T/M	2	40	9,90	5,88	3,40	24,80	22,90	20,90	18,40	17,50	16,40	13,60	9,60
PX-300T/M	3	40	-	8,00	4,90	32,00	30,00	28,00	26,00	25,00	23,50	21,00	17,00

PUMP TYPE		DIMENSIONS								/eight g)	Gross Weight (Kg)	
	DNA	DNI	Α	В	С	D	Е	F	Mo.	Tri.	Mo.	Tri.
PXJ-50M	2"	2"	470	375	185	185	460	315	16,500	-	18,120	-
PXJ-75T/M	2"	2"	470	375	185	185	460	315	17,420	-	20,320	19,120
PXJ-100T/M	2"	2"	470	375	185	185	460	315	18,620	17,420	20,320	19,120
PXJ-150T/M	2"	2"	490	395	185	185	460	315	18,520	19,420	20,120	21,120
PXJ-200T/M	2"	2"	490	395	185	185	460	315	23,420	21,420	25,120	23,120
PXJ-300T/M	2"	2"	490	395	185	185	460	315	24,120	24,420	26,120	26,120

TYPE	Packing Dimentions (mm)
PXJ - 50 / 75 / 100 / 150 / 200 / 300	560 x 360 x 400



Cross section of impeller system

Self-priming Pool Pumps

GEMAS "FLOODER"

Self-priming, thermoplastic body commercial pool pump; complete with a 20 I pre-filter. Both suction and discharge sizes are 4" (Ø110). Connections are made with slip unions. The pump shaft is made of stainless steel 2850 rpm - IP55 Motor.





Stainless steel motor shaft


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3 HP, Monophase, FLO 300M	0111FL030M	1	33,250	
•3 HP, Triphase, FLO 300T	0111FL030	1	32,250	
•3,5 HP, Monophase, FLO 350M	0111FL035M	1	33,250	
•3,5 HP, Triphase, FLO 350T	0111FL035	1	32,250	
•4,5 HP, Triphase, FLO 450T	0111FL045	1	35,350	
•5,5 HP, Triphase, FLO 550T	0111FL055	1	42,100	
•7,5 HP, Triphase, FLO 750T	0111FL075	1	49,950	
•10 HP, Triphase, FLO 1000T	0111FL0100	1	56,100	
•12,5 HP, Triphase, FLO 1250T	0111FL0125	1	56,100	

PS: * All models could be coupled with larger capacity pre-filters upon request.

** In cases of high pressure due to pool depth, a polyester pre-filter is recommended. Please refer to stock code 013209 - FR Polyester Pre-filter.



Noryl impeller





d.110 slip connection

	CONDEN- AMPERES				HEAD mwh								
PUMP TYPE	HP	SER	II	II		6	8	10	12	14	16	17	
		(μF)	220 V	230 V	230 V 380 V		FLOW m³/h						
0111FL030	3,0	-	-	10,40	6,00	65,00	56,50	47,00	25,00	-	-	-	
0111FL035	3,5	-	-	10,40	6,00	86,00	78,00	70,00	60,00	45,00	12,00	-	
0111FL045	4,5	-	-	11,70	6,75	94,00	88,00	78,00	68,00	55,00	24,00	-	
0111FL055	5,5	-	-	13,80	8,00	102,00	95,00	88,00	78,00	60,00	40,00	23,00	

CONDEN- AMPERES								H	IEAD mw	h				
PUMP TYPE	HP	SER		III		8	10	12	14	16	18	20	24	25
		(μF)	230 V	400 V	700 V				FI	OW m ³ /h	n			
0111FL075	7,5	-	-	12,10	7,00	140,00	131,00	110,00	76,00	53,00	25,00	-	-	-
0111FL0100	10,0	-	-	15,80	9,20	145,00	140,00	126,00	108,00	75,00	50,00	18,00	-	-
0111FL0125	12,5	-	-	15,80	9,20	150,00	144,00	134,30	120,00	113,00	104,00	92,70	56,80	-

PUMP TYPE		DIMENSIONS										Net Weight	Gross Weight			
	DNA	DNI	Α	K	В	С	D	Е	F	G	Н	L	M	N	(Kg)	(Kg)
0111FL030	4"	4"	890	265	415	580	400	573	485	358	210	550	467	113	30,750	32,250
0111FL035	4"	4"	890	265	415	580	400	573	485	358	210	550	467	113	30,750	32,250
0111FL045	4"	4"	890	265	415	580	400	573	485	358	210	550	467	113	33,850	35,350
0111FL055	4"	4"	910	265	415	580	420	573	485	358	210	550	467	113	40,600	42,100
0111FL075	4"	4"	910	265	415	580	420	573	485	358	210	550	467	113	48,450	49,950
0111FL0100	4"	4"	930	265	415	580	440	573	485	358	210	550	467	113	54,600	56,100
0111FL0125	4"	4"	930	265	415	580	440	573	485	358	210	550	467	113		

SUCTION PIPE DIMENSIONS

PUMP TYPE	0111FL030	0111FL035	0111FL045	0111FL055	0111FL075	0111FL0100	0111FL0125
SUCTION PIPE Ø	41/2"(Ø125 mm)	5"(Ø140 mm)	5"(Ø140 mm)	6"(Ø160 mm)	7"(Ø200 mm)	7"(Ø200 mm)	7"(Ø200 mm)

Note: We recommend using conical reducers at the pump suction point when reducing from the above pipe diameters down to 4" (110 mm).





Self-priming Pool Pumps


GEMAS "FLOODER"

Self-priming, thermoplastic body Commercial Pool Pump; complete with 20 I pre-filter. Suction and Discharge 4" (Ø110). Connections are with slip unions. Pump shaft in stainless steel. 1450 rpm - IP55 Motor.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•5,5 HP, Triphase, FLOS550T	0111FL0S55	1	42,100	0,213
•7,5 HP, Triphase, FLOS750T	0111FL0S75	1	49,950	0,213
•10 HP, Triphase, FLOS1000T	0111FL0S100	1	56,100	0,213
•12,5 HP, Triphase, FLOS1250T	0111FL0S125	1	56,100	0,213



^{**} In cases of High Pressure due to pool depth, a polyester pre-filter is preferred. See stock code 013209 - FR Polyester pre-filter.



		CONDEN-		AMPERES					HEAD mwh			
PUMP TYPE	HP	SER	II	II		6	8	10	12	14	16	17
		(μF)	220 V	220 V	380 V				FLOW m ³ /h			
0111FL0S55	5,5	-	-			-	105,00	90,00	70,00	45,00	15,00	-

		CONDEN-		AMPERES					Н	EAD mwh	1			
PUMP TYPE	HP	SER		III		8	10	11	12	13	14	16	18	19
		(μF)	230 V	400 V	700 V				FL	OW m3/h	1			
0111FL0S75	7,5	-	-			120,00	107,00	100,00	90,00	80,00	66,00	43,00	25,00	10,00
0111FL0S100	10,0	-	-			135,00	120,00	110,00	103,00	97,00	83,00	60,00	35,00	20,00
0111FL0S125	12,5	-	-			140,00	123,00		110,00		85,00	65,00	35,00	18,00

PUMP TYPE						ı	1 M I C	NSION	N S						Net Weight	Gross Weight
	DNA	DNI	Α	K	В	С	D	Е	F	G	Н	L	М	N	(Kg)	(Kg)
0111FL0S55	4"	4"	910	265	415	580	420	573	485	358	210	550	467	113	40,600	42,100
0111FL0S75	4"	4"	910	265	415	580	420	573	485	358	210	550	467	113	48,450	49,950
0111FL0S100	4"	4"	935	265	415	580	440	573	485	358	210	550	467	113	54,600	56,100
0111FL0S125	4"	4"	935	265	415	580	440	573	485	358	210	550	467	113	54.600	56.100

SUCTION PIPE DIMENSIONS

PUMP TYPE	0111FL0S55	0111FL0S75	0111FL0S100	0111FL0S125
SUCTION PIPE Ø	6"(Ø160 mm)	7"(Ø200 mm)	7"(Ø200 mm)	7"(Ø200 mm)

Note: We recommend using conical reductions at the pump suction point if reducing from the above pipe diameters down to 4" (110 mm).



Stainless steel motor shaft



Noryl impeller



d.110 slip connection

Self-priming Pool Pumps

GEMAS "FLOODER JET"
Self-priming, thermoplastic
body Jet Pump. Suction and Discharge 4" (Ø110).
Connections are with slip union. 2850 rpm - IP55
Motor. Pump shaft in stainless steel.






Stainless steel motor shaft

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•3 HP, Monophase, FLJ 300M	0111FLJ30M	1	27,000	0,150
•3 HP, Triphase, FLJ 300T	0111FLJ30	1	26,000	0,150
•3,5 HP, Monophase, FLJ 350M	0111FLJ35M	1	27,000	0,150
•3,5 HP, Triphase, FLJ 350T	0111FLJ35	1	26,000	0,150
•4,5 HP, Triphase, FLJ 450T	0111FLJ45	1	29,900	0,150
•5,5 HP, Triphase, FLJ 550T	0111FLJ55	1	37,300	0,150
•7,5 HP, Triphase, FLJ 750T	0111FLJ75	1	45,250	0,150
•10 HP, Triphase, FLJ 1000T	0111FLJ100	1	51,400	0,150
•12,5 HP, Triphase, FLJ 1250T	0111FLJ125	1	51,400	0,150

PS: All models can be produced with Ø125 or Ø110 mm suction connection.



Noryl impeller



		CONDEN-		AMPERES					HEAD mwh			
PUMP TYPE	HP	SER	II	II		6	8	10	12	14	16	17
		(μF)	220 V	220 V	380 V				FLOW m ³ /h			
0111FLJ30	3,0	-	-			65,00	56,50	47,00	25,00			
0111FLJ35	3,5	-	-	10,40	6,00	86,00	78,00	70,00	60,00	45,00	12,00	-
0111FLJ45	4,5	-	-	11,70	6,75	94,00	88,00	78,00	68,00	55,00	24,00	-
0111FLJ55	5,5	-	-	13,80	8,00	102,00	95,00	88,00	78,00	68,00	50,00	28,00

		CONDEN-		AMPERES					H	IEAD mw	h			
PUMP TYPE	HP	SER		III		8	10	11	12	13	14	16	18	21
		(μF)	230 V	400 V	700 V				Fl	OW m ³ /h	1			
0111FLJ75	7,5	-	-	12,10	7,00	121,00	112,00	107,00	101,00	96,00	87,00	65,50	42,50	-
0111FLJ100	10,0	-	-	15,80	9,20	145,00	136,60	130,00	123,00	113,00	101,50	78,50	49,50	-
0111FLJ125				15,80	9,20	150,00	144,00		134,30		120,00	113,00	104,00	

PUMP TYPE					DIMENS	ONS					Net Weight	Gross Weight
	DNA	DNI	Α	В	D	Е	F	G	Н	L	(Kg)	(Kg)
0111FLJ30	4"	4"	600	268	395	293	205	358	210	550	25,750	27,000
0111FLJ35	4"	4"	600	268	395	293	205	358	210	550	25,750	27,000
0111FLJ45	4"	4"	600	268	395	293	205	358	210	550	28,650	29,900
0111FLJ55	4"	4"	620	268	415	293	205	358	210	550	36,050	37,300
0111FLJ75	4"	4"	620	268	415	293	205	358	210	550	44,000	45,250
0111FLJ100	4"	4"	640	268	435	293	205	358	210	550	50,150	51,400
0111FLJ125	4"	4"	640	268	435	293	205	358	210	550		

SUCTION PIPE DIMENSIONS

PUMP TYPE	0111FLJ35	0111FLJ45	0111FLJ5 5	0111FLJ7 5	0111FLJ1 0 0	0111FLJ1 2 5
SUCTION PIPE Ø	5"(Ø140 mm)	5"(Ø140 mm)	6"(Ø160 mm)	7"(Ø200 mm)	7"(Ø200 mm)	7"(Ø200 mm)

Note: We recommend using conical reductions at the pump suction point if reducing from the above pipe diameters down to 4" (110 mm).



1450 rpm





Self-priming Pool Pumps

GEMAS "FLOODER JET"


Self-priming, thermoplastic
body Jet Pump. Suction and Discharge 4" (Ø110).


Connections are with slip union. 1450 rpm - IP55 Motor.


Pump shaft in stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•5,5 HP, Triphase, FLJS 550T	0111FLJS55	1	37,300	0,150
•7,5 HP, Triphase, FLJS 750T	0111FLJS75	1	45,250	0,150
•10 HP,Triphase, FLJS 1000T	0111FLJS100	1	51,400	0,150
•12,5 HP, Triphase, FLJS 1250T	0111FLJS125	1	51,400	0,150

PS: All models can be produced with Ø125 or Ø110 mm suction connection.







		CONDEN-		AMPERES					HEAD mwh			
PUMP TYPE	HP	SER	II	II	I	6	8	10	12	14	16	17
		(μF)	220 V	220 V	380 V				FLOW m ³ /h			
0111FLJS55	5,5	-	-			-	105,00	90,00	70,00	45,00	15,00	-

		CONDEN-		AMPERES					Н	IEAD mw	h			
PUMP TYPE	HP	SER		III		8	10	11	12	13	14	16	18	19
		(μF)	230 V	400 V	700 V				FL	OW m ³ /h	1			
0111FLJS75	7,5	-	-			120,00	107,00	100,00	90,00	80,00	66,00	43,00	25,00	10,00
0111FLJS100	10,0	-	-			135,00	120,00	110,00	103,00	97,00	83,00	60,00	35,00	20,00
0111FLJS125	12,5	-	-			140,00	123,00	-	110,00	-	85,00	65,00	35,00	18,00

PUMP TYPE		DIMENSIONS										Gross Weight
	DNA	DNI	Α	В	D	E	F	G	Н	L	Weight (Kg)	(Kg)
0111FLJS55	4"	4"	665	268	460	293	205	358	210	550	36,050	37,300
0111FLJS75	4"	4"	665	268	460	293	205	358	210	550	44,000	45,250
0111FLJS100	4"	4"	705	268	500	293	205	358	210	550	50,150	51,400
0111FLJS125	4"	4"	705	268	500	293	205	358	210	550	50,150	51,400

SUCTION PIPE DIMENSIONS

000110111111111111111111111111111111111	IIIIEIIOIOIIO			
PUMP TYPE	0111FLJS5 5	0111FLJS7 5	0111FLJS1 0 0	0111FLJS1 2 5
SUCTION PIPE Ø	6"(Ø160 mm)	7"(Ø200 mm)	7"(Ø200 mm)	7"(Ø200 mm)


Note: We recommend using conical reductions at the pump suction point if reducing from the above pipe diameters down to 4" (110 mm).



Stainless steel motor shaft



Noryl impeller



Self-priming Pool Pumps


GEMAS "MEGA FLOODER"

Self-priming, thermoplastic body Commercial Pool Pump; WITHOUT pre-filter. Pump shaft in stainless steel. 2850 rpm - IP55 Motor.



Stainless steel motor shaft







Note: Please refer to the "Pump pre-filters (Strainers)" section for pre-filter options and prices.



Special polyester base for heavy-duty applications







013331

		CON-	AN	/IPERE	S								HEAD	mwh							
PUMP TYPE	HP	DEN- SER	Ш	- 1	II	10	12	14	16	18	20	22	24	26	28	31	32	33	34	37	41
		(μF)	220V	220V	380V								FLOW	m³/h							
0111MFL0125	12,5	-	-	-	-	150,00	141,00	127,00	116,50	101,00	87,00	65,00	37,50		-		-		-		-
0111MFL0150	15,0	-	-	-	-	152,00	151,00	144,00	136,00	130,00	118,00	108,00	88,00	60,00			-				-
0111MFL0200	20,0	-	-	-	-	169,00	165,00	161,00	155,00	150,00	140,00	134,00	124,00	114,00	92,00	36,00	-				-
0111MFL0151	15,0	-	-	-	-	160,00	153,00	144,00	138,00	128,00	124,00	110,00	104,00	93,00	74,00	49,00	39,00	31,00	22,50		-
0111MFL0201	20,0	-	-	1	-	197,00	185,00	183,00	177,00	167,00	160,00	151,00	143,00	134,00	123,00	100,00	90,00	86,00	78,00	56,00	18,00

PUMP TYPE		DIMENSIONS										Net Weight (Kg)		Gross Weight (Kg)	
	DNA	DNI	Α	В	С	D	E	F	G	Н	L	Mo.	Tri.	Mo.	Tri.
0111MFL0125															
0111MFL0150	5"	5"	700	280	-	540	260	160	360	420	252	-	139	-	153
0111MFL0200	5"	5"	700	280	-	640	260	160	360	420	252	-	170	-	187
0111MFL0151	5"	5"	700	280	-	540	260	160	360	420	252	-	139	-	153
0111MFL0201	5"	5"	700	280	-	640	260	160	360	420	252	-	170	-	187



Polyester laminated pre-filter (optional)

SUCTION PIPE DIMENSIONS

SUCTION PIPE Ø	8"(Ø225 mm)	8"(Ø225 mm)	8"(Ø225 mm)
			0111MFL0200

SUCTION PIPE Ø 8"(Ø225 mm) 8"(Ø225 mm)

- Locking nut Transparent lid
- 2-3-4-5-6-7-8-9-
- O-ring Pre-filter basket Pre-filter body
- Gasket for drain
- Drain plug Connection screws
- Body gasket
- 10- Body o-ring












Cast Iron Pool Pumps

GEMAS "PUMPEX CAST IRON POOL PUMPS"

Cast iron body with mechanical seal and triphase motor. Shaft in Inox 420. 1450 rpm. Body for 10 bar pressure. In conformity with DIN 24255. Pre-filter not included in the price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•GNM 80-250. 70 m³/h -	011212P	1		
16 mwh - 7,5 HP (5,5 kw) 4"- 3" Disc	charge - Ø 225 Fan.			
•GNM 100-250. 100 m³/h -	011222P	1		
16 mwh - 10 HP (7,5 kw) 5"- 4" Disc	harge - Ø 232 Fan.			
•GNM 100-250. 150 m³/h -	011223P	1		
16 mwh - 15 HP (11 kw) 5"- 4" Disch	narge - Ø 252 Fan.			
•GNM 125-250. 230 m³/h -	011231P	1		
16 mwh - 20 HP (15 kw) 6"- 5" Disch	narge - Ø 238 Fan.			

Note: 1- The pumps listed are produced upon request, with a lead time of approximately 7-15 days. Please inquire about the prices for capacities that are not included in the list.
2- Pumps with a bronze fan and stainless steel shaft are available at a 30% higher price."



Pump Bases and Vibration Bricks

Pump Bases and Vibration Mounts The pump base is made of AISI 304 grade stainless steel and is specifically designed for pumps with a maximum power of 3 HP.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Single	01411	1	4,330	0,030
• Double	01412	1	8,320	0,040

FR Polyester Pump Base. Can be used for all Streamer and Flooder models up to 10 HP. 375 x 250 x 190 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Single	01413	1		

Vibration mount Installed to minimize pump vibration.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•M8, Ø30 - 25 mm	0111STS10	1		
•M10, Ø50 - 35 mm	0111STS21	1		









Pump Pre-Filters (Strainers)



Stainless Steel pre-filters

AISI 304 Quality Stainless Steel pre-filter. Lid with washer and nuts. Connections with Loose Flange.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•5"	01312	1	15,000	
•6"	01313	1	17,350	
•8"	01314	1	19,450	

01312

Plastic pre-filters

Fiberglass Reinforced PP Body. 20 I and 40 I capacity. PP basket. Polycarbonate transparent lid.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•4" - Unions	013311	1	9,740	
• 5" - Flanged	013321	1	10,750	
• Stainless Steel Pre-filter	0111FL01	1		
Basket AISI 304 Quality				
•6" - Flanged - 40 l	013331	1	25,300	







013331

013321



FR Polyester pre-filters

Fiberglass reinforced polyester body pre-filter. Plastic pre-filter basket, transparent acrylic lid, loose flange.

Description	Code	Pieces/ Weig box Kg	ht Volume m ³
• 4"-4,5" Suitable for Flooder Pump	013209	1	
• 4"	013210	1	
•6"	013323	1	

Pump Pre-Filters (Strainers)

Fiberglass reinforced polyester pre-filter. Loose flange connection and **65** I capacity. Pipe connections can be produced according to demand. Stainless steel basket. Transparent acrylic lid. Can be used up to 225 mm connections.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 4"	013215	1	31,500	0,340
• 5"	013216	1	31,500	0,340
•6"	013223	1	31,500	0,340
•8"	013229	1		





Fiber glass reinforced polyester pre-filter. Loose flange connection. Ø280, Ø315 and Ø355 has **125 I** Ø400 and Ø450 has **285 I** capacity. AISI 304 quality stainless steel basket. Transparent acrylic lid. Can be used up to 225 mm connections.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•8"- Ø280	013224	1		
•8"- Ø315	013225	1		
•8"- Ø355	013226	1		
•8"- Ø400	013227	1		
•8"- Ø450	013228	1		









PRE-FILTER TYPE	Code	DIMENSIONS								
		А	В	С	D	E	F	G	Н	
Ø225 - Ø280	013224	1098	520	400	635	Ø280	582	Ø225	983	
Ø225 - Ø315	013225	1098	520	400	635	Ø315	582	Ø225	983	
Ø225 - Ø355	013226	1098	520	400	635	Ø355	582	Ø225	983	
Ø225 - Ø400	013227	1373	680	553	864	Ø400	788	Ø225	1220	
Ø225 - Ø450	013228	1373	680	553	864	Ø400	788	Ø225	1220	







Submersible Pumps




QP550C ~ QP750C Model:

IPX8, plastic body, mechanical seal, automatic reset thermal protected motor, submersible pump suitable for clean and dirty water discharge with impeller suitable for maximum 5 mm grain size for dirty water discharge. It has vertical electronic factor against floater malfunction in the drain pit. 10 m cable. Max. water temperature is 35°C, ambient temperature is 40°C.

Description	Code	Pieces/ Wei box K	ght Volume g m ³
•QP550C	013172	1 6,0	00 0,050
•QP750C	013173	1 7,0	00 0,050

PUMP	Power In		Max.	Max.	Max.	Max.	Cable Length			HEAD	mwh		
TYPE	(W)		Pressure		Water Depth	Grain Size	(m)	1	2	4	6	7	9
			(M)	(L/H)	(m)					FLOW	m³/h		
QP550C	550	11/4"	8.0	11000	7	5 mm	H05RN-F3G 1.0 mm 2x10 m	8	7	5	4	3	2
QP750C	750	11/4"	8.5	12500	7	5 mm	H07RN-F3G 1.0 mm 2x10 m	10	9	7	6	5	3




QP550 DW ~ QP750 DW Model:

IPX8, plastic body, mechanical seal, automatic reset thermal protected motor, submersible pump suitable for clean and dirty water discharge with impeller suitable for maximum 35 mm grain size for dirty water discharge. It has vertical electronic factor against floater malfunction in the drain pit. 10 m cable. Max. water temperature is 35°C, ambient temperature is 40°C.

Description	Code	Pieces/ Weight Volume box Kg m³
•QP550DW	013191	1 6,000 0,050
•QP750DW	013192	1 7,000 0,050

PUMP	Power	Inch	Max.	Max.	Max.	Max.	Cable Length	HEAD mwh					
TYPE	(W)		Pressure	Flow	Water Depth	Grain Size	(m)	1	2	4	6	7	9
			(M)	(L/H)	(m)					FLOW	m³/h		
QP550DW	550	11/4"	6.5	10000	7	35 mm	H05RN-F3G 1.0 mm 2x10 m	8	7	5	4	3	2
QP750DW	750	11/4"	7.5	13000	7	35 mm	H07RN-F3G 1.0 mm 2x10 m	10	9	7	6	5	3







"Seljuk" BL High Rate Sand Filter

GEMAS "Seljuk" It is produced from high quality PP material with plastic injection molding technology. The upper and lower parts are joined using a special welding technique. Complete with transparent lid, multiport valve, fittings, pressure gauge and air vent. 2-year warranty. Test pressure 3,5 kg/cm², Maximum working pressure 2.5 kg/cm², Maximum filtration rate 50 m³/h/m².





Environment friendly






Folding collector arms



021131T

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø500 1,5" multi. side valve	021131	1	12,000	0,215
• Ø630 1,5" multi. side valve	021132	1	13,350	0,325
• Ø710 2" multi. side valve	021133	1	18,500	0,440
• Ø900 2" multi. side valve	021134	1		
•Ø500 1,5" multi. top valve	021131T	1	11,514	0,215
• Ø630 1,5" multi. top valve	021132T	1	13,350	0,325
•Ø710 2" multi. top valve	021133T	1	18,500	0,440
• Ø900 2" multi. top valve	021134T	1		





		17 (14)		10111					
	MODEL	021131	021132	021133	021134	021131T	021132T	021133T	021134T
	D (mm)	500	630	710	900	500	630	710	900
	H ₁ (mm)	765	850	920	990	845	930	1030	1100
	H ₂ (mm)	-	-	-	-	-	-	-	-
<u>/</u>	H ₃ (mm)	665	750	820	890	665	750	820	890
	H ₄ (mm)	430	475	510	550	-	-	-	-
	H ₅ (mm)	300	345	360	400	-	-	-	-
	W (mm)	260	260	295	295	-	-	-	-
,	CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	1,5"	1,5"	2"	2"
)	FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	32 26 19	10 8 6	16 12 9	20 16 12	32 26 19
	SAND (Kg)	100	150	250	450	100	150	250	450
	NET WEIGHT (Kg)	12.000	13.350	18.500	-	12.000	13.350	18.500	-









"Seljuk" ACRYL BL High Rate Sand Filter

GEMAS "Seljuk" ACRYL BL is made of high quality PP plastic by injection molding technology and coated with acrylic which provides an eye-catching glossy surface finish. Complete with transparent lid, multiport valve, fittings, pressure gauge and air vent.

2-year warranty.

Test pressure 3,5 kg/cm², Maximum working pressure 2.5 kg/cm², Maximum filtration rate 50 m³/h/m².



Transparent bolted lid (Patented)

Code	Pieces/ box	Weight Kg	Volume m ³
021131A	1	12,000	0,215
021132A	1	13,350	0,325
021133A	1	18,500	0,440
021134A	1		
021131TA	1	11,514	0,215
021132TA	1	13,350	0,325
021133TA	1	18,500	0,440
021134TA	1		
	021131A 021132A 021133A 021134A 021131TA 021132TA 021133TA	Code box 021131A 1 021132A 1 021133A 1 021134A 1 021131TA 1 021132TA 1 021133TA 1	Code box Kg 021131A 1 12,000 021132A 1 13,350 021133A 1 18,500 021134A 1 1,514 021131TA 1 13,350 021132TA 1 18,500







MODEL	021131A	021132A	021133A	021134A	021131TA	021132TA	021133TA	021134TA
D (mm)	500	630	710	900	500	630	710	900
H ₁ (mm)	785	870	940	990	845	930	1030	1100
H ₂ (mm)	-	-	-	-	-	-	-	-
H ₃ (mm)	665	750	820	890	665	750	820	890
H ₄ (mm)	430	475	510	550	-	-	-	-
H ₅ (mm)	300	345	360	400	-	-	-	-
W (mm)	260	260	295	295	-	-	-	-
CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	1,5"	1,5"	2"	2"
FLOW (50 m³/h/m²) max (40 m³/h/m²) (m³/h) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	32 26 19	10 8 6	16 12 9	20 16 12	32 26 19
SAND (Kg)	100	150	250	450	100	150	250	450
NET WEIGHT (Kg)	12.000	13.350	18.500	-	12.000	13.350	18.500	-



Folding collector arms



"Injectrone" High Rate Sand Filters

GEMAS "INJECTRONE" PLASTIC SAND FILTER.

Made of Injection plastic (PP). The upper and lower parts are joined with a special welding technique. As the bed depth is higher than other filter models, the filtration quality is considerably higher. Sand water discharge openings are available at both front and rear, installed w/discharge valve. Easy to open clear threaded lid (2 cm wider than bolted lid). Complete with multiport valve, fittings, and pressure gauge. 5-years body warranty. Test pressure 3,5 kg/cm², maximum operation pressure 2,5 kg/cm², Maximum filtration rate 50 m³/h/m².





Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø500 mm	0211011	1	17,000	0,180
1,5" multiport side valve - 10 m ³ /h				
•Ø600 mm	0211012	1	27,000	0,270
1.5" multiport side valve - 14 m ³ /h				

Transparent threaded lid




Side multiport valve



Water drainage with valve



Folding collector arms



MODEL	0211011	0211012	
D (mm)	500	600	
H ₁ (mm)	960	1030	
H ₂ (mm)	-	-	
H ₃ (mm)	910	980	
H ₄ (mm)	290	320	
H ₅ (mm)	415	445	
W (mm)	260	260	
CONNECTIONS Ø (mm)	1,5"	1,5"	
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	14 11 8	
SAND (Kg)	125	170	
NET WEIGHT (Kg)	8.000	11.000	



"Fusion SL" High Rate Sand Filters

GEMAS "FUSION SL" PLASTIC SAND FILTERS.

Made of Injection Plastic (PP). The upper and lower parts are joined with a special welding technique. Easy to open clear threaded lid (2 cm wider than bolted lid). Complete with multiport valve, fittings, and pressure gauge. 2-years body warranty. Test pressure 3.5 kg/cm², maximum operation pressure 2,5 kg/cm², Maximum filtration rate 50 m³/h/m².

Description



Pieces/

box

Weight

Volume

0,200

0,325

0,200


0,325



•Ø500 mm - 10 m³/h 1,5" m. valve	0211211S	1	11,700
•Ø600 mm - 14 m³/h 1,5" m. valve	0211212S	1	15,700
•Ø500 mm - 10 m³/h 1,5" top m. valve	0211211ST	1	12,000
•Ø600 mm - 14 m³/h 1,5" top m. valve	0211212ST	1	16,000

Code







0211212ST

0211211ST

MODEL	02112115	02112125	0211211ST	0211212ST
D (mm)	500	600	500	600
H ₁ (mm)	715	760	630	660
H ₂ (mm)	-	-	-	-
H ₃ (mm)	660	705	830	860
H ₄ (mm)	260	280	-	-
H ₅ (mm)	390	410	-	-
W (mm)	260	260	-	-
CONNECTIONS Ø (mm)	1,5"	1,5"	1,5"	1,5"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	14 11 8	10 8 6	14 11 8
SAND (Kg)	75	100	<i>75</i>	100
NET WEIGHT (Kg)	7,000	14,000	7,000	14,000



Folding collector arms

Environment friendly



Rotational Plastic Body Pool Filters


"Filtrone" High Rate Sand Filters


GEMAS "FILTRONE" PLASTIC SAND FILTERS.

Filter shell made of PE Plastic by Rotational Moulding.
One-piece body, including pressure gauge, side mounted multiport valve and air purge. Optional Transparent Bolted Lid.

2-years body warranty. Test pressure 3,5 kg/cm².
Max. operation pressure 2 kg/cm². Filtration rate: 50 m³/h/m².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø560 mm - 13 m³/h 1,5" m. valve	021818	1	16,500	0,215
•Ø615 mm - 15 m³/h 1,5" m. valve	021813	1	19,500	0,325
• Ø760 mm - 23 m³/h 2" m. valve	021814	1	26,500	0,440
• Ø920 mm - 33 m³/h 2" m. valve	021815	1	37,500	0,790
•Ø560 mm - 13 m³/h 1,5" top m. valve	021826	1	14,500	0,215
•Ø615 mm - 15 m³/h 1,5" top m. valve	021823	1	19,500	0,325
•Ø760 mm - 23 m³/h 2" top m. valve	021824	1	24,500	0,440
• Ø920 mm - 33 m³/h 2" top m. valve	021825	1	35,500	0,790








MODEL	021818	021813	021814	021815	021826	021823	021824	021825
D (mm)	560	615	760	920	560	615	760	920
H ₁ (mm)	730	805	925	1085	800	875	995	1155
H ₂ (mm)	610	680	805	965	610	680	805	965
H ₃ (mm)	670	745	885	1025	-	-	-	-
H ₄ (mm)	250	270	315	390	-	-	-	-
H ₅ (mm)	420	400	465	540	-	-	-	-
W (mm)	260	260	295	295	-	-	-	-
CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	1,5"	1,5"	2"	2"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	13 10 8	15 12 9	23 18 14	33 26 20	13 10 8	15 12 9	23 18 14	33 26 20
SAND (Kg)	100	150	250	450	100	150	250	450
NET WEIGHT (Kg)	16,500	19,500	26,500	37,500	14,500	17,500	24,500	35,500



Transparent bolted lid (Optional) (Patented)







Water drainage



"Filtrone L" High Rate Sand Filters

GEMAS "FILTRONE L" PE PLASTIC SAND FILTERS.

Filter shell made of PE Plastic by Rotational Moulding. One-piece body, large lid of 40 cm width including pressure gauge, side mounted multiport valve and air purge.

2-years body warranty. Test pressure 3,5 kg/cm². Max. operation pressure 2,5 kg/cm². Filtration rate: 50 m³/h/m³.

Description

•Ø615 mm - Large lid.



Pieces/

box

Weight Kg

23,000

30,000

48,000

55,000

75,000

Volume

0,325

0,440

0,790

0,930

1,160



021815LL

•Ø760 mm - Large lid.	021814LL
2" multiport side valve - 23 m ³ /h	
•Ø920 mm - Large lid.	021815LL
2" multiport side valve - 33 m ³ /h	
•Ø1000 mm - Large lid. without	021817LL
multiport valve 2,5" - 40 m ³ /h	
•Ø1200 mm - Large lid. without	021816LL
multiport valve 3" - 57 m³/h	
	6
	Almer
	And the second

1,5" multiport side valve - 15 m³/h



021817LL

Ø 1000 Plastic Filter



Code

021813LL



Unique in the Market

TECHNICAL CHARACIERISTICS							
MODEL	021813LL	021814LL	021815LL	021817LL	021816LL		
D (mm)	615	760	920	1000	1200		
H ₁ (mm)	820	960	1110	1260	1310		
H ₂ (mm)	-	-	-	-	-		
H ₃ (mm)	760	900	1050	1200	1250		
H ₄ (mm)	280	310	375	480	475		
H ₅ (mm)	410	460	525	730	685		
W (mm)	260	295	295	480	480		
CONNECTIONS Ø (mm)	1, 5"	2"	2"	2,5"	3"		
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	15 12 9	23 18 14	33 26 20	40 32 24	57 45 34		
SAND (Kg)	125	250	450	700	1300		
NET WEIGHT (Kg)	23,000	30,000	48,000	55,000	75,000		





Easy Sand Change!

Environment friendly

"Filtrone LLT" High Rate Sand Filters

GEMAS "FILTRONE LLT" PLASTIC SAND FILTERS.

Filter shell made of PE plastic by rotational molding. Wide transparent threaded lid (400 mm inner diameter), complete with plastic opening handle, multiport valve, fittings, and pressure gauge. 2-years body warranty.

Test pressure 3,5 kg/cm², maximum operation pressure 2,5 kg/cm², Maximum filtration rate 50 m³/h/m².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø615 mm - Large lid.	021813LLT	1	25,000	0,325
1,5" multiport side valve - 15 m ³ /h				
•Ø760 mm - Large lid.	021814LLT	1	32,000	0,440
2" multiport side valve - 23 m³/h				
•Ø920 mm - Large lid.	021815LLT	1	50,000	0,790
2" multiport side valve - 33 m³/h				
•Ø1000 mm - Large lid. without	021817LLT	1	57,000	0,930
multiport valve 2,5" - 40 m ³ /h				
• Ditto, GEMAS 2,5" multiport valve	021817LTM	1	57,000	0,930
•Ø1200 mm - Large lid. without	021816LLT	1	77,000	1,160
multiport valve 3" - 57 m ³ /h				



Easy opening 40 cm wide transparent lid





MODEL	021813LLT	021814LLT	021815LLT	021817LLT	021816LLT			
D (mm)	615	760	920	1000	1200			
H ₁ (mm)	820	960	1110	1260	1280			
H ₂ (mm)	-	-	-	-	-			
H ₃ (mm)	760	900	1050	1200	1230			
H ₄ (mm)	260	350	375	480	455			
H ₅ (mm)	410	500	525	730	745			
W (mm)	260	295	295	480	480			
CONNECTIONS Ø (mm)	1, 5"	2"	2"	2,5"	3"			
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	15 12 9	23 18 14	33 26 20	40 32 24	57 45 34			
SAND (Kg)	125	250	450	700	1330			
NET WEIGHT (Kg)	25,000	32,000	50,000	57,000	77,000			



021817LLT



"Premium" High Rate Sand Filters

GEMAS "PREMIUM" PE PLASTIC SAND FILTERS.

Filter shell made of PE Plastic by Rotational Moulding. One-piece body, including pressure gauge, side or top mounted multiport valve and air purge. 2-years body warranty. Test pressure 3,5 kg/cm². Max. operation pressure 2,5 kg/cm².

Filtration rate: 50 m³/h/m².





Description	Code	Pieces/ box	Weight Kg	Volume m ³
Top mounted (clamped) multiport valve				
•Ø400 mm - 7 m³/h	021921	1	9,000	0,140
•Ø500 mm - 10 m³/h	021922	1	12,000	0,200
•Ø615 mm - 15 m³/h	021923	1	16,000	0,325
Side mounted multiport valve Including cla	mped lid & side cor	nnections		
•Ø400 mm - 7 m³/h	021911	1	8,700	0,140
•Ø500 mm - 10 m³/h	021912	1	11,700	0,200
•Ø615 mm - 15 m³/h	021913	1	15,700	0,325



Ergonomic clamped lid







Side multiport valve and Water drainage



	Top mounted multiport valve			Side mounted multiport valve		
MODEL	021921	021922	021923	021911	021912	021913
D (mm)	400	500	615	400	500	615
H ₁ (mm)	695	735	855	615	660	775
H ₂ (mm)	525	565	685	-	-	-
H ₃ (mm)	-	-	-	555	600	715
H ₄ (mm)	-	-	-	200	220	280
H₅ (mm)	-	-	-	330	350	410
W (mm)	-	-	-	260	260	260
W1 (mm)	-	-	-	-	-	-
CONNECTIONS Ø (mm)	1, 5"	1, 5"	1, 5"	1, 5"	1, 5"	1, 5"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	7 5 4	10 8 6	15 12 9	7 5 4	10 8 6	15 12 9
SAND (Kg)	80	100	150	80	100	150
NET WEIGHT (Kg)	9,000	12,000	16,000	8,700	11,700	15, 700

Folding collector arms







Deep Bed, Single / Multilayer Pool Filters

GEMAS "FILTRONE-HB" PE PLASTIC SAND FILTERS.

Filter Shell made of PE plastic by rotational moulding. One-piece body, includes pressure gauge, 1,5" side mounted multiport valve and air purge. 2-years body warranty. Collector with laterals. Test pressure 3,5 kg/cm². Max. Operation ressure 2,5 kg/m².







40 cm wide opening

Folding collector arms


Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø 560 mm, 1,5" Ç.Y. Vana	021818HB	1		
•Ø 560 mm, Large Lid,1,5" multiport valve	021818LHB	1		
10 m³/h w/single layer - 13 m³/h w/multilayer				
•Ø 615 mm Large Lid, 15 m³/h	021813LH	1	04.000	0.444
Medium deep - 1,5" multiport side valve			31,000	0,444
•Ø 615 mm - 1,5" multiport valve	021813HB	1	05.000	0.504
•Ø 615 mm - 1,5" multiport valve	021813LHB	1	35,200	0,584
12 m³/h w/single layer - 15 m³/h w/multilayer			55,000	0,852
•Ø 760 mm - 2" multiport valve	021814HB	1		
18 m³/h w/single layer - 23 m³/h w/multilayer				
•Ø 760 mm - 2" multiport valve	021814LHB	1		
18 m³/h w/single layer - 23 m³/h w/multilayer				
•Ø 920 mm - 2" multiport valve	021815HB	1		
26 m³/h w/single layer - 33 m³/h w/multilayer				
•Ø 920 mm - 2" multiport valve	021815LHB	1		
26 m³/h w/single layer - 33 m³/h w/multilayer				
PS: All Filtrone Models are resistant against Oz	one			



LH 도



MODEL	021818HB	021818LHB	021813LH	021813HB	021813LHB	021814HB	021814LHB	021815HB	021815LHB
D (mm)	560	560	615	615	615	760	760	920	920
H ₁ (mm)	1460	1460	1140	1510	1560	1560	1610	1610	1660
H ₃ (mm)	1410	1410	1080	1460	1500	1510	1550	1650	1600
H ₄ (mm)	600	600	280	580	580	630	630	650	650
H ₅ (mm)	730	730	410	710	710	780	780	800	800
W (mm)	260	260	260	260	260	295	295	295	295
CONNECTIONS (Ø)	1,5"	1,5"	1,5"	1,5"	1,5"	2"	2"	2"	2"
FLOW (m ³ /h) (50 m ³ /h/m ²)	13	13	15	15	15	23	23	33	33
FLOW (m³/h) (40 m³/h/m²)	10	10	12	12	12	18	18	26	26
FLOW (m ³ /h) (30 m ³ /h/m ²)	8	8	9	9	9	14	14	20	20
ANTHRACITE 0,8 - 1,6 mm (lt)	70	70		100	100	130	130	200	200
QUARTZ SAND 0,5 - 1 mm (Kg)	175	175		200	200	300	300	300	300
QUARTZ SAND 1 - 3 mm (Kg)	50	50		100	100	130	130	150	150
NET WEIGHT (Kg)			31,000	34,250	37,150				





"Turbidron-BL" Bobbin Wound Sand Filters

GEMAS "TURBIDRON BL" SAND FILTERS.

Filter shell made of ABS plastic and reinforced by fiberglass bobbin winding outside. Size Ø830 mm and above filter plastic shell is made of one piece. ROTOMOLDED PE inner shell and bobbin winding outside. Filter lid is with bolts. Complete with pressure gauge, air purge and side mounted multiport valve. Test pressure 4,0 kg/cm². Max. operation pressure 2,5 kg/cm². Filtration rate: 50 m³/h/m². 2-years body warranty.





Transparent bolted lid (Optional) (Patented)


Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø 500 mm - 10 m³/h 1,5" multiport valve	021712	1	17,000	0,215
•Ø 630 mm - 16 m³/h 1,5" multiport valve	021713	1	20,000	0,325
•Ø 710 mm - 20 m³/h 2" multiport valve	021714	1	32,000	0,440
•Ø 830 mm - 27 m³/h 2" multiport valve	021715	1	38,000	0,660
•Ø 900 mm - 32 m³/h 2" multiport valve	021716	1	47,000	0.790
•Ø 1000 mm - 40 m³/h 2,5" multiport valve	021717M	1	58,000	0,930
•Ø 1000 mm - 40 m³/h 2,5" without m.v	021717	1	58,000	0,930

PS: All models have a transparent bolted lid. Please add "LT" to the code when ordering.





•Ø 500 mm - 10 m³/h 1,5" top multiport valve	021712T	1	15,000	0,215
•Ø 630 mm - 16 m³/h 1,5" top multiport valve	021713T	1	18,000	0,325
•Ø 710 mm - 20 m³/h 2" top multiport valve	021714T	1	30,000	0,440
•Ø 830 mm - 27 m³/h 2" top multiport valve	021715T	1	36,000	0,660
•Ø 900 mm - 32 m³/h 2" top multiport valve	021716T	1	45,000	0.790



MODEL	021712	021713	021714	021715	021716	021717IM	021712T	021713T	021714T	021715T	021716T
D (mm)	500	630	710	830	900	1000	500	630	710	830	900
H ₁ (mm)	750	830	880	940	990	1050	810	890	980	1030	1080
H ₂ (mm)	630	710	770	820	870	930	630	710	770	820	870
H ₄ (mm)	300	325	350	350	400	375					
H ₅ (mm)	430	455	500	500	550	645		-			-
W (mm)	260	260	295	205	295	370					-
CONNECT. Ø (mm)	1,5"	1,5"	2"	2"	2"	2,5"	1,5"	1,5"	2"	2"	2"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	27 22 16	32 26 19	40 32 24	10 8 6	16 12 9	20 16 12	27 22 16	32 26 19
SAND (Kg)	100	150	250	350	450	700	100	150	250	350	450
NET WEIGHT (Kg)	10,200	20,000	32,000	38,000	47,000	58,000	10,000	20,000	30,000	36,000	45,000





"Turbidron-CL" Bobbin Wound Sand Filters

GEMAS "TURBIDRON CL" SIDE MOUNTED SAND FILTERS.

Clamped Lid. Made of PE plastic core, fiberglass bobbin wound.

Complete with pressure gauge, 1,5" side mounted multiport valve and air purge. Test pressure 4,0 kg/cm².

Max. Operation pressure 2,5 kg/m². Filtration rate 50 m³/h/m².

2-years body warranty.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø400 mm -1,5" side mounted multiport valve - 7 m³/h	021311B	1	7,700	0,145
•Ø500 mm -1,5" side mounted	021312B	1	9,200	0,145
multiport valve - 10 m³/h				







GEMAS "TURBIDRON CL" MOUNTED SAND FILTERS.

Made of PE plastic shell wound by fiberglass bobbin; complete with pressure gauge and multiport valve. Max. operation pressure 2,5 kg/cm 2 . Test pressure 4,0 kg/cm 2 . Filtration rate: 50 m 3 /h/m 2 . **2-years body warranty.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø400 mm -1,5" top mounted	021321B	1	8,000	0,145
multiport valve - 7 m ³ /h			9,500	0,145
•Ø500 mm -1,5" top mounted	021322B	1		
multiport valve - 10 m³/h				



		TEIRIOTTOO		
	Top mounted	multiport valve	Side mounted i	multiport valve
MODEL	021321B	021322B	021311B	021312B
D (mm)	400	500	400	500
H ₁ (mm)	815	940	670	800
H ₂ (mm)	580	705	580	705
H ₃ (mm)	-	-	610	740
H ₄ (mm)	-	-	240	300
H ₅ (mm)	-	-	385	440
W (mm)	-	-	260	260
CONNECTIONS Ø (mm)	1,5"	1,5"	1,5"	1,5"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	7 5 4	10 8 6	7 5 4	10 8 6
SAND (Kg)	80	100	80	100
NET WEIGHT (Kg)	8,000	10,500	7,700	10,200





"Turbidron-SL" Bobbin Wound Filters

Wound Filters WARRAN

GEMAS "TURBIDRON-SL" SIDE MOUNTED POOL SAND FILTERS.

Filter shell made of smooth ABS plastic that reduces algae and bacteria adhesion. Complete with Easy opening "threaded lid", large and transparent lid (diameter is 2 cm larger than bolted lid), Complete with pressure gauge and side mounted multiport valve.

OPTIONAL LIGHTING TOUCHPAD BUTTON WITH BATTERY to

observe inside the filter. Maximum Working Pressure 2,5 kg/cm².

Test Pressure 4 kg/cm². Filtration Rate 50 m³/h/m². **2-years body warranty**.






Easy opening "threaded lid"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø500 mm - 10 m³/h 1,5" m.valve	021712S	1	17,000	0,215
•Ø630 mm - 16 m³/h 1,5" m.valve	021713S	1	20,000	0,325
•Ø710 mm - 20 m³/h 2" m.valve	021714S	1	32,000	0,440
•Ø830 mm - 27 m³/h 2" m.valve	021715S	1	38,000	0,660
•Ø900 mm - 32 m³/h 2" m.valve	021716S	1	47,000	0.790
•Ø1000 mm - 40 m³/h 2,5" without m.valve.	021717S	1	58,000	0,930
•Ø1000 mm - 40 m³/h 2,5" m.valve	021717SM	1	58,000	0,930

PS: Additional €30 for lighting. Please add "L" to the code when ordering.



LED lighting transparent lid (Optional)







42

MODEL	021712S					
MODEL	0217123	021713S	021714S	021715S	021716S	021717S
D (mm)	500	630	710	830	900	1000
H ₁ (mm)	750	865	920	910	1010	1305
H ₂ (mm)	690	815	860	870	960	1245
H ₃ (mm)	610	730	780	795	875	1185
H ₄ (mm)	300	-	350	350	390	500
H ₅ (mm)	430	-	500	500	540	830
W (mm)	260	260	295	295	295	-
CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	2"	2,5"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	27 22 16	32 26 19	40 32 24
SAND (Kg)	100	150	250	350	450	700
NET WEIGHT (Kg)	17,300	20,300	32,000	38,300	47,300	58,300





"Broadex" High Rate Sand Filters

GEMAS "BROADEX" POOL SAND FILTERS.

Made of FRP. Wide transparent threaded lid (400 mm inner diameter), complete with plastic opening handle, multiport valve, fittings and pressure gauge. Test pressure 3,5 kg/cm², maximum operation pressure 2,5 kg/cm², Maximum filtration rate 50 m³/h/m².

2-years shell warranty.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø560 mm Large Lid - 1,5"	021112LLT	1	20,000	0,215
side mounted multiport valve - 13 m ³ /h				
•Ø615 mm Large Lid - 1,5"	021113LLT	1	25,000	0,325
side mounted multiport valve - 15 m ³ /h				
•Ø760 mm Large Lid - 2"	021114LLT	1	32,000	0,440
side mounted multiport valve - 23 m³/h				
•Ø830 mm Large Lid - 2"	021115LLT	1	40,000	0,660
side mounted multiport valve - 27 m ³ /h				
• Ø920 mm Large Lid - 2"	021116LLT	1	50,000	0,790
side mounted multiport valve - 33 m ³ /h				
•Ø1000 mm Large Lid	021117LLT	1	70,000	0,930
without valve, 2,5" connection - 40 m ³ /h				
•Ø1200 mm Large Lid	021216LLT	1	80,000	1,160
without valve, 3" connection - 57 m ³ /h				



Easy opening 40 cm wide transparent lid





Side multiport valve

MODEL	021112LLT	021113LLT	021114LLT	021115LLT	021116LLT	021117LLT	021216LLT
D (mm)	560	615	760	830	920	1000	1200
H ₁ (mm)	800	830	960	1030	1140	1375	1280
H_2 (mm)	-	-	-	-	-	-	-
H ₃ (mm)	740	780	900	970	1035	1325	1230
H ₄ (mm)	285	345	350	360	450	515	455
H_5 (mm)	420	475	500	510	600	845	745
W (mm)	260	260	295	295	295	480	480
CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	2"	2,5"	3"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	13 10 8	15 12 9	23 18 14	27 22 16	33 26 20	40 32 24	57 45 34
SAND (Kg)	100	125	250	350	450	725	1330
NET WEIGHT (Kg)	20,000	25,000	32,000	40,000	50,000	70,000	80,000







"Filtrex 2025" High Rate Sand Filters

GEMAS "FILTREX 2025" SAND FILTERS.

Filter Shell Made of Smooth ABS plastic laminated with FRP, outer surface is arylic. Monobloc outlook has been produced by an unique technic. Complete with pressure gauge and side mounted multiport valve. Maximum Working Pressure 2,5 kg/cm². Test Pressure 4 kg/cm². Filtration Rate 50 m³/h/m². Transparent Bolted Lid (optional). 2-year warranty.





Transparent bolted lid (Optional) (Patented)

Т	ao	va	lve

Description	Code	box	Weight Kg	volume m ³
•Ø500 mm - 1,5" multiport side valve -10 m³/h	021610	1	19,000	0,215
•Ø630 mm - 1,5" multiport side valve -16 m³/h	021611	1	23,000	0,325
• Ø710 mm - 2" multiport side valve - 20 m³/h	021612	1	35,000	0,440
• Ø900 mm - 2" multiport side valve - 32 m³/h	021613	1		
•Ø500 mm - 1,5" multiport top valve -10 m³/h	021610T	1	17,000	0,215
•Ø630 mm - 1,5" multiport top valve -16 m³/h	021611T	1	21,000	0,325
• Ø710 mm - 2" multiport top valve - 20 m³/h	021612T	1	33,000	0,440
•Ø900 mm - 2" multiport top valve - 32 m³/h	021613T	1		
PS: Please add "TI " to the code when ordering				






Couplings compatible with d50 Fitvalf ball valve handle



Side multiport valve





MODEL	021610	021611	021612	021613	021610T	021611T	021612T	021613T
D (mm)	500	630	710	900	500	630	710	900
H ₁ (mm)	750	820	890	890	820	890	960	960
H ₂ (mm)	640	710	780	780	630	710	770	770
H ₃ (mm)	700	760	840	840	-	-	-	-
H ₄ (mm)	300	325	340	340	-	-	-	-
H ₅ (mm)	430	455	490	490	-	-	-	-
W (mm)	260	260	295	295	260	260	295	295
CONNECTIONS Ø (mm)	1,5"	1,5"	2"	2"	1,5"	1,5"	2"	2"
FLOW (50 m³/h/m²) max (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	32 26 19	10 8 6	16 12 9	20 16 12	32 26 19
SAND (Kg)	100	150	250	250	100	150	250	250
NET WEIGHT (Kg)	19,000	23,000	35,000	35,000	17,000	21,000	33,000	33,000



"Monocon" Pool Sand Filters

GEMAS "MONOCON" POOL SAND FILTER.

Filter shell made of fiberglass reinforced polyester, complete with multiport valve, fittings, manometer and purge. Max. operation Pressure 2,5 kg/cm². Test pressure: 3.5 kg/cm². 2-years warranty. All models have side valve connection. **Both connections of the filter are on the bottom shell of the filter.** Filtration Rate: 50 m³/h/m². Transparent Bolted Lid (optional).





Transparent bolted lid (Optional) (Patented)

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø 450 mm - 1,5" Multi. Side Valve	021140	1		
• Ø 500 mm - 1,5" Multi. Side Valve	021141	1	17,000	0,215
• Ø 630 mm - 1,5" Multi. Side Valve	021142	1	22,800	0,325
• Ø 710 mm - 2" Multi. Side Valve	021143	1	30,000	0,470
• Ø 830 mm - 2" Multi. Side Valve	021144	1	38,600	0,665
• Ø 900 mm - 2" Multi. Side Valve	021145	1	46,300	0,905
• Ø 1000 mm - 2,5" Multi. Side without Valve	021146	1	63,200	1,021

PS: Please add "TL" to the code when ordering.



021145





Side multiport valve

MODEL	021140	021141	021142	021143	021144	021145	021146
D (mm)	450	500	630	710	830	900	1000
H ₁ (mm)	675	725	770	920	940	1000	1060
H ₂ (mm)	-	-	-	-	-	-	-
H ₃ (mm)	565	615	660	810	830	890	950
H ₄ (mm)	245	245	280	340	380	415	330
H ₅ (mm)	375	375	410	490	530	565	575
W (mm)	260	260	260	295	295	295	370
CONNECTIONS Ø(mm)	1,5"	1,5"	1,5"	2"	2"	2"	2,5"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	8 6 5	10 8 6	16 12 9	27 22 19	27 22 16	32 26 19	40 32 24
SAND (Kg)	80	100	150	250	350	450	600
NET WEIGHT (Kg)							



"Monocon" Pool Sand Filters

GEMAS "MONOCON" POOL SAND FILTER.

Filter shell made of fiberglass reinforced polyester, complete with multiport valve, fittings, manometer and purge. Max. operation Pressure 2,5 kg/cm². Test pressure: 3.5 kg/cm². 2-year warranty.

All models have top valve connection.

Filtration Rate: 50 m³/h/m².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø 450 mm- 1,5" Multi. Top Valve	021140T	1		
• Ø 500 mm - 1,5" Multi. Top Valve	021141T	1	15,500	0,215
• Ø 630 mm - 1,5" Multi. Top Valve	021142T	1	20,000	0,325
• Ø 710 mm - 2" Multi. Top Valve	021143T	1		
• Ø 830 mm - 2" Multi. Top Valve	021144T	1		
• Ø 900 mm - 2" Multi. Top Valve	021145T	1		
• Ø 1000 mm - 2,5" Multi. Top Valve	021146T			



Top bolted lid (Optional)





Water drainage

I ACDE	004440T	004444T	004440T	004440T	004444	0044455	00444/T
MODEL	021140T	021141T	021142T	021143T	021144T	021145T	021146T
D (mm)	450	500	630	710	830	900	1000
H ₁ (mm)	745	795	840	1020	1040	1100	1160
H ₂ (mm)	-	-	-	-	-	-	-
H ₃ (mm)	565	615	660	810	830	890	950
H ₄ (mm)	-	-	-	-	-	-	-
W (mm)	-	-	-	-	-	-	-
CONNECTIONS Ø(mm)	1,5"	1,5"	1,5"	2"	2"	2"	2,5"
FLOW (50 m³/h/m²) max	8	10	16	20	27	32	40
(m3/h) (TO III /II/III)	6	8	12	16	22	26	32
(111 ⁻⁷¹¹⁾ (30 m³/h/m²) mini	5	6	9	12	16	19	24
SAND (Kg)	80	100	150	250	350	450	600
NET WEIGHT (Kg)							



"Monocon TLL" **Pool Sand Filters**

GEMAS "MONOCON TLL" POOL SAND FILTER

Filter shell made of fiberglass reinforced polyester, complete with multiport valve, fittings, manometer and purge. Max. operation Pressure 2,5 kg/cm². Test pressure: 3.5 kg/cm². 2-years warranty. All models have side valve connection. Both connections of the filter are on the bottom shell of the filter. Filtration Rate: 50 m³/h/m². Transparent large bolted lid.





Transparent large bolted lid

Description	Code	Pieces/ box
Ø500 1,5" Multi. Side Valve and Wide Transparent Lid	021141TLL	1
• Ø630 1,5" Multi. Side Valve and Wide Transparent Lid	021142TLL	1
Ø710 2" Multi. Side Valve and Wide Transparent Lid	021143TLL	1
• Ø830 2" Multi. Side Valve and Wide Transparent Lid	021144TLL	1
Ø900 2" Multi. Side Valve and Wide Transparent Lid	021145TLL	1
• Ø1000 2,5" Multi. Side without Valve Wide Transparent Lid	021146TLL	1
• Ø1200 3" Multi. Side without Valve Wide Transparent Lid	021147TLL	1



021146TLL



MODEL	<i>Ø500</i>	Ø630	Ø710	Ø830	Ø900	Ø1000	Ø1200
D (mm)	500	630	710	830	900	1000	1200
H ₁ (mm)	775	895	940	960	1020	1080	1230
H ₂ (mm)	-	-	-	-	-	-	-
H ₃ (mm)	665	765	810	830	890	950	1100
H ₄ (mm)	305	310	340	380	415	330	430
H ₅ (mm)	435	440	490	530	565	575	680
W (mm)	260	260	295	295	295	370	-
CONNECTIONS Ø(mm)	1,5"	1,5"	2"	2"	2"	2,5"	3"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 16 12	27 22 16	32 26 19	40 32 24	57 45 34
SAND (Kg)	100	175	275	375	450	600	950
NET WEIGHT (Kg)							

Monocon TLLH" Pool Sand Filters

GEMAS "MONOCON TLLH" POOL SAND FILTER

Filter shell made of fiberglass reinforced polyester, complete with multiport valve, fittings, manometer and purge. Max. operation Pressure 2,5 kg/cm². Test pressure: 3.5 kg/cm². 2-years warranty. All models have side valve connection. Both connections of the filter are on the bottom shell of the filter. Filtration Rate: 50 m³/h/m². Transparent large bolted lid.

Description	Code	Pieces/ box
Ø500 1,5" Multi. Side Valve and Wide Transparent Lid	021141TLLH	1
• Ø630 1,5" Multi. Side Valve and Wide Transparent Lid	021142TLLH	1
Ø710 2" Multi. Side Valve and Wide Transparent Lid	021143TLLH	1
Ø830 2" Multi. Side Valve and Wide Transparent Lid	021144TLLH	1
Ø900 2" Multi. Side Valve and Wide Transparent Lid	021145TLLH	1
 Ø1000 2.5" Multi. Side without Valve Wide Transparent Lid 	021146TLLH	1

021142TLLH



Transparent large bolted lid



MODEL	<i>Ø</i> 500	Ø630	Ø710	Ø830	Ø900	Ø1000
D (mm)	500	630	710	830	900	1000
H ₁ (mm)	1170	1200	1230	1270	1300	1330
H ₂ (mm)	1120	1150	1180	1220	1250	1280
H ₃ (mm)	-	-	-	-	-	-
H ₄ (mm)	450	450	470	470	500	500
H ₅ (mm)	580	580	620	620	650	650
W (mm)	260	260	295	295	295	370
CONNECTIONS Ø(mm)	1,5"	1,5"	2"	2"	2"	2,5"
FLOW (50 m³/h/m²) max (M³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	20 26 12	27 22 16	32 26 19	40 32 24
SAND (Kg)	200	300	400	550	675	800
NET WEIGHT (Kg)						





High Bed, Single or Multi-Layer Sand Filters

GEMAS FILTREX - HB SAND FILTERS. Filter shell made of fiberglass reinforced laminated polyester, including pressure gauge, air purge and multiport valve. Collector with laterals. Bed depth 100 cm. Test pressure 3.5 kg/cm². Max. operation pressure 2,5 kg/cm². Please ask price for 4,0 and 6,0 kg/cm² operation pressures. Sight Glass and Transparent Bolted Lid is optional.




Weight Kg	Volume m ³
30,000	0,403
35,200	0,584
55,000	0,852
71,000	1,230
78,500	1,420

PS: Ozone resistant filters are quoted upon request.

PS: Please add "TL" to the code when ordering.



Transparent bolted lid (Optional) (Patented)







ECHNICAL CH	AKACIE	KISTICS			
MODEL	021311HB	021312HB	021313HB	021314HB	021315HB
D (mm)	500	630	710	800	900
H ₁ (mm)	1610	1510	1690	1780	1765
H ₂ (mm)	-	-	-	-	-
H ₃ (mm)	1490	1410	1530	1600	1650
H ₄ (mm)	605	590	690	605	700
H ₅ (mm)	735	720	840	755	850
H ₆ (mm)	580	630	650	330	715
CONNECTIONS (Ø)	1,5"	1,5"	2"	2"	2"
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	10 8 6	16 12 9	21 16 12	25 20 15	32 26 19
ANTHRACITE 0,8 - 1,6 mm (It)	150, 000	200, 000	250, 000	320, 000	470, 000
QUARTZ SAND 0,5 - 1 mm (Kg)	150, 000	200, 000	250, 000	320, 000	470, 000
QUARTZ SAND 1 - 3 mm (Kg)	100, 000	150, 000	215, 000	270, 000	420, 000
NET WEIGHT (Kg)	30, 000	35, 200	55, 000	71, 000	78, 500



"Filtrex and Neptune" **Filtration Units**

GEMAS "FILTREX" FILTRATION UNIT.

Fiberglass reinforced polyester filter assembled on a plastic base and installed with a pool pump.

1,5" multiport valve **Top Mounted**. Interconnection piping between the pump and the filter are both included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø450 mm with Fiberglass Reinforced	021111TFU	1	34,050	0,440
Polyester Filter, Pump 0,5 HP, Mono				
• Ø500 mm with Fiberglass Reinforced	021112TFU	1	36,950	0,460
Polyester Filter, Pump 0,5 HP, Mono				
• Ø630 mm with Fiberglass Reinforced	021113TFU	1	39,850	0,808
Polyester Filter, Pump 1,0 HP, Mono				

Top bolted lid (Optional)

GEMAS "NEPTUNE" FILTRATION UNIT. Fiberglass reinforced polyester filter assembled on a plastic base and installed with a pool pump. 1,5" multiport valve Side Mounted. Interconnection piping between the pump and the filter are both included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø450 mm with Fiberglass Reinforced	021211FU	1	33,850	0,440
Polyester Filter, Pump 0,5 HP, Mono				
Ø500 mm with Fiberglass Reinforced	021212FU	1	36,650	0,460
Polyester Filter, Pump 0,75 HP, Mono				
Ø650 mm with Fiberglass Reinforced	021213FU	1	39,550	0,808
Polyester Filter, Pump 1,0 HP, Mono				







021212FU

Filtrex top mounted multiport valve Neptune side mounted multiport valve MODEL 021111TFU 021112TFU 021113TFU 021211FU 021112TFU 021113TFU D (mm) 450 500 630 500 650 450 H_1 (mm) 585 610 770 890 H_2 (mm) 765 790 865 615 655 735 H_3 (mm) 710 740 830 H_4 (mm) H_5 (mm) W (mm) W1 (mm) 675 775 675 775 925 CONNECTIONS Ø (mm) 1,5" 1,5" 1,5" 1,5" 1,5" 1,5" FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) 16 12 9 16 12 9 8 10 10 6 5 (30 m³/h/m²) mini SAND (Kg) 150 80 80 100 100 150 NET WEIGHT (Kg) 23,000

33,850

36,650

39,550



52

18,000

TECHNICAL CHARACTERISTICS

16,000

Plastic Body Filtration Units





"Premium" Filtration Units






GEMAS "PREMIUM" FILTRATION UNIT.

Sand filter made of plastic with rotational technique, with a **top-mounted six-way valve**, which is prepared to be combined with a thermoplastic pool pump on a stand. Interconnection piping between the pump and the filter are both included.









GEMAS "PREMIUM" FILTRATION UNIT. Sand filter made of plastic with rotational technique, with a **side-mounted six-way valve**, which is prepared to be combined with a thermoplastic pool pump on a stand. Interconnection piping between the pump and the filter are both included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø400 mm with Plastic Sand Filter, Pump	021911FU	1	24,000	0,150
0,33 HP, Mono - Micro				
• Ø500 mm with Plastic Sand Filter, Pump	021912FU	1	29,000	0,190
0,5 HP, Mono - Micro				
• Ø615 mm with Plastic Sand Filter, Pump	021913FU	1	36,000	0,190
0,75 HP, Mono - Mini				



Folding collector arms





	Premium top mounted multiport valve			Premium side mounted multiport valve		
MODEL	021921FU	021922FU	021923FU	021911FU	021912FU	021913FU
D (mm)	1120	1120	1120	1120	1120	1120
H ₁ (mm)	290	330	344	280	320	334
H ₂ (mm)	220	260	274	220	260	274
W1 (mm)	444	444	500	444	444	500
CONNECTIONSØ (mm)	1,5"	1,5"	1,5"	1,5"	1,5"	1,5"
51 Q141 (50 m³/h/m²) max	7	10	15	7	10	15
FLOW (40 m³/h/m²) (m³/h) (20 m³/h/m²) mini	5	8	12	5	8	12
(1119/11) (30 m³/h/m²) mini	4	6	9	4	6	9
SAND (Kg)	75	100	150	75	100	150
NET WEIGHT (Kg)	25,000	30 ,000	38,000	24,000	29 ,000	36,000




Palletized Filtration System


Completely Installed on 100 x 120 cm pallet. 3 suctions, 1 return and 1 back wash line (d63 mm). Salt Chlorinator, Electric Panel, and transformers are optional. Extra bypass connection available for auxillary unit installation such as chlorinator, heater, heat pump etc.



Description		Code

• Ø500 mm Top Filter - 0,75 HP Mini Mono Pump	02526
• Ø615 mm Top Filter - 1 HP Mini Mono Pump	02527
• Ø760 mm Top Filter - 1,5 HP Pump	02528
• Ø500 mm Top Filter - 0,75 HP Mini Mono Pump - with Salt Chlorinator, Electric Panel	02536
• Ø615 mm Top Filter - 1 HP Mini Mono Pump - with Salt Chlorinator, Electric Panel	02537
Ø760 mm Ton Filter - 1 5 HP Pump - with Salt Chlorinator Flectric Panel	02538





MODEL	Α	В	D	Н	H¹	H²
D.500 Premium Filter - 0,75 HP Mini Streamer Pump	1200	1000	500	1100	855	1100
D.615 Premium Filter - 1 HP Mini Streamer Pump	1200	1000	615	1200	975	1100
D.760 Filtrone Filter - 1.5 HP Mini Streamer Pump	1200	1000	760	1300	1195	1100



Salt chlorinator (optional)



Electric panel (optional)





Cartridge Filters




GEMAS CARTRIDGE FILTER. Body made in ABS plastic. Complete with manometer and air purge connections 1,5" BSP threaded. Max. operation pressure: 2.5 Bar.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• AF25 Cartridge Filter - 5,5 m³/h	02411	1	5,000	0,040
AF50 Cartridge Filter - 11,4 m³/h	02413	1	5,500	0,050
AF75 Cartridge Filter - 17,0 m³/h	02414	1	6,500	0,060
• AF100 Cartridge Filter - 22,9 m³/h	02415	1	7,500	0,070
• AF150 Cartridge Filter - 33,4 m³/h	02416	1		
• AF200 Cartridge Filter - 40,9 m³/h	02417	1		



MODEL	DIA (mm)	HEIGHT (mm)	CONNECTIONS (Inlet-Outlet)	OPER.PRESSURE (kg/cm²)	FLOW (m ³ /h)	FILTRATION CAP. (µ)
AF25	445	387	1/2"	2,5	5,5	≥15
AF50	625	567	1/2"	2,5	11,4	≥15
AF75	805	747	1/2"	2,5	17,0	≥15
AF100	985	927	2"	2,5	22,9	≥15
AF150	1165	1107	2"	2,5	33,4	≥15
AF200	1345	1287	2"	2,5	40,9	≥15



MODEL	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	F (mm)	FILTRATION AREA (m²)
AF25	445	387	225	397	178	185	2,25
AF50	625	567	225	397	358	185	4,63
AF75	805	747	225	397	537	185	7,00
AF100	985	927	225	397	717	185	9,38
AF150	1165	1107	225	397	896	185	13,72
AF200	1345	1287	225	397	538x2pcs	185	16,82



OZIMIO ILZI ZITOZIMZITI OITITI				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
AF25-CE Cartridge	0241101	1		
AF50-CE Cartridge	0241301	1		
AF75-CE Cartridge	0241401	1		
AF100-CE Cartridge	0241501	1		
AF150-CE Cartridge	0241601	1		
AF200-CE Cartridge	0241701	1		



"Turbidron" Bobbin Wound Filters

ADDITIONAL OPTIONS FOR GEMAS "TURBIDRON" BOBBIN WOUND SAND FILTERS



Description	Code	Pieces/ box	Weight Kg	Volume m ³			
• Round Manhole (2,5 bar) Ø400 mm	0217172	1					
Ditto, Transparent Lid	0217172T	1					
• Round Manhole (4 bar) Ø400 mm	0217182	1					
Transparent Lid (Price difference w/ opaque)	0217119						
Sight Glass Ø90 mm	0217192	1					
Sight Glass Ø125 mm	0217202	1					
Sight Glass Ø200 mm	0217212	1					
Automatic Air Purge 1"	0217222	1					
Automatic Air Purge 2"	0217232	1					
Double Manometer Set	0217242	1					
Double Manometer Set W/Sampling V.	0217252	1					
Ozone Protection (Vinylester coating)							
• Sand Bed Depth = 1,5 m (Price difference w/1,0 m	• Sand Bed Depth = 1,5 m (Price difference w/1,0 m depth)						
• Sand Bed Depth = 1,2 m (Price difference w/1,0 m	depth)						





"Turbidron" Bobbin Wound Filters

2 years Parts WARRANTY

GEMAS "TURBIDRON" SAND FILTERS.


Up to size Ø1800, filter shell made of single piece Roto MOLDED PE. Larger sizes shell made of FR Polyester shell reinforced by fiberglass bobbin winding outside. Complete with pressure gauge, air release valve of 0,5". Test pressure 4,0 kg/cm². Max. operation pressure 2,5 kg/cm². Filtration rate: 50 m³/h/m². Filtration bed depth:1,0 m (Excluding 021717E, 021725 and 021718). Please ask price for 4,0 and 6,0 kg/cm² operation pressures. 2-year warranty.






021725

Description	Code	Pieces/ \ box	Neight V Kg	olume m³
• Ø1200 mm - 57 m³/h, 75 mm unions	021717E	1	95,000	
• Ø1200 mm - 57 m³/h	021725	1	110 ,000	
• Ø1400 mm - 77 m³/h	021718	1	180,000	
• Ø1600 mm - 101 m³/h	021719	1	240,000	
• Ø1800 mm - 127 m³/h	021720	1	275,000	
• Ø2000 mm - 157 m³/h	021721	1	300,000	
• Ø2200 mm - 190 m³/h	021722	1	425,000	
• Ø2350 mm - 217 m³/h	021727	1		
• Ø2400 mm - 226 m³/h	021723	1	535,000	
• Ø2500 mm - 246 m³/h	021724	1		
• Ø3000 mm - 354 m³/h	021726	1		





021721



	MODEL	021717E	021725	021718	021719	021720	021721	021722	021727	021723	021724	021726
	D (mm)	1200	1200	1400	1600	1800	2000	2200	2350	2400	2500	3000
	H₁ (mm)	1410	1410	1560	1860	1890	2000	2160	2300	2300	2450	2770
	H₂ (mm)	-	-	-	-	-	-	-	-	-	-	-
	H₃ (mm)	1350	1350	1500	1800	1830	1940	2100	2240	2240	2390	2710
	H₄ (mm)	520	520	600	640	670	740	800	850	850	900	
	H₅ (mm)	880	880	1000	1200	1170	1240	1300	1450	1450	1550	
CONNECTI	ONS Ø (mm)	90	90	110	125	140	160	200	200	200	200	200
(m3/h) (40	m³/h/m²) max m³/h/m²) m³/h/m²) mini	57 45 34	57 45 34	77 62 46	101 80 60	127 102 76	157 126 94	190 152 114	217 174 130	226 181 136	246 196 147	354 283 212
	SAND (Kg)	1100	1100	1750	2800	3200	4200	5600	7600	8000	8600	7000
NET V	VEIGHT (Kg)	95,000	110,000	180,000	240,000	275,000	300,000	425,000	500,000	535,000		



Turbidron Commercial Sand Filters Design Options

9	∞	7	6	5	4	ω	2		~		9	∞	7	6	л	4	ω	2		×	
Filter Ø3000 mm - 283 m ³ /h	Filter Ø2500 mm - 196 m ³ /h	Filter Ø2350 mm - 174 m ³ /h	Filter Ø2200 mm - 152 m ³ /h	Filter Ø2000 mm - 126 m ³ /h	Filter Ø1800 mm - 102 m ³ /h	Filter Ø1600 mm - 80 m ³ /h	Filter Ø1400 mm - 62 m ³ /h	Filter Ø1200 mm - 45 m ³ /h	Operation Pressure Max. 4 kg/cm ² Test Pressure 6 kg/cm ² Filtration Speed 40 m ³ /H/m ²	DESCRIPTION	Filter Ø3000 mm - 283 m ³ /h	Filter Ø2500 mm - 196 m ³ /h	Filter Ø2350 mm - 174 m ³ /h	Filter Ø2200 mm - 152 m ³ /h	Filter Ø2000 mm - 126 m ³ /h	Filter Ø1800 mm - 102 m ³ /h	Filter Ø1600 mm - 80 m ³ /h	Filter Ø1400 mm - 62 m ³ /h	Filter Ø1200 mm - 45 m ³ /h	Operation Pressure Max. 2,5 kg/cm² Test Pressure 4 kg/cm² Filtration Speed 40 m 3/H/m²	DESCRIPTION
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	А	Bed Depth 1.0 m Lateral Distribution	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	A	Bed Depth 1.0 m Lateral Distribution
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	В	Bed Depth 1.20 m	P.A.P. P.A.P.	P.A.P.	В	Bed Depth 1.20 m							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	С	Nozzle plate distribution system	P.A.P. P.A.P.	P.A.P.	С	Nozzle plate distribution system							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	D	Circular Manhole 4 Bar Ø400 mm	P.A.P. P.A.P.	P.A.P.	D	Circular Manhole 2,5 Bar Ø400 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	Z	Circular Manhole 4 Bar Ø500 mm	P.A.P. P.A.P.	P.A.P.	Z	Circular Manhole 2,5 Bar Ø500 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	E	Circular Manhole 4 Bar Ø600 mm	P.A.P. P.A.P.	P.A.P.	ш	Circular Manhole 2,5 Bar Ø600 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	F	Sight Glass 4 Bar Ø90 mm	P.A.P. P.A.P.	P.A.P.	П	Sight Glass 2,5 Bar Ø90 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	G	Sight Glass 4 Bar Ø125 mm	P.A.P. P.A.P.	P.A.P.	G	Sight Glass 2,5 Bar Ø125 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	т	Sight Glass 4 Bar Ø200 mm	P.A.P. P.A.P.	P.A.P.	エ	Sight Glass 2,5 Bar Ø200 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	_	Sight Glass 4 Bar Ø250 mm	P.A.P. P.A.P.	P.A.P.	_	Sight Glass 2,5 Bar Ø250 mm							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	J	Automatic Air Purge 1"	P.A.P. P.A.P.	P.A.P.	ر	Automatic Air Purge 1"							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	~	Automatic Air Purge 2"	P.A.P. P.A.P.	P.A.P.	~	Automatic Air Purge 2"							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	Г	Double Manometer Set	P.A.P. P.A.P.	P.A.P.	Г	Double Manometer Set							
P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	P.A.P.	Z	Ozon Protection	P.A.P. P.A.P.	P.A.P.	S	Ozon Protection							

NOTE: Please generate the product code number as per filter option configuration. (i.e X1B for d1200 Sand filter, 2,5 bar working pressure, 1,20 Sand Depth)





"Turbidron - Norm Plus" Deep - Bed Sand Filter

GEMAS "TURBIDRON-NORM PLUS" SAND FILTERS (According to DIN 19605 and 19643).

Bed depth:1,20 m. Test pressure 4 kg/cm².

Max. operation pressure 2,5 kg/cm².

Filtration Rate: Single Layer (Quartz Sand): 30 m³/h/m².

Multilayer (Quartz Sand + Anthracite and/or zeolite) : 50 m³/h/m².








Large top lid

Code	Pieces/ box	Weight Kg	Volume m ³
021512	1	1000,000	
021513	1	1300,000	
021514	1	1800,000	
021515	1	2350,000	
021516	1	3300,000	
021517	1	4400,000	
021518	1	5700,000	
021519	1	6850,000	
021520	1	7700,000	
021521	1	8300,000	
	021512 021513 021514 021515 021516 021517 021518 021519 021520	Code box 021512 1 021513 1 021514 1 021515 1 021516 1 021517 1 021518 1 021519 1 021520 1	Code box Kg 021512 1 1000,000 021513 1 1300,000 021514 1 1800,000 021515 1 2350,000 021516 1 3300,000 021517 1 4400,000 021518 1 5700,000 021519 1 6850,000 021520 1 7700,000

PS: Filtration rate for public pools should not exceed 50 m³/h/m².



FR polyester connection





Side manhole



Nozzle distribution system

MODEL	021512	021513	021514	021515	021516	021517	021518	021519	021520	021521		
D (mm)	900	1000	1200	1400	1600	1800	2000	2200	2400	2500		
D ₁ (mm)	-	-	-	-	-	-	-	-	-	-		
H ₃ (mm)	2000	2100	2180	2360	2420	2530	2580	2580	2580	2580		
H ₄ (mm)	550	750	750	820	850	900	950	950	1000	1000		
H ₅ (mm)	1450	1550	1550	1520	1550	1600	1700	1700	1750	1750		
H ₆ (mm)	900	900	900	1000	950	950	1100	1000	1000	1000		
H ₇ (mm)	1200	1200	1200	1200	1200	1200	1200	1200	1200	1200		
CONNECTIONS Ø (mm)	63	63	75	90	110	110	125	140	160	160		
FLOW (50 m³/h/m²) max (m³/h) (40 m³/h/m²) (30 m³/h/m²) mini	32 26 19	40 32 24	57 45 34	77 62 46	101 80 60	127 102 76	157 126 94	190 152 114	226 181 136	246 196 147		
SAND (Kg)	1000	1300	1900	2600	3400	4400	5300	6600	8000	8600		





"Turbidron" Bobbin Wound Horizontal Filters

Filter shell made of fiberglass reinforced laminated polyester by fiberglass bobbin winding outside. Complete with pressure gauge, 1,5" air valve and 400 mm side manhole. Test pressure 4 kg/cm². Max. operation pressure 2,5 kg/cm². Filtration rate Max. 30 m³/h/m². Pls. ask price for 4 Bar working pressure. Pls. ask price for "Dual Stack" version.

Description	Code	Pieces/ box
Filtration Bed Depth 0,6 m.		
•Ø1000 mm - L=1500 mm. 34 m³/h	02197161	1
•Ø1000 mm - L=2000 mm. 51 m³/h	02197162	1
•Ø1200 mm - L=2000 mm. 63 m³/h	02197171	1
•Ø1200 mm - L=2500 mm. 80 m³/h	02197172	1
Filtration Bed Depth 0,8 m.		
•Ø1400 mm - L=2000 mm. 70 m³/h	02197181	1
•Ø1400 mm - L=2500 mm. 88 m³/h	02197182	1
•Ø1400 mm - L=3000 mm. 110 m³/h	02197183	1
•Ø1600 mm - L=2000 mm. 87 m³/h	02197191	1
•Ø1600 mm - L=2500 mm. 105 m³/h	02197192	1
•Ø1600 mm - L=3000 mm. 137 m³/h	02197193	1
•Ø1600 mm - L=4000 mm. 163 m³/h	02197194	1
•Ø1600 mm - L=4500 mm. 190 m³/h	02197195	1
Filtration Bed Depth 1,0 m.		
•Ø1800 mm - L=2500 mm. 114 m³/h	02197201	1
•Ø1800 mm - L=3000 mm. 140 m³/h	02197202	1
•Ø1800 mm - L=3500 mm. 166 m³/h	02197203	1
•Ø1800 mm - L=4000 mm. 191 m³/h	02197204	1
•Ø2000 mm - L=2500 mm. 123 m³/h	02197211	1
•Ø2000 mm - L=3000 mm 152 m³/h	02197212	1
•Ø2000 mm - L=3500 mm. 180 m³/h	02197213	1
•Ø2000 mm - L=4000 mm. 209 m³/h	02197214	1
•Ø2000 mm - L=4500 mm. 236 m³/h	02197215	1
•Ø2000 mm - L=5000 mm. 265 m³/h	02197216	1
•Ø2200 mm - L=2500 mm. 137 m ³ /h	02197221	1
•Ø2200 mm - L=3000 mm. 165 m^3/h	02197222	1
•Ø2200 mm - L=3500 mm. 197 m³/h	02197223	1
•Ø2200 mm - L=4000 mm. 229 m³/h	02197224	1
•Ø2200 mm - L=4500 mm. 258 m³/h	02197225	1
•Ø2200 mm - L=5000 mm. 287m³/h	02197226	1
Filtration Bed Depth 1,2 m.		
•Ø2400 mm - L=3000 mm. 179 m³/h	02197231	1
•Ø2400 mm - L=3500 mm. 214 m³/h	02197232	1
•Ø2400 mm - L=4000 mm. 248 m³/h	02197233	1
•Ø2400 mm - L=5000 mm. 306 m ³ /h	02197234	1
•Ø2500 mm - L=4000 mm. 267 m³/h	02197241	1
•Ø2500 mm - L=5000 mm. 341 m³/h	02197242	1








Dual stack assembly detail






"Turbidron" Bobbin Wound Horizontal Filters







TECHNICAL CHARACTERISTICS

TECHNICAL CHARACTERISTICS																
MODEL	D (mm)	<i>L±20</i> (mm)	A±50 (mm)	<i>B±20</i> (mm)	C±50 (mm)	E±50 (mm)	F±20 (mm)	G±50 (mm)	H±50 (mm)	/±100 (mm)	K±50 (mm)	<i>T±30</i> (mm)	Connec. (Ø) (mm)	Flow (m³/h) (50 m³/h/m²)	Sand (Kg)	Net Weight (Kg)
02197161	1000	1500	610	930	370	380	190	250	1250	750	750	1630	90	40	1260	138
02197162	1000	2500	610	930	1170	500	190	250	1250	1250	750	2650	125	40	2100	208
02197171	1200	2000	710	1030	840	380	200	250	1450	750	900	2250	125	57	2016	216
02197172	1200	2500	710	1030	1100	500	200	250	1450	1000	900	2650	140	57	2520	258
02197181	1400	2000	810	1200	820	380	210	250	1650	750	1000	2250	125	77	3136	262
02197182	1400	2500	810	1200	1080	500	210	250	1650	1000	1000	2650	140	77	3920	310
02197183	1400	3000	810	1200	685	500	210	250	1650	1000	1000	3180	160	77	4704	359
02197191	1600	2000	810	1380	600	450	240	250	1850	750	1200	2250	140	101	3584	310
02197192	1600	2500	910	1380	1020	500	240	250	1850	1000	1200	2680	160	101	4480	366
02197193	1600	3000	910	1380	640	500	240	250	1850	1000	1200	3180	160	101	5376	421
02197194	1600	4000	910	1380	1090	550	240	250	1850	1500	1200	4180	160	101	5940	561
02197195	1600	4500	910	1380	780	600	240	250	1850	1500	1200	4700	200	101	6730	631
02197201	1800	2500	910	1560	860	550	270	300	2080	1000	1400	2680	160	127	6300	472
02197202	1800	3000	1030	1560	1260	600	270	300	2080	1000	1400	3680	160	127	7560	541
02197203	1800	3500	1030	1560	795	550	270	300	2080	1000	1400	3700	200	127	8820	611
02197204	1800	4000	1030	1560	1045	550	270	300	2080	1500	1400	4200	200	127	10080	680
02197211	2000	2500	1030	1730	800	550	300	400	2300	1000	1500	2680	160	157	7000	540
02197212	2000	3000	1160	1730	1100	650	300	400	2300	1000	1500	3180	160	157	8400	617
02197213	2000	3500	1160	1730	750	550	300	400	2300	1000	1500	3700	200	157	9800	694
02197214	2000	4000	1160	1730	1000	550	300	400	2300	1500	1500	4200	200	157	11200	771
02197215	2000	4500	1160	1730	1150	650	300	400	2300	1500	1500	4730	225	157	12600	848
02197216	2000	5000	1160	1730	900	550	300	400	2300	1750	1500	5230	225	157	14000	925
02197221	2200	2500	1260	1860	800	550	300	400	2500	1000	1750	2750	200	190	7700	673
02197222	2200	3000	1260	1860	1100	650	300	400	2500	1000	1750	3200	200	190	9240	766
02197223	2200	3500	1260	1860	750	550	300	400	2500	1000	1750	3700	200	190	10780	860
02197224	2200	4000	1260	1860	1000	550	300	400	2500	1500	1750	4230	225	190	12320	953
02197225	2200	4500	1260	1860	1250	550	300	400	2500	1500	1750	4730	225	190	13860	1046
02197226	2200	5000	1260	1860	900	550	300	400	2500	1750	1750	5200	250	190	15400	1245
02197231	2400	3000	1380	2030	1000	550	350	450	2720	1000	1900	3200	200	226	12096	935
02197232	2400	3500	1380	2030	625	650	350	450	2720	1000	1900	3700	200	226	14112	1277
02197233	2400	4000	1380	2030	875	600	350	450	2720	1500	1900	4230	225	226	16128	1413
02197234	2400	5000	1380	2030	1275	700	350	450	2720	1500	1900	5250	225	226	16800	1486
02197241	2500	4000	1430	2130	875	600	350	450	2820	1500	1980	4230	225	246	16800	1486
02197242	2500	5000	1430	2130	1275	700	350	450	2820	1750	1980	5250	250	246	21000	1769

PS: Sight glass is optional. You can add it from the optional table on page 57.





"Neptune" High Rate Sand Filters

GEMAS "NEPTUNE" COMMERCIAL SAND FILTERS.

Filter shell made of fiberglass reinforced laminated polyester, including pressure gauge, air release valve of 0,5".


Test pressure 3.5 kg/cm². Max. operation pressure 2,5 kg/cm².

Filtration rate: 50 m³/h/m².

Filtration Depth: 1,0 m (except 021216, 021217). Counter flange is not included in price (021216).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•Ø1200 mm - Connections	021216L	1	78,500	1,460
Ø90 mm w/loose flange. Max. 57 m ³ /h.				
•Ø1400 mm - Connections	021217	1	145,000	2,350
Ø110 mm flanged. Max. 77 m³/h				
•Ø1600 mm - without valve Ø125 mm	021218	1	202,500	3,760
flanged connection. Max. 101 m³/h				
•Ø1800 mm - without valve Ø140 mm	021224	1	225,000	5,080
flanged connection. Max. 127 m³/h				
• Ø2000 mm - without valve Ø160 mm	021219	1	245,000	6,410
flanged connection. Max. 157 m³/h				
•Ø2200 mm - without valve Ø200 mm	021220	1	425,000	8,900
flanged connection. Max. 190 m³/h				
•Ø2400 mm - without valve Ø200 mm	021225	1	535,000	12,200
flanged connection. Max. 226 m³/h				

 $\textbf{PS:} \ \text{Filtration rate for public pools should not exceed 50 } \ m^3/h/m^2.$





Loose flange connection (021216)



021218

TECHNICAL CHARACTERISTICS

TECHNICAL CHARACTERISTICS											
MODEL	021216L	021217	021218	021224	021219	021220	021225				
D (mm)	1200	1400	1600	1800	2000	2200	2400				
H ₁ (mm)	1325	1380	1640	1960	1960	2160	2750				
H ₃ (mm)	1265	1320	1580	1890	1900	2200	2600				
H ₄ (mm)	500	630	670	680	830	850	900				
H ₅ (mm)	900	980	1200	1090	1330	1280	1700				
CONNECTIONS Ø (mm)	90	110	125	140	160	200	200				
FLOW (50 m³/h/m²) max (40 m³/h/m²) (30 m³/h/m²) mini	57 45 34	77 62 46	101 80 60	127 102 76	157 126 94	190 152 114	226 181 136				
SAND (Kg)	1300	1950	2750	3650	4750	5700	6600				
NET WEIGHT (Kg)	78, 500	145, 000	202, 500	225, 000	245, 000	425	535				



Water drainage

62





"Filtrex - Norm Plus" Sand Filters - Deep Bed

GEMAS FILTREX - NORM PLUS SAND FILTERS According to DIN 19605 and 19643).

Filter shell made of fiberglass reinforced laminated polyester, including pressure gauge, air purge. Manufactured with collector plate with nozzles. Sight glass at side. Bed depth 120 cm. Filtration rate for single layer: 30 m³/h/m².

Test pressure 3,5 kg/cm². Max. operation pressure 2,5 kg/cm².








Sight glass


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø630 mm - 9 m³/h - 12,5 m³/h	021411	1	52,650	0,630
• Ø830 mm -16 m³/h - 21,5 m³/h	021412	1	102,000	1,050
• Ø1000 mm - 23,5 m³/h - 31,5 m³/h	021413	1	135,000	1,880
• Ø1250 mm - 37 m³/h - 49 m³/h	021414	1	237,400	2,930
• Ø1400 mm - 46 m³/h - 61,5 m³/h	021415	1	300,000	3,700
• Ø1600 mm - 63 m³/h - 84 m³/h	021416	1	355,000	4,800











Nozzle Distribution system

ILCHINICAL CHARACTERISTICS											
MODEL	021411	021412	021413	021414	021415	021416					
D (mm)	630	830	1000	1250	1400	1600					
H ₁ (mm)	2060	1970	2145	2560	2540	2480					
H_2 (mm)	-	-	-	-	-	-					
H ₃ (mm)	1940	1850	1985	2320	2380	2320					
H_4 (mm)	330	385	500	270	840	830					
H ₅ (mm)	1720	1560	1620	2070	1620	1600					
H ₆ (mm)	600	940	970	950	1000	1050					
H ₇ (mm)	1750	1620	1665	1550	1600	1650					
CONNECTIONS Ø (mm)	1,5"	2"	3"	3"	4"	4"					
FLOW (m³/h) (40 m³/h/m²)	12	22	31	49	61	80					
ANTHRACITE 0,8 - 1,6 mm (It)	200,000	300,000	475,000	675,000	770,000	1000,000					
QUARTZ SAND 0,5 - 1 mm (Kg)	200,000	300,000	475,000	675,000	770,000	1000,000					
QUARTZ SAND 1 - 3 mm (Kg)	150,000	225,000	425,000	525,000	630,000	825,000					
NET WEIGHT (Kg)	52,650	102,000	135,000	237,000	300,000	355,000					
· · · · · · · · · · · · · · · · · · ·											





"Filtrex - Norm Plus" Sand Filters - Deep Bed

GEMAS FILTREX - NORM PLUS SAND FILTERS (According to DIN 19605 and 19643).

Filter shell made of fiberglass reinforced laminated polyester, including pressure gauge, air purge. Manufactured with collector plate with nozzles.

Sight glass at side. Bed depth 120 cm. Filtration rate for single layer: 30 m³/h/m². Test pressure 3,5 kg/cm².


Max. operation pressure 2,5 kg/cm².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø1800 mm - 76 m³/h - 101 m³/h	021417	1	450,000	
• Ø2000 mm- 94 m³/h - 125 m³/h	021418	1	470,000	
• Ø2200 mm - 114 m³/h - 152 m³/h	021419	1	685,000	
• Ø2400 mm - 136 m³/h - 181 m³/h	021420	1	860,000	
• Ø2500 mm - 136 m³/h - 181 m³/h	021421	1	910,000	



021417







Sight glass

MODEL	021417	021418	021419	021420	021421
D (mm)	1800	2000	2200	2400	2500
H ₁ (mm)	2490	2670	2610	2760	2710
H ₂ (mm)	-	-	-	-	-
H ₃ (mm)	2330	2600	2450	2600	-
H ₄ (mm)	800	950	850	970	1000
H ₅ (mm)	1550	1710	1630	1720	1800
H ₆ (mm)	980	1040	950	1060	1090
H ₇ (mm)	1580	1700	1660	1770	
CONNECTIONS Ø (mm)	5"	5"	6"	7,5"	7,5"
FLOW (m³/h) (40 m³/h/m²)	102	126	152	181	197
ANTHRACITE 0,8 - 1,6 mm (It)	1221,000	1507,000	1821,000	2170,000	4712,000
QUARTZ SAND 0,5 - 1 mm (Kg)	3205,000	3951,000	4787,000	5697,000	6185,000
QUARTZ SAND 1 - 3 mm (Kg)	1068,000	1319,000	1596,000	1899,000	2062,000
NET WEIGHT (Kg)	450,000	470,000	685,000	860,000	910,000





Nozzle Distribution system



Volume

Valve Batteries for Commercial Filters



FOR SINGLE FILTER: PVC Valve Batteries with 5 pieces of Ball/Butterfly valves complete mounted including pipe support pivots with arm clamps and anchoring system, all made in zinc-plated steel. (Please see Battery Supports)

Pieces/

Weight

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø75 Ball Valves Battery	131117B	1		
Ø90 Ball Valves Battery	131118B	1		
Ø110 Ball Valves Battery	131119B	1		
 Ø110 Butterfly Valves Battery 	131603B	1		
Ø125 Butterfly Valves Battery	131604B	1		
 Ø140 Butterfly Valves Battery 	131605B	1		
 Ø160 Butterfly Valves Battery 	131606B	1		
 Ø200 Butterfly Valves Battery 	131607B	1		
Ø225 Butterfly Valves Battery	131608B	1		



FOR TWO FILTERS: PVC Valve Batteries with 5 pieces of Ball/Butterfly valves including pipe support pivots with arm clamps and anchoring system, all made in zinc-plated steel. (Please see Battery Supports)

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø110 Ball Valves Battery	131119BD	1		
Ø110 Butterfly Valves Battery	131603BD	1		
Ø125 Butterfly Valves Battery	131604BD	1		
 Ø140 Butterfly Valves Battery 	131605BD	1		
Ø160 Butterfly Valves Battery	131606BD	1		
Ø200 Butterfly Valves Battery	131607BD	1		
Ø225 Butterfly Valves Battery	131608BD	1		





AUTOMATIC AIR PURGE. Automatic Air Purge for filters with large lid. Made of PVC, 1" male threaded connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1"	02701	1		
• 2"	02702	1		



Motor Actuated Valves and Automatic Battery Sets For Filters

FOR SINGLE FILTER: Motor Actuated PVC valve batteries with ball or butterfly valves for commercial sand filters. Complete with zinc plated Battery Support Sets and Clamp Support Systems. **(Please see Valve Battery Support Systems).** The system is designed with 5 valve Groups including FILTRATION, BACKWASH, RINSE, RECIRCULATION and WASTE functions completely. DOES NOT INCLUDE CONTROL UNIT. Can be used manually in case of a power cut.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø90 Butterfly Valves Battery	131602BM	1		
Ø110 Butterfly Valves Battery	131603BM	1		
Ø125 Butterfly Valves Battery	131604BM	1		
• Ø140 Butterfly Valves Battery	131605BM	1		
• Ø160 Butterfly Valves Battery	131606BM	1		
Ø200 Butterfly Valves Battery	131607BM	1		
• Ø225 Butterfly Valves Battery	131608BM	1		



AUTOMATIC VALVE BATTERY CONTROL UNIT WITH MICROPROCESSOR:

It is designed to work with 5 valve groups (described above) with pressure and/or time controlled. It deactivates the pump in case of high pressure. It stops/starts the pump during the valve position changes.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Control Unit	0221350P	1		
• Electronic Pressure Sensor	0221350PS	1		
Wifi addition	0221350WF	1		














Valve Battery Support Systems



GEMAS VALVE BATTERY SUPPORT PIVOT SET. Made of zinc plated steel, 40x40x2,5 mm steel profile, complete with 2 pieces of stainless steel sliding pipe clamp and 2 sets of sliding fixing part; with steel footers to be fixed with 4 screws on the ground.




Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2 x Ø90 Clamp - h=1,5 m	139111	1		
• 2 x Ø110 Clamp - h=1,5 m	139112	1		
• 2 x Ø125 Clamp - h=1,5 m	139113	1		
• 2 x Ø140 Clamp - h=1,5 m	139114	1		
• 2 x Ø160 Clamp - h=1,5 m	139115	1		
• 2 x Ø200 Clamp - h=1,5 m	139116	1		
• 2 x Ø225 Clamp - h=1,5 m	139117	1		
• 2 x Ø140 Clamp - h=2,0 m	139121	1		
• 2 x Ø160 Clamp - h=2,0 m	139122	1		
• 2 x Ø200 Clamp - h=2,0 m	139123	1		
• 2 x Ø225 Clamp - h=2,0 m	139124	1		







Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 x Ø90 Clamp - h=0,40 m	139211	1		
• 1 x Ø110 Clamp - h=0,40 m	139212	1		
• 1 x Ø125 Clamp - h=0,40 m	139213	1		
• 1 x Ø140 Clamp - h=0,40 m	139214	1		
• 1 x Ø160 Clamp - h=0,40 m	139215	1		
• 1 x Ø200 Clamp - h=0,40 m	139216	1		
• 1 x Ø225 Clamp - h=0,40 m	139217	1		





Detail 1

Detail 2



Valve Battery Support Systems

GEMAS VALVE BATTERY SUPPORT LANE - SINGLE.

Made of zinc plated steel, 40x40x2,5 mm steel profile. Complete with steel footers to be fixed with 4 screws on the ground. Other end with plastic cap.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• h= 2,0 m, Support Pivot	1391112	1		
• h= 1,5 m, Support Pivot	1391111	1		
• h= 0,4 m, Horizontal Support	1391110	1		



GEMAS SLIDING PIPE CLAMP FOR SUPPORT. Made of zinc plated steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø90	13911111	1		
• Ø110	13911112	1		
• Ø125	13911113	1		
• Ø140	13911114	1		
• Ø160	13911115	1		
• Ø200	13911116	1		
• Ø225	13911117	1		



GEMAS SLIDING CLAMP FIXING PART.

Complete with M8 nuts and bolts. Two pieces of fixing part is necessary for each clamp.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1391114	1		



GEMAS CAP FOR SUPPORT LANE. Made of plastic, black cap - 400 x 400 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1391113	1		





HANG-OVER Filtration Units



GEMAS "DECKON" HANG-OVER FILTRATION UNIT.

HANG-OVER Unit: The body is made of UV-resistant ABS plastic and includes a 23 W/12 V LED underwater light, skimmer, suction inlet, and 2+1 side and bottom oriented inlets. The Hang-over unit and filter room can be assembled separately using two different plastic covers (included).

Filtration Room: The base part is made of FRP, and the upper frame and room cover are made of UV-resistant ABS plastic. It comes complete with a sand or cartridge filter, electrical control board, pneumatic on-off switch, and transformer. The machine room and Hang-over unit can be installed separately. Top covers for such applications are included.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Hang-over Unit	02511	1	19,100	0,420
Filtration room w/sand filter				
• Ø400 mm sand filter + 0,5 HP	02512	1	65,850	0,870
Pump - 6 m ³ /h				
• Ø500 mm sand filter + 0,75 HP	02513	1	67,650	0,870
Pump - 10 m ³ /h				

PS. In case of any inquiry for Ø615 or Ø710 filter, this unit could be incorporated w/fitration room 02517.


Filtration room w/cartridge filter		
• P510 cartridge filter + 0,5 HP	02514	1
Pump - 6 m ³ /h		
• P512 cartridge filter + 0,75 HP	02515	1
Pump - 10 m³/h		
• P513 cartridge filter + 1" HP	02516	1
Pump - 15 m³/h		





Options

• ECOSlimLED Light 051130EO 1
• Chlorine feeder 069CLT167B 1

PS. Filter media not included.















HANG-OVER Filtration Units

GEMAS "DECKON JET" HANG-OVER FILTRATION UNIT, with COUNTER CURRENT. HANG-OVER Unit: The body is made of UV-resistant ABS plastic and includes a 23 W/12 V LED underwater light, skimmer, suction inlet, and 2+1 side and bottom oriented inlets, jet inlet, air regulator, counter current on/off pneumatic button, stainless steel handles. The Hang-over unit and filter room can be assembled separately using two different plastic covers (included).

Filtration Room: The base part is made of FRP, and the upper frame and room cover are made of UV-resistant ABS plastic. It comes complete with a circulation pump, 2 HP jet pump, sand or cartridge filter, electrical control board, pneumatic on-off switch, and transformer. The machine room and Hang-over unit can be installed separately. Top covers for such applications are included.




Code	Pieces/ box	Weight Kg	Volume m ³
02511J	1	20,000	0,420
02512J	1	85,850	0,870
02513J	1	89,650	0,870
	02511J 02512J	Code box 02511J 1 02512J 1	Code box Kg 02511J 1 20,000 02512J 1 85,850


PS. In case of any inquiry for Ø615 or Ø710 filter, this unit could be incorporated w/fitration room 02517. Filtration room w/cartridge filter


gg		
• P510 cartridge filter + 0,5 HP +	02514J	1
2" HP Jet pump - 6 m³/h		
• P512 cartridge filter + 0,75 HP +	02515J	1
2" HP Jet pump - 10 m ³ /h		
• P513 cartridge filter + 1" HP + 2" HP	02516J	1
Jet pump - 15 m³/h		

T 312 Cartilage liller + 0,73111 +	023133	I I	
2" HP Jet pump - 10 m³/h			
• P513 cartridge filter + 1" HP + 2" HP	02516J	1	
Jet pump - 15 m³/h			
Options			
ECOSlimLED Light	051130E0	1	
Chlorine feeder	069CLT167B	1	

PS. Filter media not included.



















Filtration Rooms



GEMAS FILTRATION ROOM

CABIN II: Body made of FRP, frame and top up made of ABS. Suitable up to Ø500 mm size premium top mounted sand filter. Body to be mounted in the ground.

CABIN III: Body and lid made LDPE, It is produced with rotational moulding technique. Complete with double sided wall joints, water drainage and locking nuts. Max. filter size Ø830 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Cabin II	02510	1		
Cabin III	0251702	1		









GEMAS FILTRATION UNIT WITH ROOM

Gemas Filtration Room 0251702 installed with Filtrone Sand Filter, Mini Streamer Pump. **Options:** Pool Control Mono pH and Redox Controller, Chlorine Feeder, HOZ-01/02 Ozone Generator, Remote Control for UW Light and Pump, Electrical Control Panel, Transformer.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø615 mm Sand Filter (021713) +	02517	1	124,000	1,950
0,75 HP Pump - 15 m³/h.				
• Ø710 mm Sand Filter (021814) +	02518	1	140,000	1,950
1,5 HP Pump - 20 m³/h.				







GEMAS Multiport Valves - Manual

GEMAS VALVEX 03 - SIDE. Multiport valve, 1,5".

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Threaded connections	02400T	1	1,600	
• Ø50 mm Slip connections - metric	02400	1	1,600	0,008



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Threaded connections	02403T	1	1,900	0,015
• Ø50 mm Slip connections - metric	02403	1	1,900	
• 2" Threaded connections	02213029T	1	3,500	
• Ø63 mm Slip connections - metric	02213029	1		

GEMAS VALVEX 03 - TOP CLAMPED. Multiport valve, 1,5", clamp set not included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Threaded connections	02404T	1	1,900	0,015
• Ø50 mm Slip connections - metric	02404	1	1,900	
• Clamp set - (old)	024041	1		
• Clamp set - (new)	024042	1		

GEMAS VALVEX 04 - SIDE. Multiport valve, 2"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Multiport valve, 2" Threaded connections	02213027T	1	2,956	0,016
• Ø63 mm Slip connections - metric	02213027	1	3,000	

GEMAS VALVEX 05 - SIDE. Multiport valve, 2,5".

2" multiport valve outputs are with Ø75 mm sockets outside.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø75 mm Slip connections - metric	02213028	1		0,016

SIDE MULTIPORT VALVE. Threaded connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Side M.Valve 2,5" w/out connection, IMPORT	022130001	1		
• GEMAS Side M.Valve, 3"w/out connection	022130003T	1	8,000	0,050
• Side M.Valve, 3" w/out connection, IMPORT	022130002	1		
• Side M.Valve, 4" w/out connection, IMPORT	022380-E20	1	18,000	0,120





02213027






Automatic Multiport Valves




An Automatic Multiport Valve (AMV) is a type of control valve used primarily in water treatment systems, especially in swimming pool filters, softeners, demineralizers, and filtration units, to automatically manage the flow of water through different processes. It simplifies and automates the routing of water through multiple ports (inlet, outlet, drain, backwash, rinse, etc.) by using pre-programmed electronic or mechanical controls.

- Easy installation
- Low weight and volume with compact design
- Waterproof IP40
- · Complies with CE standards and directives
- 230/115V AC power supply
- Compatible with Ø1.5" and Ø2" multiport valve bodies
- Pressure- and time-based programming
- Adjustable backwash and rinse durations
 Backwash: 0.5~4 min. / Rinse: 20~40 seconds)
- Automatic pump control
- Pool can be drained at any time via the drain button on the keypad
- Optional Wi-Fi control allows remote operation via the GEMAS SMART application
- Fast technical support service and hassle-free spare part supply

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Automatic M.Valves; 1,5", Threaded con. IMPORT	0221310	1	4,000	0,033
• Automatic M.Valves; 2", Threaded con. IMPORT	0221320	1	5,000	0,033
• GEMAS Automatic M.Valves; 1,5", Threaded con.	0221311	1		
• GEMAS Automatic M.Valves; 2", Threaded con.	0221312	1		





- Fully Automated Operation Automatically controls all valve functions without manual intervention, ensuring reliable and consistent system performance.
- Multi-Function Control Supports multiple processes such as filtration, backwash, rinse, regeneration, and drain within a single compact unit.
- Programmable Settings Can be configured based on time, flow rate, or system demand for flexible and optimized operation.
- Compact and Space-Saving Design Combines several flow functions in one valve, reducing the need for multiple individual components.
- Reduced Maintenance and Labor Minimizes human error and manual handling, lowering operational costs and improving system reliability.
- Durable Construction Built from corrosion-resistant materials suitable for continuous use in harsh water treatment environments.



Filtration Media - Ouartz Sand

Ouartz Sand

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• (0,5 - 1,0 mm)	02312	1	25,000	0,040
• (1,0 - 3,0 mm)	02313	1	25,000	0,040
• (3,0 - 5,0 mm)	02314	1	25,000	0,040



Anthracite

De	scription	Code	Piece box	., 5	Volume m ³
Pri	ce per liter	02321	1	30,000	0,040



Zeolite

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Price per liter	02331	1	25,000	0,050

PS: Zeolite is used instead of Quartz or with Quartz.

It is used to reduce Iron elements or stabilize the hardness in pool water. Should be backwashed and rinsed for 30 minutes before first operation.

Filter Sand Evacuation Tool

SANDVAC. Sand Evacuation Tool. Works with wet-dry vacuuming. Stainless Steel Body. Complete with hose. 220V / 50 Hz - Monophase

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	02601	1		







GEMAS Glass Filtration Media














GEMAS GLASS FILTER-MEDIA

An environmentally friendly alternative to silica sand for filtration purposes. It is made from recycled glass, eliminating the need for intrusive mining and reducing the consumption of scarce resources.

GGFM offers several benefits over silica sand:

Improved Efficiency: Due to its angular to sub-angular particle shape and bound silica content, GGFM provides a 30% improvement in turbidity removal compared to silica sand. It also has the ability to remove finer particles from water.

Reduced Backwashing: The non-porous composition of GGFM prevents it from clumping, resulting in reduced backwashing needs. This leads to water, energy, and chemical treatment cost savings.

Cleaner Performance: GGFM's smooth surface area makes it less susceptible to bio-fouling compared to silica sand. Bacteria are unable to get trapped in cracks or flaws, reducing the need for remedial action and chemical treatment to combat pollutants.

Lower Material Requirement: GGFM is less dense than sand, requiring 15% less media to fill an equivalent filter.

Longer Lifespan: GGFM's durability translates to a longer lifespan, potentially eliminating the need for media replacement during filter refurbishment.

Overall, GEMAS GLASS FILTER-MEDIA offers superior performance, cost-effectiveness, and environmental advantages compared to traditional silica sand. It contributes to efficient filtration, reduced maintenance, and a longer-lasting filtration system.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 0,6 mm - 1,00 mm grain thickness	023411	1		
• 1 mm - 3,00 mm grain thickness	023412	1		
• 3 mm - 5,00 mm grain thickness	023413	1		

Density Comparison GGFM Against Sand

Dia of Filter (mm)	Total Grade 1&3 Sand Required (kg)	Total Grade 1&3 GGFM GGFM Required (kg)	
600	150	130	
750	250	215	
900	450	385	
1000	700	595	
1200	1300	1100	
1400	1950	1660	
1600	2750	2340	
1800	3650	3105	
2000	4750	4040	
2200	5700	4845	
2400	6600	5610	
2500	7000	5950	

As GGFM is lighter than sand, it requires approximately 15% less GGFM to achieve the same filter bed depth as sand.



Polymer Filtration Media

Polymer Filtration Media - PFM: Syntetic Filtration Media made of polymer, can be used instead of quartz sand for commercial or domestic sand filters. Its being lightweight is a great advantage during the application. Backwash can be done as usual. But as pressure increase is low inside the polluted filter, backwash should be done with timing (The longest backwash period once in a week). It gives opportunity to get the required flow rate rate with a smaller pump, as pressure loss is low. 1 bag of PFM is 500 gr and it's equal to 25 kg sand. Can also be used inside cartridge filters. It filters 1 micron particules and yet not flocculant is required with PFM.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• PFM Bag	02351	1	25	







Poolside Equipment

In-Pool Materials

04

77









Pool Ladders




STANDARD




"U" MODEL




COMBINED



Number of Treads	А	В	С	D	E	F
2	700	690	250	700	190	500
3	700	690	250	950	190	500
4	700	690	250	1200	190	500
5	700	690	250	1450	190	500



1	Number of Treads	А	В	С	D	E	F
	2	330	670	250	700	190	500
	3	330	670	250	950	190	500
	4	330	670	250	1200	190	500
	5	330	670	250	1450	190	500



Number of Treads	Α	В	С	D	E	F	G
2	210	690	250	630	190	500	640
3	210	690	250	880	190	500	640
4	210	690	250	1130	190	500	640
5	210	690	250	1380	190	500	640

STANDARD 304 MODEL WITH STAINLESS STEEL TREADS.

500 mm width. The treads are made of AISI 304 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 304 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311111	1	10,200	0,122
• With 3 Stainless Steel Treads	0311112	1	11,900	0,122
• With 4 Stainless Steel Treads	0311113	1	13,300	0,122
• With 5 Stainless Steel Treads	0311114	1	14,800	0,139

U 304 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0311211	1	8,800	0,071
• With 3 Stainless Steel Treads	0311212	1	10,200	0,071
• With 4 Stainless Steel Treads	0311213	1	11,800	0,071
With 5 Stainless Steel Treads	0311214	1	13,100	0,079

COMBINED 304 MODEL WITH STAINLESS STEEL TREADS



Zinc Anode

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0311311	1	9,700	0,118
• With 3 Stainless Steel Treads	0311312	1	11,200	0,118
With 4 Stainless Steel Treads	0311313	1	12,800	0,118
• With 5 Stainless Steel Treads	0311314	1	14,300	0,118

PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.






Pool Ladders









Number of Treads	А	В	С	D	E	F
2	700	690	250	700	190	500
3	700	690	250	950	190	500
4	700	690	250	1200	190	500
5	700	600	250	1/50	100	500





	Number of Treads	А	В	С	D	E	F
1	2	330	670	250	700	190	500
]	3	330	670	250	950	190	500
1	4	330	670	250	1200	190	500
	5	330	670	250	1450	190	500





COMBINED

	Number of Treads	А	В	С	D	E	F	G
	2	210	690	250	630	190	500	640
ı	3	210	690	250	880	190	500	640
ı	4	210	690	250	1130	190	500	640
ı	5	210	690	250	1380	190	500	640

STANDARD 316 MODEL WITH STAINLESS STEEL TREADS.

500 mm width. The treads are made of AISI 316 grade stainless steel and feature anti-slip surface. The handrails are made of Ø42 mm AISI 316 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312111	1	10,600	0,122
• With 3 Stainless Steel Treads	0312112	1	12,300	0,122
• With 4 Stainless Steel Treads	0312113	1	13,700	0,122
• With 5 Stainless Steel Treads	0312114	1	15,200	0,139

U 316 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312221	1	9,200	0,071
With 3 Stainless Steel Treads	0312222	1	10,600	0,071
With 4 Stainless Steel Treads	0312223	1	12,200	0,071
With 5 Stainless Steel Treads	0312224	1	13,500	0,079

COMBINED 316 MODEL WITH STAINLESS STEEL TREADS.



Zinc Anode

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312311	1	10,100	0,118
• With 3 Stainless Steel Treads	0312312	1	11,600	0,118
• With 4 Stainless Steel Treads	0312313	1	13,200	0,118
• With 5 Stainless Steel Treads	0312314	1	14,700	0,118

PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.







Pool Ladders - Commercial Pools














Number of Treads	Α	В	С	D	E	F
2	700	690	250	700	190	500
3	700	690	250	950	190	500
4	700	690	250	1200	190	500
5	700	600	250	1/50	100	500

_	_							
	N	lumber of Treads	А	В	С	D	E	F
		2	330	670	250	700	190	500
		3	330	670	250	950	190	500
	L	4	330	670	250	1200	190	500
1	Г	5	330	670	250	1450	190	500

1	N	Number of Treads	А	В	С	D	Е	F	G
1	Γ	2	210	690	250	630	190	500	640
]		3	210	690	250	880	190	500	640
]		4	210	690	250	1130	190	500	640
	L	5	210	690	250	1380	190	500	640

500 mm width. The treads are made of AISI 304 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 304 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Manufactured with double safety tread in accordance to EN 13451-2/AC standard.

STANDARD 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0311111EU	1	11,400	0,122
• With 3 Stainless Steel Treads	0311112EU	1	13,100	0,122
• With 4 Stainless Steel Treads	0311113EU	1	14,500	0,122
• With 5 Stainless Steel Treads	0311114EU	1	16,000	0,139

U 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311211EU	1	10,000	0,071
• With 3 Stainless Steel Treads	0311212EU	1	11,400	0,071
With 4 Stainless Steel Treads	0311213EU	1	13,000	0,071
• With 5 Stainless Steel Treads	0311214EU	1	14,300	0,079

COMBINED 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Code	Pieces/ box	Weight Kg	Volume m ³
0311311EU	1	10,900	0,118
0311312EU	1	12,400	0,118
0311313EU	1	14,000	0,118
0311314EU	1	15,500	0,118
	0311311EU 0311312EU 0311313EU	Code box 0311311EU 1 0311312EU 1 0311313EU 1	box Kg 0311311EU 1 10,900 0311312EU 1 12,400 0311313EU 1 14,000



Zinc Anode

PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.







Pool Ladders - Commercial Pools














Number of Treads	А	В	С	D	E	F
2	700	690	250	700	190	500
3	700	690	250	950	190	500
4	700	690	250	1200	190	500
5	700	690	250	1450	190	500

Number of Treads	А	В	С	D	E	F
2	330	670	250	700	190	500
3	330	670	250	950	190	500
4	330	670	250	1200	190	500
5	330	670	250	1450	190	500

Number of Treads	А	В	С	D	E	F	G
2	210	690	250	630	190	500	640
3	210	690	250	880	190	500	640
4	210	690	250	1130	190	500	640
5	210	690	250	1380	190	500	640

500 mm width. The treads are made of AISI 316 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 316 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Manufactured with double

safety tread in accordance to EN 13451-2/AC standard.

STANDARD 316 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0312111EU	1	11,800	0,122
• With 3 Stainless Steel Treads	0312112EU	1	13,500	0,122
• With 4 Stainless Steel Treads	0312113EU	1	14,900	0,122
With 5 Stainless Steel Treads	0312114EU	1	16,400	0,139

U 316 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312211EU	1	10,400	0,071
• With 3 Stainless Steel Treads	0312212EU	1	11,800	0,071
With 4 Stainless Steel Treads	0312213EU	1	13,400	0,071
With 5 Stainless Steel Treads	0312214EU	1	14,700	0,079

COMBINED 316 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0312311EU	1	11,300	0,118
• With 3 Stainless Steel Treads	0312312EU	1	12,800	0,118
• With 4 Stainless Steel Treads	0312313EU	1	14,200	0,118
• With 5 Stainless Steel Treads	0312314EU	1	15,900	0,118



Zinc Anode


PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.






Pool Ladders





Number of Treads	А	B1	B2	С	D	E	F		
2	700	690	980	250	730	190	500		
3	700	690	980	250	980	190	500		
4	700	690	980	250	1230	190	500		
5	700	600	080	250	1/80	100	500		





	Number of Treads	А	В	С	D	E	F	J
	2	1020	650	250	750	190	500	100
	3	1020	650	250	1000	190	500	100
	4	1020	650	250	1250	190	500	100
	5	1020	650	250	1500	190	500	100



F A A Flanged Type (Optional)

Number of Treads	А	В	С	D	E	F	J
2	1020	670	250	770	440	500	150
3	1020	670	250	1020	615	500	150
4	1020	670	250	1270	790	500	150
5	1020	670	250	1520	965	500	150

500 mm width. The treads are made of AISI 304 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 304 grade polished stainless steel pipe. Manufactured with double safety tread in accordance to EN 13451-2/AC standard. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.



Zinc Anode

ASYMMETRIC 304 MODEL WITH STAINLESS STEEL TREADS.

Description	Code		ight Volume (g m³
• With 2 Stainless Steel Treads	0311811	1	0,247
With 3 Stainless Steel Treads	0311812	1	0,247
With 4 Stainless Steel Treads	0311813	1	0,247
• With 5 Stainless Steel Treads	0311814	1	0,271

OVERFLOW 304 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0311411	1	12,500	0,247
• With 3 Stainless Steel Treads	0311412	1	13,700	0,247
• With 4 Stainless Steel Treads	0311413	1	15,100	0,247
With 5 Stainless Steel Treads	0311414	1	17,000	0,271

EASY ACCESS 304 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311511	1		
With 3 Stainless Steel Treads	0311512	1		
With 4 Stainless Steel Treads	0311513	1		
With 5 Stainless Steel Treads	0311514	1		


PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.




Pool Ladders









F A A Flanged Type (Optional)

F A Flanged Type (Optional)

Number of Treads	Α	B1	B2	С	D	E	F
2	700	690	980	250	730	190	500
3	700	690	980	250	980	190	500
4	700	690	980	250	1230	190	500
-	700	/00	000	050	4.400	400	500

	Number of Treads	А	В	С	D	E	F	J
1	2	1020	650	250	750	190	500	100
1	3	1020	650	250	1000	190	500	100
	4	1020	650	250	1250	190	500	100
ı	5	1020	650	250	1500	190	500	100

Number of Treads	A	В	С	D	E	F	J
2	1020	670	250	770	440	500	150
3	1020	670	250	1020	615	500	150
4	1020	670	250	1270	790	500	150
5	1020	670	250	1520	965	500	150

500 mm width. The treads are made of AISI 316 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 316 grade polished stainless steel pipe. Manufactured with double safety tread in accordance to EN 13451-2/AC standard. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

ASYMMETRIC 316 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Volume Kg m ³
• With 2 Stainless Steel Treads	0312811	1	0,247
• With 3 Stainless Steel Treads	0312812	1	0,247
With 4 Stainless Steel Treads	0312813	1	0,247
• With 5 Stainless Steel Treads	0312814	1	0,271

OVERFLOW 316 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312411	1	12,500	0,247
With 3 Stainless Steel Treads	0312412	1	13,700	0,247
With 4 Stainless Steel Treads	0312413	1	15,100	0,247
With 5 Stainless Steel Treads	0312414	1	17,000	0,271

EASY ACCESS 316 MODEL WITH STAINLESS STEEL TREADS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 2 Stainless Steel Treads	0312511	1		
• With 3 Stainless Steel Treads	0312512	1		
With 4 Stainless Steel Treads	0312513	1		
 • With 5 Stainless Steel Treads	0312514	1		











Pool Ladders - Commercial Pools





Number of Treads	Α	B1	B2	С	D	E	F
2	700	670	965	250	720	180	500
3	700	670	965	250	980	180	500
4	700	670	965	250	1260	180	500
5	700	670	965	250	1470	180	500





Number of Treads	А	В	С	D	E	F
2	1020	660	250	650	180	500
3	1020	660	250	900	180	500
4	1020	660	250	1240	180	500
5	1020	660	250	1425	180	500

ASYMMETRIC 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

500 mm width. The treads are made of AISI 304 grade stainless steel and feature anti-slip surface.

The handrails are made of Ø42 mm AISI 304 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Manufactured with double safety tread in accordance to EN 13451-2/AC standard.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311811EU	1		
With 3 Stainless Steel Treads	0311812EU	1		
With 4 Stainless Steel Treads	0311813EU	1		
• With 5 Stainless Steel Treads	0311814EU	1		

OVERFLOW 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311411EU	1	13,700	0,247
• With 3 Stainless Steel Treads	0311412EU	1	14,900	0,247
• With 4 Stainless Steel Treads	0311413EU	1	17,300	0,247
• With 5 Stainless Steel Treads	0311414EU	1	19,200	0,271




Zinc Anode

PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.




Pool Ladders - Commercial Pools





U U				E	<u> </u>	
Number of Treads	А	В	С	D	E	F
2	1020	660	250	650	180	500
3	1020	660	250	900	180	500
4	1020	660	250	1240	180	500
5	1020	660	250	1425	180	500





Number of Treads	А	B1	B2	С	D	E	F
2	700	670	965	250	720	180	500
3	700	670	965	250	980	180	500
4	700	670	965	250	1260	180	500
5	700	670	965	250	1470	180	500

ASYMMETRIC 316 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

500 mm width. The treads are made of AISI 316 grade stainless steel and feature anti-slip surface.
The handrails are made of

The handrails are made of Ø42 mm AISI 316 grade polished stainless steel pipe. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Manufactured with double safety tread in accordance to

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312811EU	1		
• With 3 Stainless Steel Treads	0312812EU	1		
• With 4 Stainless Steel Treads	0312813EU	1		
With 5 Stainless Steel Treads	0312814EU	1		

OVERFLOW 316 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312411EU	1	14,100	0,247
• With 3 Stainless Steel Treads	0312412EU	1	15,300	0,247
With 4 Stainless Steel Treads	0312413EU	1	16,700	0,247
 With 5 Stainless Steel Treads 	0312414EU	1	19,600	0.271



EN 13451-2/AC standard.

Zinc Anode

PS: It is functional with an anchor suitable for ladder grounding. For ladders with zinc anode protection, please add "Z" at end of product code.



Volume

 \mathbf{m}^3

5,000

Grab Rails for Split Model Pool Ladders

Description

Steep Grab Rail: 510 x 800 mm. Made of \emptyset 42 mm AISI 304 stainless steel pipe. Complete with fixing plates, bolts and bolt plugs.

Code

Pieces/

box

Weight

Kg

5,000

Weight Kg

5,000

Volume

5,000

Pieces/

box




Set of 2			03322
Set Of 2	800	510	03322
	+	150	<u>)</u>

Deep Grab Rail: 800 x 800 mm. Made of \emptyset 42 mm AISI 304 stainless steel pipe. Complete with fixing plates, bolts and bolt plugs.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Set of 2	03323	1	5,000	5,000





Cross Grab Rail: Ø42 mm. Made of Ø42 mm AISI 304 stainless steel pipe. Complete with monoblock rectangular fixing plate, bolts and bolt plugs.

Code

03324

Description
Set of 2
1030






Pool Ladders

SPLIT 304 MODEL WITH STAINLESS STEEL TREADS.

500 mm width. Treads in AISI 304 grade stainless steel and anti-slip. Handrails made of Ø42 mm pipe are in AISI 304 grade polished stainless steel. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

_							
	Number of Treads	Α	В	С	Е	F	J
	2	250	50	250	190	500	100
	3	250	50	250	190	500	100
Γ	4	250	50	250	190	500	100
	5	250	50	250	190	500	100



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311711	1	12,500	0,247
• With 3 Stainless Steel Treads	0311712	1	13,700	0,247
• With 4 Stainless Steel Treads	0311713	1	15,100	0,247
• With 5 Stainless Steel Treads	0311714	1	17,000	0,271



500 mm width. Treads in AISI 316 grade stainless steel and anti-slip. Handrails made of Ø42 mm pipe are in AISI 316 grade polished stainless steel. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0312711	1	12,500	0,247
• With 3 Stainless Steel Treads	0312712	1	13,700	0,247
• With 4 Stainless Steel Treads	0312713	1	15,100	0,247
With 5 Stainless Steel Treads	0312714	1	17.000	0.271

SPLIT 304 MODEL WITH STAINLESS STEEL TREADS - FOR PUBLIC POOLS.

500 mm width. Treads in AISI 304 grade stainless steel and anti-slip. Handrails made of Ø42 mm pipe are in AISI 304 grade polished stainless steel. Complete with plastic anchors, anchor escutcheons, end caps, bolts and nuts. Manufactured with double safety tread in accordance to EN 13451- 2/AC standard.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With 2 Stainless Steel Treads	0311711EU	1	12,900	0,247
• With 3 Stainless Steel Treads	0311712EU	1	14,100	0,247
• With 4 Stainless Steel Treads	0311713EU	1	15,500	0,247
• With 5 Stainless Steel Treads	0311714EU	1	17,400	0,271








Pool Ladders for Disabled Persons



INCLINED 304 MODEL STAINLESS STEEL POOL LADDER - WIDTH=500 mm.

For easy entry and exit in to and out from leisure or hydrotherapy pools for people not requiring a hydraulic lift chair. Handrails made of Ø42 mm pipe are in AISI 304 grade polished stainless steel. Complete with anti-slip stainless steel treads plastic anchors, anchor escutcheons, end caps, bolts and nuts.





Number of Treads	Height H	Length L
4	950 - 1150	1290
5	1175 - 1375	1550
6	1400 - 1600	1810
7	1625 - 1825	2070
8	1850 - 2050	2330



Description	Code	Pieces/ Weight box Kg	Volume m ³
With 4 Stainless Steel Treads	0311611	1	
With 5 Stainless Steel Treads	0311612	1	
With 6 Stainless Steel Treads	0311613	1	
With 7 Stainless Steel Treads	0311614	1	
With 8 Stainless Steel Treads	0311615	1	

PS: For 316 stainless steel P.A.P.

INCLINED 304 MODEL STAINLESS STEEL POOL LADDER - WIDTH=970 mm.

For easy entry and exit in to and out from leisure or hydrotherapy pools for people not requiring a hydraulic lift chair. Handrails made of Ø42 mm pipe are in AISI 304 grade polished stainless steel. Complete with anti-slip stainless steel treads plastic anchors, anchor escutcheons, end caps, bolts and nuts.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
With 4 Stainless Steel Treads	0311621	1		
With 5 Stainless Steel Treads	0311622	1		
With 6 Stainless Steel Treads	0311623	1		
• With 7 Stainless Steel Treads	0311624	1		
With 8 Stainless Steel Treads	0311625	1		

PS: For 316 stainless steel P.A.P.






Handrails for Concrete Steps

IN-POOL HANDRAIL. Made of AISI 304 grade polished stainless steel Ø42 mm pipe. Complete with fixing plates and screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 1220 mm	03311	1	7,000	0,237
• Length: 1524 mm	03312	1	8,000	0,261






L	А	В
1220	800	680
1524	800	855

OUT-POOL HANDRAIL. Made of AISI 304 grade polished St. steel Ø42 mm pipe. Complete with fixing plates and screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Length: 1250 mm	03321	1	5,000	0.060





А	В	С
1250	850	200

LATERAL GRAB RAIL WITH FIXING PLATES. Made of AISI 304 grade polished stainless steel Ø42 mm pipe. Complete with fixing plates and screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 0.5 m	03331	1	2,000	0,019
• Length: 1.0 m	03332	1	3,000	0,037
• Length: 2.0 m	03333	1	7,500	0,072
• Length: 2.5 m	03334	1	9,000	0,089




LIFEGUARD SEAT.

AISI 304 grade polished stainless steel Ø42 mm pipe.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Model 2	14671	1		









Ladder Accessories



LADDER ANCHOR. Made of plastic for Ø42 mm pipe, grounding connection is optional.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Solid plastic for Ø42 mm pipe.	03201		0,142	
Stainless steel anchor	03201S			
• Ditto, 316 K	03201S01			

PS: Please place special order for anchor models with ground connection.

ANCHOR ESCUTCHEON

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Made of AISI 304 grade polished	032021			
stainless steel, price per piece				

LADDER TREADS



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Made of AISI 304 St. steel with	032031	1		
anti-slip pad for Ø42 mm handrails, w	vidth 500 mm			
Ditto, Inclined	0320311	1		
 Made of AISI 304 St. steel with 	032032	1		
anti-slip pad for Ø38 mm handrails, w	vidth 500 mm			
Ditto, Inclined	0320321	1		
• Double Tread.Made of AISI 304 St.	032033	1		
steel with anti-slip pad for Ø42 mm h	andrails, width 500 mm			
Ditto Inclined	0320331	1		

ARTICULATED ANCHOR

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Made of AISI 304 grade St.steel	03210		0,602	
for Ø42 mm handrails. Price per piece				



03204


Dos

END CAP

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Flexible for Ø42 mm pipe.	03204			
Price per piece				
 Swivel foot pad for Ø42 mm pipe. 	03205			
Angle can be adjusted by rotating the	eve hall socket. Price per piece			



ZINC ANODE FOR LADDER PROTECTION



PS: It is functional with an anchor suitable for ladder grounding.





Pool Lift for Disabilities

Pool lift for disabilities: Hydraulic lift made of AISI 316 stainless steel. Garden irrigation hose has to be connected to hydraulic lift. Required minimum water pressure is 3,5 kg/cm². User friendly installation and can easily be adapted to existing pool.

osor menary installation and sally be dadpted to existing pool.					
Description	Code	Pieces/ Weight Volume box Kg m³			
Pool lift for disabilities	04101	1			
900 705 50 30 ANKRAJ 45 540	500	735			
95 100 365 660	1730				



Disabled Lift Rechargeable

Disabled Lift Rechargeable: The stainless steel rechargeable disabled elevator is crafted from high-quality materials with specific features for enhanced functionality and durability. Key attributes include corrosion resistance to water and high temperatures, a rechargeable and removable battery system, a digital battery charge indicator for user awareness, and a convenient charging device. The elevator is designed for practical installation, easily adaptable to existing pool systems. Overall, it presents a reliable, long-lasting, and user-friendly solution.

Description	Code	Pieces/ box	Weight Kg	Volume m ³	
Disabled Lift Rechargeable	04104	1			
490 ± 20 000 ±	1030 ±50		JIED TRADE		445 ± 3 445 ± 3 5 ± 9 ± 0.02 5 ± 0.



Pool Lift for Disabilities - Stretcher



	hose has to be conn	ected to a hydraulic lift. Red	304 stainless steel. Garden irriga quired minimum water pressur y be adapted to an existing pool
1	Description	Code	Pieces/ Weight Volu box Kg m ³
	Pool lift for disabilities - S 900 705 ANKRAJ 95 100 365 660 16	Stretcher 04103	box kg m
1			



















Pool Showers


Shower Tunnels. For public pools, made of AISI 304 stainless steel. Complete with photocell and solenoid valve, associated with control column.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3 Shower 1 arch. Width: 1,2 m	03641	1		
• 5 Shower 1 arch. Width: 1,2 m	03642	1		
• 2 Arched. Each arch has 3 showers	03643	1		
Width:1,2 m, Lateral acrylic transparent p	anels, Maximum height: 2	2,5 m, Lenght:	2,1 m	
Stainless Steel Showers				
Single shower, box profile body	03645	1		
• Same, also with foot washing tap.	03645A	1		
• Cobra shower, with foot washing tap.	03648A	1		
 Single head shower, baston type. 	03647	1		
• 4 head shower, with foot washing tap.	03644	1		
• Same, with electric heater, hot and cold	03656	1		






water mixing possible.








Pool Slides

SLIDES. Pool slide made of FRP. Complete with the hose system to connect to the pool supply line. Handles are AISI 304 grade stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slide, curved to left	03520	1	83,000	2,913
Slide, curved to right	03521	1	83,000	2,913









Diving Boards

S - DIVING BOARD Made in laminated polyester and fiberglass.


1600 +10



CLASSIC 200 DIVING BOARD Base and board made in laminated polyester and fiberglass.



CLASSIC 200 HR DIVING BOARD Base and board made in laminated polyester and fiberglass. Complete with stainless steel handrails.



Stainless Steel Maintenance and Cleaning Chemicals

Complete box set including cleaning sponge and plastic gloves. Can be used for any kind of stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Kit 1, Rust Remover + Protector	031001	1		
• Kit 2, Rust Remover + Protector + Polisher	031002	1		





Overflow Grating

"MODEL 2018" Overflow Grating

Made of PP plastic; modular with a single joint. "I" shaped profile. Height: 33 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 20 cm (price per meter)	0372232	5 m		
• Width: 25 cm (price per meter)	0372332	5 m		




MODEL 2001 OVERFLOW GRATING - DOUBLE JOINT

Made of PP plastic; modular with two joints. "I" shaped profile.

Height: 25 mm. Price per meter.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Classical Design Width: 20 cm	0372221	10 m	13,000	0,062
Classical Design Width: 25 cm	0372321	10 m	13,000	0,062
Classical Design Width: 30 cm	0372421	10 m	13,500	



MODEL 2001 OVERFLOW GRATING - SINGLE JOINT

Made of PP plastic; modular with single joint. "I" shaped profile.

Height: 25 mm. Price per meter.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Classical Design Width: 15 cm	0372211	10 m	11,900	0,044
Classical Design Width: 20 cm	0372212	10 m	11,500	0,062
Classical Design Width: 25 cm	0372312	10 m	13,100	0,062




"MODEL GEMAS-FUTURO" OVERFLOW GRATING

Modular, plastic product. Adaptable to all types of pool shapes.

Height: 25 mm. Price per meter.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Modular Plastic Width: 20 cm	037321K	10 m	15,400	0,067



"MONOBLOCK" Overflow Grating

Single Joint. six pieces, "T" shaped plastics, grating height: 22 mm. Price per meter.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 20 cm	037321	10 m	11,700	0,062
• Width: 25 cm	037331	10 m	18,320	0,061





Overflow Grating



"MODEL GEMAS SQUARE" OVERFLOW GRATING

Plastic modular, single joint. "I" shaped profile. Height: 25 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 20 cm (price per meter)	0372212K	1	14,000	0,051
• Width: 25 cm (price per meter)	0372213K	1	19,050	0,051

Overflow - For Strip Led Implementation



"Model GEMAS - Transparent Squared" Overflow Grating

Made of polycarbonate, modular with single joint. "I" shaped profile. Squared upper surface. Height: 25 mm. Designed for strip LED implementation inside the overflow grating channel (It's recommended to use IP68 strip LED)


100000	STORESOCKER	ининенный

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 20 cm (price per meter)	0372212KT	1	14,000	0,051
• Width: 25 cm (price per meter)	0372213KT	1	19,050	0,051










Corner Tiles for Overflow Grating



CORNER TILES 90° PLASTIC.

Corner Tile made of PP plastic for an angle of 90 Degrees.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 25 cm	037431	20	9,960	0,048
• 20 cm	037421	25	8,800	0,038
• 25 cm - Transparent	037431T	20		
• 20 cm - Transparent	037421T	25		
• 15 cm	037411	20	4,438	0,019
• 25 cm H:33 mm	037434	20		
• 20 cm H:33 mm	037433	25		
• 30 cm	037413			



CORNER TILES 45° PLASTIC.

Corner Tile made of PP plastic for an angle of 45 Degrees.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 25 cm H:33 mm	037432	20	6,950	0,042
• 20 cm H:33 mm	037422	20	4,470	0,028
• 25 cm - Transparent	037432T	20		
• 20 cm - Transparent	037422T	20		
• 15 cm	037412	10	1,636	0,008
• 30 cm	037414			

Grating Support Profile

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Overflow Support Profile	03750	100 m	18,170	0,051
PVC, 23 x 26 mm (Price per meter)		(2 m x 50)		
• Same, 33 x 25 mm (Price per meter)	03751	100 m (2 m x 50)		






Stainless Steel Overflow Gratings

Made of AISI 304 grade stainless steel. Length: 0,50 m monoblock grating. Standard antislip pattern.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Width: 25 cm (price per meter) - 2 pcs.	0372221SS1	1		





Description	Code	Pieces/ box	Weight Kg	Volume m ³
Width: 25 cm (price per meter) - 2 pcs.	0372221SS2	1		

PS: Prices are for Standard Pattern. Prices of Point and Leather Patterns are 20% higher.



Point Pattern

Stainless Steel Corner Tiles for Overflow Gratings

Corner Tiles, 90° - Stainless Steel

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 25 cm AISI 304 grade	037421SS1			
• 25 cm AISI 316 grade	037421SS2			





Standard Pattern Leather Pattern Grating

Point Pattern

Grating



Grating And Corner Tile Detail

Grating



Strainer for Overflow Gutter Drain



Made in stainless steel adjustable to drain pipes in gutter.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• for Ø63 mm pipe	03801	1		
• for Ø75 mm pipe	03802	1		
• for Ø90 mm pipe	03803	1		
• for Ø110 mm pipe	03804	1		
 Plastic - for up to Ø110 mm pipe 	03811	1		



OVERFLOW GUTTER DRAIN.

Made of white ABS plastic. 2,5" male - threaded, Ø63 mm inside. Stainless steel screws included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04150	50	11,000	0,067

Foot Bath



Foot washing bath, made of fiberglass reinforced polyester, for disinfection of feet before entering pool.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 52,50 x 37,50 x 8,75 cm	03900	1	1,270	0,021
• 85,00 x 65,00 x 9,00 cm	03902	1		
• 120,00 x 80,00 x 9,00 cm	03901	1		





Hatch for Engine Room

Hatch for engine room: Made of FRP, plastic hinged lid complete with steel reinforcements and locking mechanism.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 50 x 50 cm	03911	1	7,000	0,040
• 75 x 75 cm	03912	1	14,000	0,080
• 100 x 100 cm	03913	1	19.000	0.140

CODE	Inner Size (cm)	Outer Size (cm)
03911	50 x 50	66 x 66
03912	75 x 75	88 x 88
03913	100 x 100	123 x 123






Inox handle with key lock

Double piston

Pool Side Anti Slip MAT

Plastic anti slip MAT for pool decks. Width: 0,9 m. 15 m rolled.

Description	Code	Pieces/ Weight Volume box Kg m³
Red. Price per meter	03011	1 Roll
Blue. Price per meter	03012	1 Roll
Green. Price per meter	03013	1 Roll








I.T.U. Olympic Pool / Istanbul





Skimmers for Concrete Pools


All skimmer models are made in ABS plastic and equipped with "suction regulator" and locking mechanism of baskets against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 1,5" female threaded (2" also possible upon request), \emptyset 63 mm external slip. Second port: \emptyset 50 mm female slip. Overflow drainage: \emptyset 40 mm female slip.











Description	Code	Pieces/ box	Weight Kg	Volume m ³
Standard				
Standard squared lid skimmer	04111	1	3,036	0,054
Ditto, w/floating weir	04111FW	1	2,840	0,054



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Extended Throat (+10 cm)				
Standard extended	04111E	2	6,372	0,107
Ditto, w/floating weir	04111EFW	2	5,942	0,107



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Wide Mouth				
Wide mouth squared lid skimmer	04112	2	8,000	0,137
Ditto, w/floating weir	04112FW	2	7,524	0,137





Lux-Skimmers for Concrete Pools


All Lux-Skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism of baskets against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 2" female threaded. Second port: 1,5" female threaded supplied with blind cap. Overflow drainage: Ø40 mm female slip.

Additional Features:

- Child-proof decklid features safety locking mechanism.
- Extension collar allows for correction with uneven deck finishes.
- Locking basket design prevents basket floating due to back pressure.
- Locking vacuum adapter prevents adapter plate floating during suction cleaning.
- Extended throat facilitates convenient installation in the pool wall (Optional).
- Aesthetic face plate in the pool.









Locked basket datail




Lockable lid for child protection

		m ³				
Lux Extended Throat (+10 cm)	Lux Extended Throat (+10 cm)					
• Lux standard extended 04121E 2 4,350 0	 Lux standard extended 	0,108				
• Ditto, w/floating weir 04121EFW 2 4,150 0	Ditto, w/floating weir	0,108				



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Lux Wide Mouth				
Lux wide mouth squared lid skimmer	04122	2	4,610	0,108
• Ditto, w/floating weir	04122FW	2	4,378	0,108





Pieces/ Weight

Elevated Wide Mouth Skimmers for Concrete Pools

S


Elevated Skimmer raises the pool water level by 5 cm compared to normal skimmers.

All skimmer models are made in ABS plastic and equipped with "suction regulator" and locking mechanism of baskets against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 1,5" female threaded (2" also possible upon request), Ø63 mm external slip. Second port: Ø50 mm female slip. Overflow drainage: Ø40 mm female slip.



Elevated wide mouth for high water level

Description	Code	box	Kg
Elevated Standard Wide Mouth Skimmer	04115FW	1	
Complete Elev. Std. Wide Skimmer Anthracite - RAL 7016	04115FWA	1	
Complete Elev. Std. Wide Skimmer Beige - RAL 1015	04115FWB	1	
Complete Elev. Std. Wide Skimmer Gray - RAL 7004	04115FWG	1	



Lux-Elevated Wide Mouth Skimmers for Concrete Pools



RAL 7016

All Lux-Skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism of baskets against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 2" female threaded. Second port: 1,5" female threaded supplied with blind cap. Overflow drainage: Ø40 mm female slip.

Additional Features:

Child-proof decklid features safety locking mechanism.


 Child-proof decklid features safety locking mechanism.

• Extension collar allows for correction with uneven deck finishes.

Locking basket design prevents basket floating due to back pressure.
 Locking vacuum adapter prevents adapter plate floating during suction cleaning.
 Extended throat facilitates convenient installation in the pool wall (Optional).




Description	Code	Pieces/ Weight box Kg
Elevated Standard Wide Mouth Skimmer	04125FW	1
Complete Elev. Lux Wide Skimmer Anthracite - RAL 7016	04125FWA	1
Complete Elev. Lux Wide Skimmer Beige - RAL 1015	04125FWB	1
Complete Elev. Lux Wide Skimmer Gray - RAL 7004	04125FWG	1






Skimmers - Level Regulator

Automatic Level Regulator. Body is made of ABS plastic. Complete with 3/8" plastic floating valve and Ø50 mm PVC slip connection, either side or bottom alternatively.











Description	Code	Pieces/ box	Weight Kg	Volume m ³
Automatic Level Regulator	04120	1	1,600	0,021
Ditto, with locking decklid	04120L	1	1,650	0,021

Skimmers - Optional Parts

Face Plate for Concrete or Liner Standard Skimmer. Made of ABS plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Face Plate Skimmer Standard	0412102	1	0,300	0,003
Face Plate Skimmer Anthracite - RAL 7016	0412102A	1	0,300	0,003
Face Plate Skimmer Beige - RAL 1015	0412102B	1	0,300	0,003
• Face Plate Skimmer Gray - RAL 7004	0412102G	1	0,300	0,003



Skimmer Extension Collar. Made of ABS plastic for 4,5 cm vertical modular extension.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Skimmer Extension Collar	04111E01	1	0,188	0,003
• Skimmer Extension Collar Anthracite - RAL 7016	04111E01A	1	0,188	0,003
Skimmer Extension Collar Beige - RAL 1015	04111E01B	1	0,188	0,003
Skimmer Extension Collar Gray - RAL 7004	04111E01G	1	0,188	0,003



Skimmer Horizontal Extension. Made of ABS plastic. Compatible with all GEMAS skimmer models. Extends each model by 10,5 cm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Skimmer Horizontal Extension	04111E10	1		





Skimmers - Optional Parts



Skimmer Angle Horizontal Extension.

Made of ABS plastic. Compatible with all GEMAS skimmer models. Each model (models can be added together) provides 30 mm extension in the middle axis and 5° inclined pool surface adaptations designed for polyester and slope pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04111E03	1		

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.



Decklid with Safety Locking Mechanism. Made of ABS plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	0412101	1		

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.



Buoy Float. Made of ABS plastic. Complete with the ring.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04110BF	1	0,364	0,006

PS. Designed for replacing skimmer floating weir. Releases trapped debris when the pump stops.

Return Inlets (Concrete Pools) - ABS



Wall Inlet for Concrete Pools.

Injected of white ABS plastic with adjustable ball for alternative discharges.





Ø14 mm ball 3 m³/h Ø20 mm ball 5 m³/h Ø25 mm ball 7 m³/h



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded :	04131T	10	1,000	0,006
Ø50 mm internal slip connection.				
• 2" Slip to be glued inside Ø63 mm	04131S	10	1,000	0,006
(10 atm) pipe.				
• 1,5" Slip to be glued inside	04131S1			
Ø50 mm (10 atm) pipe.				
Breaking Tool	04131T05			

 $\textbf{PS:} \ \ \textbf{Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. \\ \textbf{Prices will be 10\% more expensive.}$



Breaking tool


Return Inlets (Concrete Pools) - ABS

Wall Inlet for Concrete Pools, according to EU 13451-1/4.8.3 Injected of white ABS plastic with protection and adjustable ball for alternative discharges.





	Ø14 mm ball 3 m ³ /h
	Ø20 mm ball 5 m ³ /h
8	Ø25 mm ball 7 m ³ /h



PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.



Suction Inlet for Concrete Pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded :	04134T	10	0,900	0,006
Ø50 mm internal slip connection.				
• 2" Slip to be glued	04134S	10	0,900	0,006
inside Ø63 mm (10atm) pipe.				
Slip to be glued	04134S1			
inside Ø50 mm (10atm) pipe.				

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.






Wall Conduit for Concrete Pools. Injected of white ABS plastic. Pipe connection side is Ø63 mm externally and Ø50 mm internally. Overall length is 30 cm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded: Pool side 2" Female thr.	04160T	20	8,700	0,060
Ditto, with nozzle seat	04260T1			
Ditto, back outlet 2" Male threaded	04160T1	20	8,700	0,060
• Ditto, with Protection plugs	04160TP	20	9,200	0,014
Pool side for slip	04160S	20	8,700	0,060
connection. (i.e same size with internal dia of Ø63 mm (10atm) PVC pipe.)				





Return Inlets (Concrete Pools) - ABS







AD



EU 13451-¼.8.3" male threaded, Ø50 mm internal slip connection. Discharge can be regulated by means of an inner lid which can be screwed up and down.

Description

Code

Pieces/ Weight Volume

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Flat Lid - 2" Male Threaded	04132TF	8	1,430	0,006
Flat Lid - Slip, to be	04132SF	8	1,400	0,006
glued inside Ø63 mm (10 atm) pipe.				
Conical Lid - 2" Male Threaded	04132TC	8	1,300	0,006
Conical Lid - Slip, to be	04132SC	8	1,600	0,006
glued inside Ø63 mm (10 atm) pipe.				

Floor Inlet - Adjustable for Concrete Pools. Injected of white ABS plastic, according to

Floor Inlet - Adjustable (AD) and Constant (CD) Discharge for Concrete Pools. Made of ABS plastic. Distributes water at an angle of 45°. All slip connections are for 10 atm PVC pipes.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded - CD	04133T	10	0,930	0,007
• Ditto, AD	04133T4			
• 2" Slip - CD	04133S	10	0,912	0,007
• Ditto, AD	04132S4			
• 1,5" Slip - CD	04133S1			

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.



041331S




041321S



Eccentric Floor Inlet Special inlet nozzle to be installed inside Ø63-10 bar PVC pipe, for inclined pool bottom.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Slip - CD	041331S			
• 2" Slip - AD	041321S			

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expencia.





Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04150	50	11,000	0,067



Balance Tank Basket. Made of white ABS plastic. Adjustable up to Ø125 mm diameter PVC overflow pipes.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04151	1		



Junction Box

Junction Box. Made of white ABS plastic. Connections are for "05051" conduits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	05040	8	2,610	0,016


PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.



Main Drains (Concrete Pools) - ABS

Circular Main Drain for Concrete Pools. Made of ABS plastic. Grille fixed w/stainless steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Female Thread	04141T1	1	0,832	0,013
• 2" Female Thread	04141T2	1	0,800	0,013
 Ø50 mm Slip Connection 	04141S1	1	0,802	0,013
 Ø63 mm Slip Connection 	04141S2	1	0,776	0,013
 Ø75 mm Slip Connection 	04141S3	1	0,784	0,013





Squared Main Drain. Made of white ABS plastic. Grille fixed w/stainless steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Female Thread	04142T1	1	1,360	0,013
• Ditto, but with extended thread of	04142T1E	1	1,400	0,013
5 cm length facilitating test plug				
• 2,5" Female Thread	04142T2	1	1,590	0,013
3" Female Thread	04143T3	1	1,520	0,013
 Ø63 mm Slip Connection 	04142S1	1	1,352	0,013
Ø75 mm Slip Connection	04142S2	1	1,250	0,013
• Ø90 mm Slip Connection	04142S3	1	1,346	0,013



Grilles for Main Drain (Concrete Pools) - ABS

Circular Grilles. Made of ABS Plastic Circular Grille Ø186-242 mm. Complete with stainless steel screws necessary to fix the frame on concrete. Max. recommended drain pipe size: Ø63 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04143C	1	0,376	0,003

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 15% more expensive.





Grilles for Main Drain (Concrete Pools) - ABS



Squared Grilles for Main Drain for Concrete Pools.

Made of ABS Plastic Squared Grille 26,5 x 26,5 cm.Complete with fixing screws. Max. recommended drain pipe size: Ø90 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04143R1	1	0,954	0,003

PS: Full colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 15% more expensive.



Squared Grilles for Main Drain for Concrete Pools. Fiberglass reinforced polyester frame with ext. dimensions of $60 \times 60 \text{ cm}$ complete with fixing screws. Max. recommended drain pipe size: $\emptyset 225 \text{ mm}$.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04143R2	1	4,200	0,015


St. Steel Skimmers for Concrete Pools



Stainless Steel Skimmer Body - Model 1.

Made of AISI 304 quality stainless steel. Ø50 mm overflow. Skimming width: 190 mm, installation depth: 240 mm. Suction: Ø63 mm PVC. Floater installation option for water level regulation. Earth connection included. Complete with skimmer strainer basket 04111SS01 and level adjustable lid 04111SS02.







Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Model 1	04112SS	1	6,510	0,040
• Ditto, with Floater	04112SSF	1	6,710	0,040




Stainless Steel Skimmer Body for Concrete Pool - Model 2.

Made of AISI 304 quality stainless steel. Ø50 mm overflow. Skimming width: 190 mm, installation depth: 240 mm. Suction: Ø63 mm PVC. Earth connection included. Complete with skimmer strainer basket 04111SS01 and level adjustable lid 04111SS02.







Description	Code	Pieces/ box	Weight Kg	Volume m ³
Model 2	04111SS	1	5,250	0,040



St. Steel Skimmers for Concrete Pools


Stainless Steel Skimmer Strainer Basket for Concrete Pools. Made of AISI 304 quality stainless Steel Complete with face plate for direct removal through skimmer mouth. (Applicable to Model 1 and Model 2).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04111SS01	1	2,190	0,020



Stainless Steel Level Adjustable Lid for Concrete Pools. Made of AISI 304 Stainless steel Dimensions: 180 x 180 mm. Height level can be adjustable from 60 to 110 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04111SS02	1	1,630	0,010



Stainless Steel Skimmer Flange Set for Liner Pools. Made of AISI 304 Stainless steel. Complete with 2 gaskets and bolts.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04211SS01	1	0,780	0,002



Solid Inox Inlets

Full Body made of Stainless Steel.

Ball for wall inlet is from transparent polycarbonate. SS ball is optional. Floor inlets are either adjustable (AD) or constant discharge (CD) types.

Code	Pieces/ box	Weight Kg	Volume m ³
04131TSSM	1		
04134TSSM	1		
04133TSSM	1		
04135TSSM	1		
04131TSSM01	1		
04134TSSM01	1		
04133TSSM01	1		
04135TSSM01	1		
	04131TSSM 04134TSSM 04133TSSM 04135TSSM 04131TSSM01 04134TSSM01 04133TSSM01	Code box 04131TSSM 1 04134TSSM 1 04133TSSM 1 04135TSSM 1 04131TSSM01 1 04134TSSM01 1 04133TSSM01 1 04133TSSM01 1	Code box Kg 04131TSSM 1 04134TSSM 1 04133TSSM 1 04135TSSM 1 04131TSSM01 1 04134TSSM01 1 04133TSSM01 1 04133TSSM01 1



04131TSSM01




04134TSSM01





04135TSSM



Wall Inlet (Concrete Pools) - St. Steel Dressed



Stainless Steel Wall Inlet for Concrete Pools. Body is injected of white ABS plastic dressed with AISI 304 quality stainless steel plate. The butterfly of nozzle is made of solid inox inlets stainless steel and the sphere is of acrylic transparent plastic with adjustable ball for alternative discharges.





Breaking tool



Ø14 mm ball 3 m³/h Ø20 mm ball 5 m³/h Ø25 mm ball 7 m³/h

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded : Ø50 mm	04131TSS	10	2,400	0,006
internal slip connection				
• 2" Slip to be glued inside Ø63 mm pipe	04131SSS			



Stainless Steel Suction Inlet for Concrete Pools.

Body is injected of white ABS plastic dressed with AISI 304 quality stainless steel plate. The blind cap is made of solid inox inlets stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded : Ø50 mm	04134TSS	10	3,572	0,007
internal slip connection.				
• 2" Slip to be glued inside Ø63 mm pipe	04134SSS			



Floor Inlet with Chrome Painted Stainless Steel Lid - Flow Adjustable.

Flat lid of AISI 304 quality stainless steel. Body in ABS plastic.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Flad Lid - 2" Male Threaded :	04132TFSS	8	2,200	0,006
Flat Lid AISI 304 Quality St.Steel				
• 2" Slip to be glued inside Ø63 mm pipe	04132SFSS			



Stainless Steel Floor Inlet - Constant Flow.

Stainless Steel Floor Inlet - Constant Flow. Body in ABS plastic, front face is dressed with AISI 304 quality stainless steel sheet. The central part is solid AISI 304 quality stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male Threaded :	04133TSS	8	2,400	0,007
Ø50 mm internal slip connection				
• 2" Slip to be glued inside Ø63 mm pipe	04133SSS			



Main Drains (Concrete Pools) - St. Steel

Circular Main Drain with St. Steel Grille for Concrete Pools. Body made of ABS plastic. Stainless steel grille fixed w/st. steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Female Thread	04141T1SS	1		
• 2" Female Thread	04141T2SS	1		
• 1,5" glued	04141S1SS	1		
• 2" glued	04141S2SS	1		
• 2,5" glued	04141S3SS	1		



Grilles for Main Drain (Concrete Pools) - St. Steel


Stainless steel circular grilles. Made of AISI 304 quality stainless steel with stainless steel screws Ø186 - 242 mm.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Circular Grille	04143SS	1	0,258	0,003




St. Steel Squared Grilles for Main Drain for Concrete Pools. Frame and grille made of AISI 304 quality stainless steel complete with fixing screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 200 x 200 mm (out)	04143RSS1	1		
• 300 x 300 mm (out)	04143RSS2	1		
• 400 x 400 mm (out)	04143RSS3	1		
• 500 x 500 mm (out)	04143RSS4	1		
• 600 x 600 mm (out)	04143RSS5	1		














Skimmers for Liner Pools



All skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism basket against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 1,5" female threaded (2" also possible upon request), Ø63 mm external slip. Discharge port: Ø50 mm female slip. Overflow drainage: Ø40 mm female slip. Complete with flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.









Description	Code	Pieces/ box	Weight Kg	Volume m ³
Standard Throat				
Standard Squared Lid Skimmer	04211	1	4,104	0,054
Ditto, W/Brass Cavities	04211B	1	4,142	0,054
Standard Squared Lid Skimmer	04211FW	1	3,820	0,054
W/Floating Weir				
Ditto, W/Brass Cavities	04211BFW	1	3,986	0,054



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Extension Throat (+ 10 cm)				
Standard Squared Lid Skimmer	04211E	2	8,504	0,107
Ditto, W/Brass Cavities	04211EB	2	8,600	0,107
Standard Squared Lid Skimmer	04211EFW	2	8,070	0,107
W/Floating Weir				
Ditto, W/Brass Cavities	04211FBFW	2	8.160	0.107



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Wide Mouth				
Wide Mouth Squared Lid Skimmer	04212	2	9,430	0,135
Ditto, W/Brass Cavities	04212B	2	9,678	0,135
Wide Mouth Squared Lid Skimmer	04212FW	2	9,012	0,135
W/Floating Weir				
Ditto, W/Brass Cavities	04212BFW	2	9,112	0,135



Lux Skimmers for Liner Pools

All Lux-Skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism basket against back pressure. Skimming by "buoy float" or "floating weir". Suction port: 2" female threaded. Discharge port: 1,5" female threaded, supplied with blind cap. Overflow drainage: Ø40 mm female slip. Complete with flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.

Additional Features:

- Child-proof decklid features safety locking mechanism.
- Extension collar allows for correction of uneven deck finishes.
- Locking basket design prevents basket floating due to back pressure.
- Extended throat facilitates convenient installation in the pool wall. (Optional)
- Aesthetic face plate in the pool.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Lux Standard Throat				
Lux Standard Squared Lid Skimmer	04221	2	9,150	0,137
Ditto, W/Brass Cavities	04221B	2	9,400	0,137
Lux Standard Squared Lid Skimmer	04221FW	2	8,720	0,137
W/Floating Weir				
Ditto, W/Brass Cavities	04221BFW	2	8,890	0,137



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Lux Extension Throat (+ 10 cm)				
Lux Standard Squared Lid Skimmer	04221E	1	5,600	0,110
Ditto, W/Brass Cavities	04221EB	1	5,700	0,110
Lux Standard Squared Lid Skimmer	04221EFW	1	4,350	0,110
W/Floating Weir				
Ditto, W/Brass Cavities	04221EBFW	1	4,500	0,110

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Lux Wide Mouth				
• Lux Wide Mouth Squared Lid Skimmer	04222	1	5,296	0,110
Ditto, W/Brass Cavities	04222B	1	5,525	0,110
• Lux Wide Mouth Squared Lid Skimmer	04222FW	1	5,250	0,110
W/Floating Weir				
Ditto, W/Brass Cavities	04222BFW	1	5,370	0,110





Pieces/ Weight

Κğ

box

Elevated Wide Mouth Skimmers for Liner Pools

Elevated Skimmer raises the pool water level by 5 cm compared to **normal skimmers**. All skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism basket against

back pressure. Skimming by "buoy float" or "floating weir". Suction port: 1,5"


female threaded (2" also possible upon request), Ø63 mm external slip. Discharge port: Ø50 mm female slip. Overflow drainage: Ø40 mm female slip. Complete with flange, gaskets, stainless steel

screws and front cover.

Pieces/ Weight Flange connections can be with Description Code box Kg brass cavities or plastic nests. • Liner Pools with brass cavities 04215BFW · Liner Pools wout brass cavities 04215FW

> PS: Full colored products can be ordered by adding "A" for Anthracite, "B" for Beige, "G" for Grey. Prices will be 15% more expensive. See below RAL codes. RAL 7016 RAL 1015





Liner Flange, Gasket ans Screws

Lux-Elevated Wide Mouth Skimmers for Liner Pools

All Lux-Skimmer models are made of ABS plastic and equipped with "suction regulator" and locking mechanism basket against back pressure.


Skimming by "buoy float" or "floating weir". Suction port: 2" female threaded.

Discharge port: 1,5" female threaded, supplied with blind cap. Overflow drainage:

Ø40 mm female slip. Complete with flange, gaskets, stainless steel screws and front cover.

Flange connections can be with brass cavities or plastic nests.

Additional Features: • Child-proof decklid features safety locking mechanism. • Extension collar allows for correction with uneven deck finishes. •Locking basket design prevents basket floating due to back pressure. •Locking vacuum adapter prevents adapter plate floating during suction cleaning. • Extended throat facilitates convenient installation in the pool wall (Optional).



ner Pools wout brass cavities	04225FW	1
Full colored products can be ordered by adding s will be 15% more expensive. See RAL codes		
562 495	500	222 35 36 37 38 38 38 38 38 38 38 38 38 38

Code

04225BFW





Mini Skimmers for Liner Pools


All Skimmer models are made of ABS plastic. Suction port: Female threaded 1,5". Complete with vacuum adaptor, flange, gaskets and stainless steel screws.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Standard Mouth Square Lid Skimmer	04213	8	19,500	
Wide Mouth Square Lid Skimmer	04214	8	27,500	













Return Inlets (Liner Pools) - ABS

Wall Inlet for Liner Pools. Injected of white ABS plastic with adjustable ball for alternative discharges. Complete with flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.






Ø14 mm ball 3 m³/h Ø20 mm ball 5 m³/h Ø25 mm ball 7 m³/h



Breaking tool

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male threaded :	04231T	8	1,520	0,006
Ø50 internal slip connection.				
Ditto, W/Brass Cavities	04231BT	8	1,682	0,006
• 2" Male threaded : Also 2" nut included	04231TN		1,800	0,006
Ditto, W/Brass Cavities	04231BTN	8	1,934	0,006
Breaking Tool	04131T05			





Wall Inlet for Liner Pools.

Breaking tool

According to EU 13451-1/4.8.3 Injected of white ABS plastic with protection and adjustable ball for alternative discharges. Complete with flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.





Ø14 mm ball 3 m³/h Ø20 mm ball 5 m³/h Ø25 mm ball 7 m³/h

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male threaded :	04231TP	8	1,460	0,007
Ø50 internal slip connection.				
• Ditto, W/Brass Cavities	04231BTP	8	1,508	0,007
• 2" Male threaded : Also 2" nut included	04231TNP	8	1,750	0,007
Ditto, W/Brass Cavities	04231BTNP	8	1,806	0,007

PS: Colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.





Return Inlets (Liner Pools) - ABS



Specially designed for concrete-shell liner pools. Injected of white ABS plastic with adjustable ball for alternative discharges. Complete with flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.





Ø14 mm ball 3 m³/h Ø20 mm ball 5 m³/h Ø25 mm ball 7 m³/h



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male threaded: Ø50 internal slip con.	04231C	8	1,676	0,006
Ditto, W/Brass Cavities	04231CB	8	1,718	0,006



can be with brass cavities of pias	uc nesis.			
Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Male threaded:	04231CN	8		
Ø50 internal slip connection.				
Ditto, W/Brass Cavities	04231CNB	8		



injected of white ABS plastic. Complete with blind cap, flange, gaskets, stainless steel screws and front cover. Flange connections can be with brass cavities or plastic nests.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
2" Male Threaded: Injected of white	04234T	8	1,500	0,006
ABS plastic.				
Ditto, W/Brass Cavities	04234TB	8	1,600	0,006
• 2" Male Threaded: Injected of white	04234TN	8	1,520	0,006
ABS plastic. Also 2" nut included.				
Ditto, W/Brass Cavities	04234TNB	8	1,732	0,006

PS: Colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.

Floor Inlet - Adjustable for liner pools.

White ABS plastic, according to EU 13451-174.8.3 regulations. 2" male threaded, Ø50 mm internal slip connection. Adjustable flow. Complete with flange gaskets and stainless steel screws.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Flat Lid - 2" Male Threaded	04232TF	4	1,270	0,007
Ditto, W/Brass Cavities	04232TFB	4	1,270	0,007
Conycal Lid - 2" Male Threaded	04232TC	4	1,340	0,007
Ditto, W/Brass Cavities	04232TCB	4	1,308	0,007

PS: Colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.

Clamping nut, 2".

White ABS plastic. 2" Femals threaded.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
 Nut with gasket for wall inlets 	04237	35	1,474	0,006



Main Drains for Liner Pools

Circular Main Drain. Made of white ABS plastic. Grille fixed with stainless steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection. Complete with flange, stainless steel screws and gaskets. **Flange height:** 17,20 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Female Thread	04241T1	1	1,740	0,013
 Ditto, W/Brass Cavities 	04241T1B	1	1,130	0,013
• 2" Female Thread	04241T2	1	1,134	0,013
Ditto, W/Brass Cavities	04241T2B	1	1,572	0,013



PS: Colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.

Circular Main Drain.

Made of white ABS plastic. Grille fixed with stainless steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection. Complete with flange, stainless steel screws and gaskets. Flange height: 6,35 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Thread	04243T1	1	1,034	0,013
 Ditto, W/Brass Cavities 	04243T1B	1	1,034	0,013
• 2" Thread	04243T2	1	1,072	0,013
Ditto, W/Brass Cavities	04243T2B	1	1,072	0,013



PS: Colored products can be ordered by adding "G" for Grey, "B" for Beige, "A" for Anthracite. Prices will be 10% more expensive.

Circular Main Drain with St. Steel Grille for Concrete Pools. Body made of ABS plastic. Stainless steel grille fixed w/st. steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection.


,				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Female Thread	04241T1SS	1		
• 2" Female Thread	04241T2SS	1		



Squared Main Drain.

Made of white ABS plastic. Grille fixed with stainless steel screws, Ø50 mm female slip blind connection at the bottom for hydrostatic valve connection. Complete with flange, stainless steel screws and gaskets.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" Female Thread	04242T1	1	1,600	0,013
Ditto, but with extended threaded	04242T1E	1	1,600	0,013
of 5 cm length facilitating test plug				
Ditto, W/Brass Cavities	04242T1EB	1	1,600	0,013
• 2,5" Female Thread	04242T2	1	1,606	0,013
 Ditto, W/Brass Cavities 	04242T2B	1	1,606	0,013
3" Female Thread	04242T3	1	1,606	0,013
Ditto, W/Brass Cavities	04242T3B	1	1,606	0,013
Ø63 mm Slip Connection	04242A1	1	1,600	0,013
Ditto, W/Brass Cavities	04242A1B	1	1,570	0,013
Ø75 mm Slip Connection	04242A2	1	1,570	0,013
Ditto, W/Brass Cavities	04242A2B	1	1,570	0,013
Ø90 mm Slip Connection	04242A3	1	1,570	0,013
Ditto, W/Brass Cavities	04242A3B	1	1,570	0,013









Underwater Lights for Concrete Pools

New Generation

"SlimLED"

Underwater Light without Niche, Silicone Filled, Single Color.

Frame made of ABS Plastic. Polycarbonate light body with a choice of LED quantities and powers, embedded into a special transparent silicone. Complete with epoxy PCB. 2 x 1,5 mm cable of 2,5 m length. 120° - IP68. Wall mounting is done by fixing the light directly onto the pool wall with stainless steel screws and plugs. Optional wall mounting bracket is available. 2 Year Leakage Warranty.

The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available on the market. **Max. operating temperature 30°**.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	051140	1	1,050	0,005
• 252 LED Daylight - 50 W	051141	1	1,050	0,005
• 81 LED White - 35 W Aluminium PCB	051130	1	1,050	0,005
• 81 LED Daylight - 35 W Aluminium PCB	051131	1	1,050	0,005
Optional Wall Mounting Bracket	051130EY01	1		

Note: Other Single Color prices are the same. The last digit of the product code should be changed to the following - for Turquoise 2, for Blue 3, for Red 4, for Green 5.



"SlimLED" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.


For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Central Control				
• 252 LED RGB, 36 W Aluminium PCB	051155	1	1,050	0,005
• 90 LED RGB-White, 36 W Aluminium PCB	051152	1	1,050	0,005
• 81 LED RGB, 30 W	051157	1	1,050	0,005
Built-in Control				
• 252 LED RGB, 36 W Aluminium PCB	051153	1	1,050	0,005
• 90 LED RGB-White, 36 W Aluminium PCB	051150	1	1,050	0,005
• 81 LED RGB, 30 W	051156	1	1,050	0,005






051130EY01 Optional wall mounting bracket











"New Generation" Underwater Lights for Concrete Pools



Underwater Light without Niche, Single Color.

Frame made of ABS or Transparent Plastic. Complete with 72 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1,5 m length. 120° - IP68. Wall mounting is done by fixing the light directly onto the pool wall with stainless steel screws and plugs. Optional wall mounting bracket is available. The light, without the frame, can be used as a replacement bulb for

LED conversion of all PAR56 products available on the market. Max. operating temperature 30°.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 24 W	051130E0	1	0,835	0,005
• 72 LED Daylight - 24 W	051131E0	1	0,835	0,005
• 72 LED Turquoise - 20 W	051132E0	1	0,835	0,005
• 72 LED Blue - 20 W	051133E0	1	0,835	0,005
• 72 LED Red - 20 W	051134E0	1	0,835	0,005
• 72 LED Green - 20 W	051135E0	1	0,835	0,005
Optional Wall Mounting Bracket	051130EY01	1		




"ECOSlimLED" Underwater Light without Niche; Ditto, but RGB Changing Color.


For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB-Built-in Control-20 W	051150E0	1	0,835	0,005
• 72 LED RGB-Central Control-20 W	051152E0	1	0,835	0,005
• 72 LED RGB-Self Control	051150SCE0	1	0,835	0,005
Optional Wall Mounting Bracket	051130EY01	1	0,835	0,005











051130EY01 Optional wall mounting bracket



Underwater Lights for "New Generation" Concrete Pools

ECOSIim2025 LED

Underwater Light without Niche, Single Color.

Frame made of ABS or Transparent Plastic. Complete with 72 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1,5 m length. 120° - IP68. Wall mounting is done by fixing the light directly onto the pool wall with stainless steel screws and plugs. Optional wall mounting bracket is available. Max. operating temperature 30°.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 24 W	051120E0	1	0,835	0,005
• 72 LED Daylight - 24 W	051121E0	1	0,835	0,005
• 72 LED Turquoise - 20 W	051122E0	1	0,835	0,005
• 72 LED Blue - 20 W	051123E0	1	0,835	0,005
• 72 LED Red - 20 W	051124E0	1	0,835	0,005
• 72 LED Green - 20 W	051125E0	1	0,835	0,005
Optional Wall Mounting Bracket	051130EY01			



"ECOSIm2025 LED" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB-Built-in Control-20 W	051126EO	1	0,835	0,005
• 72 LED RGB-Central Control-20 W	051127E0	1	0,835	0,005
Optional Wall Mounting Bracket	051130EY01			







051130EY01 Optional wall mounting bracket



Underwater Lights for Concrete Pools

New Generation



"MAXI-Clicker"

Underwater light without niche. Single color, frame made of ABS Plastic complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length. 120° - IP68 Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise.



 (ϵ)

2 Year Leakage Warranty.
The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market.

This product is patented.



Patented Bayonet "Click" System


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 35 W Aluminium PCB	051230	1		
• 72 LED Daylight - 35 W Aluminium PCB	051231	1		
• 72 LED Turquoise - 30 W	051232	1		
• 72 LED Blue - 30 W	051233	1		
• 72 LED Red - 30 W	051234	1		
• 72 LED Green - 30 W	051235	1		
• 72 LED White - 24 W	0512301	1		
• 72 LED Daylight - 24 W	0512311	1		
• 72 LED Turquoise - 20 W	0512321	1		
• 72 LED Blue - 20 W	0512331	1		
• 72 LED Red - 20 W	0512341	1		
• 72 LED Green - 20 W	0512351	1		

"MAXI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns. For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.



Description	Code	Pieces/ Weight Volume box Kg m³
• 72 LED RGB - Built-in Control - 30 W	051236	1
• 72 LED RGB - Center Control - 30 W	051237	1
• 72 LED RGB - Built-in Control - 20 W	0512361	1
• 72 LED RGB - Center Control - 20 W	0512371	1





"MAXI-Clicker" Underwater Light Colored Frame

RAL 7016 Made of ABS. Different Color options can be adapted to all Maxi-Clicker Models.



)15	Description	Code	Pieces/ box	Weight Kg	Volume m ³
	Anthracite - RAL 7016	05120001A	1		
)	• Beige - RAL 1015	05120001B	1		
04	• Gray - RAL 7004	05120001G	1		
	Stainless Steel 304	0512001SS	1		



New Generation

Underwater Lights for Concrete Pools



Underwater Light without Niche, Single Color.

Designed for pool stairs, small pools and spas. Single color, frame made of ABS Plastic complete with 72 SMD LED.

Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the

bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR38 products available on the market. This product is patented.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 10 W	051160E	1		
• 72 LED Daylight - 10 W	051161E	1		
• 72 LED Turquoise - 9 W	051162E	1		
• 72 LED Blue - 9 W	051163E	1		
• 72 LED Red - 9 W	051164E	1		
• 72 LED Green - 9 W	051165E	1		




Patented Bayonet "Click" System


"MIDI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control -9 W	051170E	1		
• 72 LED RGB - Central Control -9 W	051171E	1		









Rear View



Wall Mounting Bracket

Cable Conduit for Surface Mounted Lights

"Sealed Cable-Concrete Transition" Made of ABS. Complete with seal nut suitable for 2 x 0,75 mm cable passage, gasket, union and 2 stainless steel fixing screws. Can be used with all surface mounted pool lights for concrete pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	0511175	1	1,882	0,016





(6

Underwater Lights for Concrete Pools





"MINI-Clicker"

Underwater Light without Niche, Single Color.

Designed for pool stairs, small pools and spas. Underwater light without niche. Single color, frame made of ABS Plastic complete with 36 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of

1,0 m length. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. This product is patented.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - 7 W	051180	1		
• 36 LED Daylight - 7 W	051181	1		
• 36 LED Turquoise - 4 W	051182	1		
• 36 LED Blue - 4 W	051183	1		
• 36 LED Red - 4 W	051184	1		
• 36 LED Green - 4 W	051185	1		

Patented Bayonet "Click" System



Rear View



Wall Mounting Bracket



For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ W box	eight Volume Kg m³
• 36 LED RGB-Built-in Control -4 W	051190	1	
• 36 LED RGB-Central Control -4 W	051191	1	









"New Generation"





Underwater Lights for Concrete Pools

"Twister" Underwater light without niche.

Single color, frame made of ABS Plastic complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length. 120° - IP68 Consists of wall bracket and the light w/frame. Installation for different pool types could be achieved easily as shown in the schemes below. The bracket facilitates adjusting the distance between light frame and pool wall. It is very easy to fix the frame onto the bracket and to remove it just by a 30° clockwise turn. Just turn & click or remove!

2 Year Leakage Warranty.

Description	Code	Pieces/ Weight box Kg	Volume m ³
• 72 LED White - 24 W	051210	1	
• 72 LED Daylight - 24 W	051211	1	
• 72 LED Turquoise - 20 W	051212	1	
• 72 LED Blue - 20 W	051213	1	
• 72 LED Red - 20 W	051214	1	
• 72 LED Green - 20 W	051215	1	



"Twister" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB-Built-in Control -20 W	051216	1		
• 72 LED RGB-Central Control -20 W	051217	1		





FRP Pool



Concrete Pool



Concrete - Membrane Pool

Liner Panel Pool



AISI 304/316

Underwater Lights for Concrete Pools - St. Steel

"SlimLED-INOX"

Underwater Light without Niche, Silicone Filled, Single Color.

Frame made of AISI 304 grade Stainless Steel. Polycarbonate light body with a choice of LED quantities and powers embedded into a special transparent silicone. Complete with Aluminium PCB. 2 x 1,5 mm cable of 2,5 m length. 120° - IP68. Wall mounting is done by screwing the wall mounting bracket directly to the pool wall. A single screw then attaches the light to the bracket making it easy to lift the light out of the pool. 2 Year Leakage Warranty. For AISI 316 grade stainless steel option, 01 should be added to the end of product codes below and 20% should be added to the price. Max. operating temperature 30°.







Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	051140SS	1	1,100	0,005
• 252 LED Daylight - 50 W	051141SS	1	1,100	0,005
• 252 LED Turquoise - 36 W	051142SS	1	1,100	0,005
• 252 LED Blue - 36 W	051143SS	1	1,100	0,005
• 252 LED Red - 36 W	051144SS	1	1,100	0,005
• 252 LED Green - 36 W	051145SS	1	1,100	0,005

"SlimLED-INOX" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.




Fixing with Top Screw

|--|

Rear View

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED RGB, 36 W - Built-in Control	051153SS	1	1,100	0,005
• 252 LED RGB, 36 W - Centrally Control	051155SS	1	1,100	0,005

Note: For RGB 81 LED and RGB 90 LED options with stainless steel frame, please add SS to the end of the product codes on page 122 and ask for price.









AISI 304/316

New Generation

Underwater Lights for Concrete Pools - St. Steel


"SlimLED-INOXCLICK"

Underwater Light without Niche, Silicone Filled, Single Color. Frame made of AISI 304 grade Stainless Steel. Polycarbonate light

body with a choice of LED quantities and powers embedded into a special transparent silicone. Complete with Aluminium PCB. 2 x 1,5 mm cable of 2,5 m length. 120° - IP68. Wall mounting is done by screwing the wall mounting bracket directly to the pool wall. After the excess cable is wrapped, the light frame is easily slotted onto the mounting bracket (no screw required).

This allows for very easy removal of the light out of the pool. By means of a screw driver. 2 Year Leakage Warranty. For AISI 316 grade stainless steel option, 01 should be added to the end of the product codes below and 20% should be added to the price. Max. operating temperature 30°.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	051140SSC	1	1,100	0,005
• 252 LED Daylight - 50 W	051141SSC	1	1,100	0,005
• 252 LED Turquoise - 36 W	051142SSC	1	1,100	0,005
• 252 LED Blue - 36 W	051143SSC	1	1,100	0,005
• 252 LED Red - 36 W	051144SSC	1	1,100	0,005
• 252 LED Green - 36 W	051145SSC	1	1,100	0,005




For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED RGB, 36 W - Built-in Control	051153SSC	1	1,100	0,005
• 252 LED RGB, 36 W - Centrally Control	051155SSC	1	1,100	0,005

Note: For "INOXCLICK" in RGB 81 LED and RGB 90 LED please add SSC to the end of the product codes on page 122 and ask for price.











Wall Mounting Bracket



Underwater Lights for Wew Generation Concrete Pools - St. Steel

AISI 304/316



"MAXI-Clicker"

Underwater light without niche. Single color, Frame made of AISI 304 Stainless Steel complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise

turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty.

The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market. This product is patented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, and 20% should be added to the price.



	Description	Code	Pieces/ box	Weight Kg	Volume m ³
١	• 72 LED White - 35 W Aluminium PCB	051230SS	1		
١	• 72 LED Daylight - 35 W Aluminium PCB	051231SS	1		
	• 72 LED Turquoise - 30 W	051232SS	1		
	• 72 LED Blue - 30 W	051233SS	1		
ĺ	• 72 LED Red - 30 W	051234SS	1		
	• 72 LED Green - 30 W	051235SS	1		
	• 72 LED White - 24 W	0512301SS	1		
	• 72 LED Daylight - 24 W	0512311SS	1		
	• 72 LED Turquoise - 20 W	0512321SS	1		
	• 72 LED Blue - 20 W	0512331SS	1		
	• 72 LED Red - 20 W	0512341SS	1		
	• 72 LED Green - 20 W	0512351SS	1		



Patented Bayonet "Click" System

"MAXI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.


For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control - 30 W	051236SS	1		
• 72 LED RGB - Center Control - 30 W	051237SS	1		
• 72 LED RGB - Built-in Control - 20 W	0512361SS	1		
• 72 LED RGB - Center Control - 20 W	0512371SS	1		



Rear View





AISI 304/316

"New Generation"



(6



Underwater Lights for Concrete Pools - St. Steel

"MIDI-Clicker-INOX"

Underwater Light without Niche, Single Color.

Designed for stairs, small pools and spas. Frame made of AISI 304 grade Stainless Steel. Complete with 72 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length. 120° - IP68Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the fram onto the

bracket by a 30° clockwise turn. Just turn & click! In order to remove it,

push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market. This product is patented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, and 20% should be added to the price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 10 W	051160ESS	1		
• 72 LED Daylight - 10 W	051161ESS	1		
• 72 LED Turquoise - 9 W	051162ESS	1		
• 72 LED Blue - 9 W	051163ESS	1		
• 72 LED Red - 9 W	051164ESS	1		
• 72 LED Green - 9 W	051165ESS	1		




"MIDI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.


For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control -9 W	051170ESS	1		
• 72 LED RGB - Central Control -9 W	051171ESS	1		









Patented Bayonet "Click" System



Rear View



Wall Mounting Bracket



Underwater Lights for New Generation. Concrete Pools - AISI 304 St. Steel

AISI 304/316





Underwater Light without Niche, Single Color.

Designed for stairs, small pools and spas. Frame made of AISI 304 grade Stainless Steel. Complete with 36 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30°



clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market. This product is patented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, and 20% should be added to the price.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - 7 W	051180SS	1		
• 36 LED Daylight - 7 W	051181SS	1		
• 36 LED Turquoise - 4 W	051182SS	1		
• 36 LED Blue - 4 W	051183SS	1		
• 36 LED Red - 4 W	051184SS	1		
• 36 LED Green - 4 W	051185SS	1		



"MINI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.


For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED RGB-Built-in Control -4 W	051190SS	1		
• 36 LED RGB-Central Control -4 W	051191SS	1		






Rear View









Wall Mounting Bracket



"New Generatio<u>n</u>"

Underwater Lights for Liner Pools

"SlimLED"


Underwater Light without Niche, Silicone Filled, Single Color.

Frame made of ABS Plastic. Polycarbonate light body with a choice of LED quantities and powers embedded into a special transparent silicone.

Complete with epoxy PCB. 2 x 1,5 mm cable of 2,5 m length and Liner Pool Wall Mounting Kit (0521402). 120° - IP68. 2 Year Leakage Warranty.

The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available on the market. Max. operating temperature 30°.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	052140	1	0,835	0,005
• 252 LED Daylight - 50 W	052141	1	0,835	0,005
• 81 LED White - 35 W Aluminium PCB	052130	1	0,835	0,005
• 81 LED Daylight - 35 W Aluminium PCB	052131	1	0,835	0,005





"SlimLED" Underwater Light without Niche, Silicone Filled, RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Centrally Control				
• 252 LED RGB, 36 W Aluminium PCB	052155	1	1,350	0,005
• 90 LED RGB-White, 36 W Aluminium PCB	052152	1	1,350	0,005
• 81 LED RGB, 30 W	052157	1	1,350	0,005
Built-in Control				
• 252 LED RGB, 36 W Aluminium PCB	052153	1	1,350	0,005
• 90 LED RGB-White, 36 W Aluminium PCB	052150	1	1,350	0,005
• 81 LED RGB, 30 W	052156	1	1,350	0,005



O



051130EY01 Optional Wall Mounting Bracket

"SlimLED" Underwater Light without Niche, Silicone Filled Mounting Kits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Liner panel pool mounting kit (2" with nut)	052160E01	1	0,300	0,003
• Polyester pool mounting kit (2" with nut)	0521403	1	0,300	0,003



052160E01



Underwater Lights for Liner Pools

"New Generation"



"MAXI-Clicker"

Underwater Light without Niche, Single Color.

Frame made of ABS Plastic complete with 72 SMD LED.

Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.5 m length 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws,

it is very easy to fix the frame onto the bracket by a 30° clockwise turn.

Just turn & click! In order to remove it, push a screw driver on to the button

gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market. This product is patented.





Patented Bayonet "Click" System

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 35 W Aluminium PCB	052230	1		
• 72 LED Daylight - 35 W Aluminium PCB	052231	1		
• 72 LED Turquoise - 30 W	052232	1		
• 72 LED Blue - 30 W	052233	1		
• 72 LED Red - 30 W	052234	1		
• 72 LED Green - 30 W	052235	1		
• 72 LED White - 24 W	0522301	1		
• 72 LED Daylight - 24 W	0522311	1		
• 72 LED Turquoise - 20 W	0522321	1		
• 72 LED Blue - 20 W	0522331	1		
• 72 LED Red - 20 W	0522341	1		
• 72 LED Green - 20 W	0522351	1		



Rear View

"MAXI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control - 30 W	052236	1		
• 72 LED RGB - Center Control - 30 W	052237	1		
• 72 LED RGB - Built-in Control - 20 W	0522361	1		
• 72 LED RGB - Center Control - 20 W	0522371	1		



052160E01

"MAXI-Clicker" Underwater Light without Niche, Mounting Kits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Liner panel pool mounting kit (2" with nut)	052160E01	1	0,300	0,003
 Polyester pool mounting kit (2" with nut) 	05223003	1	0,300	0,003



05223003

030	
-----	--





"New Generation"

Underwater Lights for Liner Pools

"MIDI-Clicker"

Underwater Light without Niche, Single Color.

Designed for stairs, small pools and spas. Frame made of ABS Plastic. Complete with 72 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1 m length and Liner Pool Wall Mounting Kit (0521402). 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless steel screws, it is very easy to fix the frame onto

the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 10 W	052160E	1		
• 72 LED Daylight - 10 W	052161E	1		
• 72 LED Turquoise - 9 W	052162E	1		
• 72 LED Blue - 9 W	052163E	1		
• 72 LED Red - 9 W	052164E	1		
• 72 LED Green - 9 W	052165E	1		




"MIDI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control -9 W	052170E	1		
• 72 LED RGB - Central Control -9 W	052171E	1		



•

"MIDI-Clicker" Underwater Light without Niche Mounting Kits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Liner panel pool mounting kit (2" with nut)	052160E01	1	0,300	0,003
 Polyester pool mounting kit (2" with nut) 	052160E03	1	0,300	0,003







Patented Bayonet "Click" System



052160E01



052160E03



Underwater Lights for Liner Pools

"New Generation"



"MINI-Clicker"

Underwater Light without Niche, Single Color.

Designed for stairs, small pools and spas. Underwater light without niche. Single color, frame made of ABS Plastic complete with 36 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1,0 m length.

120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on

pool wall by means of stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. This product is patented.







Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - 7 W	052180	1		
• 36 LED Daylight - 7 W	052181	1		
• 36 LED Turquoise - 4 W	052182	1		
• 36 LED Blue - 4 W	052183	1		
• 36 LED Red - 4 W	052184	1		
• 36 LED Green - 4 W	052185	1		



Patented Bayonet "Click" System

"MINI-Clicker" Underwater Light without Niche; Ditto, but RGB Changing Color.

For built in PCB models there are 13 different lighting patterns.

For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). 120° - IP68.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED RGB-Built-in Control -4 W	052190	1		
• 36 LED RGB-Central Control -4 W	052191	1		

"MINI-Clicker" Underwater Light without Niche, Mounting Kits.









• Polyester pool mounting kit (2" with nut)

Description



Code

052160E01

052180E03



Pieces/

box

Weight

Kg

0.300

0,300

Volume

 m^3

0.003

0,003

052180E03



AISI 304/316 New Generation

Underwater Lights for Liner Pools - AISI 304 St. Steel

"SlimLED-INOX"

Underwater Light without Niche, Silicone Filled, Single Color.
Frame made of AISI 304 grade Stainless Steel. Polycarbonate light body with a choice of LED quantities and powers embedded into a special transparent silicone. Complete with Aluminium PCB. 2 x 1,5 mm cable of 2,5 m length. 120° - IP68. Wall mounting is done by screwing the wall mounting bracket directly to the pool wall. A single screw then attaches the light to the bracket

making it easy to lift the light out of the pool. 2 Year Leakage Warranty. For AISI 316 grade stainless steel option, 01 should be added to the end of product codes below and 20% should be added to the price. Max. operating temperature 30°.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	052140SS	1	1,400	0,008
• 252 LED Daylight - 50 W	052141SS	1	1,400	0,008
• 252 LED Turquoise - 36 W	052142SS	1	1,400	0,008
• 252 LED Blue - 36 W	052143SS	1	1,400	0,008
• 252 LED Red - 36 W	052144SS	1	1,400	0,008
• 252 LED Green - 36 W	052145SS	1	1,400	0,008




"SlimLED-INOX" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns.


For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED RGB, 36 W - Built-in Control	052153SS	1	1,400	0,008
• 252 LED RGB, 36 W - Centrally Control	052155SS	1	1,400	0,008

Note: For RGB 81 LED and RGB 90 LED options with stainless steel frame, please add SS to the end of the product codes on page 127, request 'Liner Pool' and ask for price.









Rear View



Liner Wall Mount Bracket



AISI 304/316

Underwater Lights for "New Generation" Liner Pools - AISI 304 St. Steel

"SlimLED-INOXCLICK"

Underwater Light without Niche, Silicone Filled, Single Color.

Frame made of AISI 304 grade Stainless Steel.

Polycarbonate light body with a choice of LED quantities and powers embedded into a special transparent silicone. Complete with Aluminium PCB. 2 x 1,5 mm cable of 2,5 m length and Liner Pool Wall Mounting Kit (0521402). 120° - IP68. Wall mounting is done by screwing the wall mounting bracket directly to the pool wall. After the excess cable is wrapped, the light frame is easily slotted onto the mounting bracket (no screw required). This allows for very easy removal of the light out

of the pool. By means of a screw driver. 2 Year Leakage Warranty. For AISI 316 grade stainless steel option, 01 should be added to the end of the product codes below and 20% should be added to the price. Max. operating temperature 30°.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED White - 50 W	052140SSC	1	1,400	0,008
• 252 LED Daylight- 50 W	052141SSC	1	1,400	0,008
• 252 LED Turquoise - 36 W	052142SSC	1	1,400	0,008
• 252 LED Blue - 36 W	052143SSC	1	1,400	0,008
• 252 LED Red - 36 W	052144SSC	1	1,400	0,008
• 252 LED Green - 36 W	052145SSC	1	1,400	0,008

"SlimLED-INOXCLICK" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns.


For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).




Wall Mount Bracket

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 LED RGB, 36 W - Built-in Control	052153SSC	1	1,400	0,008
• 252 LED RGB, 36 W - Centrally Control	052155SSC	1	1,400	0,008

Note: For "INOXCLICK" in RGB 81 LED and RGB 90 LED please add SSC to the end of the product codes on page 128, request 'Liner Pool' and ask for price.







AISI 304/316

"New Generation"





Underwater Lights for Liner Pools - St. Steel

"MAXI-Clicker-INOX"

Underwater Light without Niche, Single Color.




Frame made of AISI 304 Stainless Steel complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1 mlength and Liner Pool Wall Mounting Kit. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of stainless

steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and

turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR56 products available in the market. This product is patented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, an 20% should be added to the price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 35 W Aluminium PCB	052230SS	1		
• 72 LED Daylight - 35 W Aluminium PCB	052231SS	1		
• 72 LED Turquoise - 30 W	052232SS	1		
• 72 LED Blue - 30 W	052233SS	1		
• 72 LED Red - 30 W	052234SS	1		
• 72 LED Green - 30 W	052235SS	1		
• 72 LED White - 24 W	0522301SS	1		
• 72 LED Daylight - 24 W	0522311SS	1		
• 72 LED Turquoise - 20 W	0522321SS	1		
• 72 LED Blue - 20 W	0522331SS	1		
• 72 LED Red - 20 W	0522341SS	1		
• 72 LED Green - 20 W	0522351SS	1		




For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control - 30 W	052236SS	1		
• 72 LED RGB - Center Control - 30 W	052237SS	1		
• 72 LED RGB - Built-in Control - 20 W	0522361SS	1		
• 72 LED RGB - Center Control - 20 W	0522371SS	1		

"MAXI-Clicker" Underwater Light without Niche Mounting Kits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Liner panel pool mounting kit (2" with nut)	052160E01	1	0,300	0,003
Polyester pool mounting kit (2" with nut)	05223003	1	0,300	0,003











Patented Bayonet "Click" System



052160E01





Underwater Lights for Liner Pools - St. Steel

Designed for stairs, small pools and spas. **Frame** made of AISI 304 Stainless Steel complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1,0 m length and Liner Pool Wall Mounting Kit. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of

"MIDI-Clicker-INOX"

Underwater Light without Niche, Single Color.

"New Generation"

AISI 304/316







stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR38 products available in the market. This product is atented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, and 20% should be added to the price.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 10 W	052160ESS	1		
• 72 LED Daylight - 10 W	052161ESS	1		
• 72 LED Turquoise - 9 W	052162ESS	1		
• 72 LED Blue - 9 W	052163ESS	1		
• 72 LED Red - 9 W	052164ESS	1		
• 72 LED Green - 9 W	052165ESS	1		



"MIDI-Clicker-INOX" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns. For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB - Built-in Control -9 W	052170ESS	1		
• 72 LED RGB - Central Control -9 W	052171ESS	1		


Patented Bayonet "Click" System



"MIDI-Clicker" Underwater Light without Niche Mounting Kits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Liner panel pool mounting kit (2" with nut)	052160E01	1	0,300	0,003
Polyester pool mounting kit (2" with nut)	052160E03	1	0,300	0,003









AISI 304/316

"New Generation"

Underwater Lights for Liner Pools - AISI 304 St. Steel





"MINI-Clicker-INOX"

Underwater Light without Niche, Single Color.

Designed for stairs, small pools and spas. Frame made of AISI 304 Stainless Steel complete with 72 SMD LED. Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1.0 m length and Liner Pool Wall Mounting Kit. 120° - IP68. Consists of wall bracket and the light w/frame. After fixing the bracket on pool wall by means of

stainless steel screws, it is very easy to fix the frame onto the bracket by a 30° clockwise turn. Just turn & click! In order to remove it, push a screw driver on to the button gently and turn the

frame 30° counter clockwise. 2 Year Leakage Warranty. The light, without the frame, can be used as a replacement bulb for LED conversion of all PAR38 products available in the market. This product is patented. For 316 quality Stainless Steel option, 01 should be added to the end of product codes below, and 20% should be added to the price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - 7 W	052180SS	1		
• 36 LED Daylight - 7 W	052181SS	1		
• 36 LED Turquoise - 4 W	052182SS	1		
• 36 LED Blue - 4 W	052183SS	1		
• 36 LED Red - 4 W	052184SS	1		
• 36 LED Green - 4 W	052185SS	1		



"MINI-Clicker-INOX" Underwater Light without Niche; Ditto, but RGB Changing Color. For built in PCB models there are 13 different lighting patterns. For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional).


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED RGB-Built-in Control -4 W	052190SS	1		
• 36 LED RGB-Central Control -4 W	052191SS	1		



Patented Bayonet "Click" System

"MINI-Clicker" Underwater Light without Niche Mounting Kits.

Code	Pieces/ box	Weight Kg	Volume m ³
052160E01	1	0,300	0,003
052180E03	1	0,300	0,003
	Code 052160E01 052180E03	Code box 052160E01 1	Code box Kg 052160E01 1 0,300







052180E03



Hang Over Underwater LED Light for Prefbricated Pools

2 years Parts WARRANI

"Hang Over"

Underwater LED Light.

Hang Over Underwater LED Light specifically designed for DIY installation to above ground pools. Complete with 50 W/12 V AC transformer, 5+2 meters cable. The product is ready to be connected to 220 V AC to start function. Easy DIY install with two screws to pool coping. Optional elongation part (13,5 cm) to be used to install at deeper levels.

Technical Features:

- Special, elegant, stylish and patented design
- Easy snap mechanism by design
- In IP68 protection, class III
- Ability to direct connect 220-230 V / 50-60 Hz network line



"New Generation"

(



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - 16 W	0511611	1		
• 72 LED Daylight - 16 W	0511612	1		
• 72 LED Turquoise - 13 W	0511613	1		
• 72 LED Blue - 13 W	0511614	1		
• 72 LED Red - 13 W	0511615	1		
• 72 LED Green - 13 W	0511616	1		

"Hang Over" Underwater LED Light. RGB Changing Color

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED RGB-Built-in Control - 13 W	0511711	1		







Easy DIY Installation



50W/12VAC Transformer





"Bottom" cable outlet on the niche.




Underwater Lights for Concrete Pools - ABS

"Standard 95"

Underwater Lights. Frame made of ABS plastic, niche in white plastic. Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light, with 300 W/12 V PAR56	051111	1	2,160	0,016
Complete light, with 20 W-63 SMD LED	051111LS	1		
• 051111, without cable	051111C	1		
051111LS, without cable	051111LSC	1		
• 051111, without niche and cable	051111NC	1		
• 051111LS, without niche and cable	051111LSNC	1		
• Niche	05111110S	1		



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light, with 300 W/12 V PAR56	051114	1	2,160	0,016
• Complete light, with 20 W-63 SMD LED	051114LS	1		
• 051114, with locking	051115	1		
051114LS, with locking	051115LS	1		
• 051114, without cable	051114C	1		
051114LS, without cable	051114LSC	1		
• 051114, without cable and niche	051114NC	1		
• 051114LS, without cable and niche	051114LSNC	1		
• Niche	05111410S	1		
Modular niche extension	0511411	1		

"Standard 2004" Underwater Lights. Frame made of ABS plastic, niche in white plastic. Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light, with 300 W/12 V PAR56	051118	1		
• Complete light, with 20 W-63 SMD LED	051118LS	1		
• 051118, with locking	051119	1		
051118LS, with locking	051119LS	1		
• 051118, without cable	051118C	1		
051118LS, without cable	051118LSC	1		
• 051118, without cable and niche	051118NC	1		
• 051118LS, without cable and niche	051118LSNC	1		
• Niche	05111810S	1		
Modular niche extension	0511411	1		



051111LS



051114



051114LS



051119



0511411

Underwater Lights for Concrete Pools - ABS





"Standard 2006" Underwater Lights.

Frame made of ABS plastic, niche in white plastic.

Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche. Light is fixed to the niche with 2 front screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete Light, with 300 W/12 V PAR56	051112	1	2,800	0,016
Complete Light, with 20 W-63 SMD LFD	051112LS	1	2.800	0.016



"Mini 2008" Underwater Lights.

For concrete pools. Frame and niche made of ABS plastic. Complete with halogen or power led bulb, 2 m cable and special tightening tool.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 50 W/12 V	05112	1		
• 7 W/12 V with white SMD 36 LED	05112LS	1		
• Niche	0511212S	1		



"Mini 2001" Underwater Lights.

Heat resistant plastic body, bottom outlet. Complete with 2 m. cable. 50 W/12 V bulb or power LED.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slip type body with plastic frame	05112S	4	2,000	0,007
• 05112S, with 7 W/12 V SMD 36 LED	05112SLS	4	2,500	0,007
• 2" threaded with plastic frame	05112T	4	2,100	0,007
• 05112T, with 7 W/12 V SMD 36 LED	05112TLS	4	2,500	0,007



05112SLS



Housing for Mini 2001 for Concrete Pools.

Complete with the special "no-leak" cable outlet.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
	04160A	20	10,420	0,060



Can be adhered to the back of the GEMAS Housing for Concrete Pools, or at the mouth of Ø 63 mm 10 atm PVC pipes. With cable gland seal.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
	0511200101S	1		



Underwater Lights for Concrete Pools - S.S.

"Standard 2002" Underwater Lights.

AISI 304 grade Stainless Steel Frame.Frame made of AISI 304 grade stainless steel, niche in white plastic. Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Complete Light	051114SS	1	2,790	0,016
Complete Light, SMD LED version	051114SSLS	1		



051114SSLS

"Standard 95" Underwater Lights. AISI 304 Grade Stainless Steel Plated Frame.

Frame made of AISI 304 grade stainless steel plated ABS plastic, niche in white plastic. Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Complete Light	051113SS	1	2,646	0,016
Complete Light, SMD LED version	051113SSLS	1		



Stainless Steel Frame For Underwater Lights.

Made of AISI 304 grade stainless steel. Can easily be adapted to existing ABS frames.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For "Flat" Light	05111608	1		
• For "Standard 2002" Light	05111408	1		
• For "Mini 2008" Light	0511212508	1		
• "Standard 2002" For Locked Light	05111508	1		
• For "Standard 95" Light	05111108	1		



05111608

"Mini 2008" Underwater Lights.

Concrete pools, the frame is made of AISI 304 quality stainless steel and the housing is made of ABS plastic. Complete with halogen bulb or SMD LED bulb, 2 m cable and special clamping device.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Complete Light 50 W / 12 V	05112C	4	2,300	0,007
• Ditto, 7 W/12 V SMD 36 LED	05112LSC	4	2,300	0,007



"Mini 2001" Underwater Lights.

Heat resistant plastic body, bottom outlet. Complete with 2 m. cable. 50 W/12 V bulb or 7 W SMD LED bulb.

Code	Pieces/ box	Weight Kg	Volume m ³
05112SC	4	2,300	0,007
05112SCLS	4		
05112TC	4	2,400	0,007
05112TCLS	4		
	05112SC 05112SCLS 05112TC	Code box 05112SC 4 05112SCLS 4 05112TC 4	Code box Kg 05112SC 4 2,300 05112SCLS 4 05112TC 4 2,400



05112SC

Underwater Lights for Liner Pools







052111B

"Standard 95" Underwater Lights.

Frame made of ABS plastic, brass screw fittings, niche in white plastic.

Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche. Complete with flange, bolts and gaskets.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light with 300 W/12 V PAR56	052111B	1	2,450	0,016
• Complete light with 20 W-63 SMD LED	052111BLS	1	2,450	0,016
052111B, without cable	052111BC	1	2,300	0,016
052111BLS, without cable	052111BLSC	1	2,300	0,016
052111B, without niche and cable	052111BNC	1	2,100	0,016
• 052111BLS, without niche and cable	052111BLSNC	1	2,100	0,016
• Niche	05211101BSP	1		0,016

"Standard 2002" Underwater Lights.

Frame made of ABS plastic, brass screw fittings, niche in white plastic.

Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche. Complete with flange, bolts and gaskets.



052114B

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light, with 300W/12V PAR56	052114B	1	2,450	0,016
• Complete light, with 20W – 63 SMD LED	052114BLS	1	2,450	0,016
• 052114B, with locking mechanism	052115B	1	2,700	0,016
• 052114BLS, with locking mechanism	052115BLS	1	2,700	0,016
• 052114B, without cable	052114BC	1	2,300	0,016
• 052114BLS, without cable	052114BLSC	1	2,300	0,016
• 052114B, without niche and cable	052114BNC	1	2,100	0,016
• 052114BLS, without niche and cable	052114BLSNC	1	2,100	0,016
• Niche	05211410BSP	1		0,016

"Standard 2004" Underwater Lights.

Frame made of ABS plastic, brass screw fittings, niche in white plastic.

Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche. Complete with flange, bolts and gaskets.



052118B

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Complete light, with 300W/12V PAR56	052118B	1	2,450	0,016
• Complete light, with 20W - 63 SMD LED	052118BLS	1	2,450	0,016
• 052118B, with locking mechanism	052119B	1	2,700	0,016
• 052118BLS, with locking mechanism	052119BLS	1	2,700	0,016
• 052118B, without cable	052118BC	1	2,300	0,016
052118BLS, without cable	052118BLSC	1	2,300	0,016
052118B, without niche and cable	052118BNC	1	2,100	0,016
• 052118BLS, without niche and cable	052118BLSNC	1	2,100	0,016
• Niche	05211810BSP	1		0,016





Underwater Lights for Liner Pools

"Standard 2006" Underwater Lights.

Frame, niche and niche fittings made of ABS plastic. Complete with either 300 W/12 V PAR56 bulb with 2 x 4 mm cable of 2,5 m length or PAR56 SMD LED bulb with 2 x 0,75 mm cable of 1,5 m length. Choice of "Side" or "Bottom" cable outlet on the niche. Complete with flange, bolts and gaskets. Light is fixed to the niche with 2 front screws. **Specially designed for panel type liner pools.** Complete with flange, bolts and gaskets.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Complete Light	052112	1	2,800	0,016
Complete Light, with SMD LED	052112LS	1		



052112

"Mini 2008" Underwater Light for Concrete Pools.

For liner pools. Frame, niche and flange made of ABS plastic. Complete with halogen bulb or power LED, 2 m. cable and special locking tool.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 50 W / 12 V	05212B	1		
• 7 W / 12 V White SMD 36 LED	05212BLS	1		
• Niche	0521212S	1		



05212B

"Mini 2001" Underwater Light.

Heat resistant plastic body, bottom cable outlet, 2 m silicon cable. 50 W / 12 V.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slip body, plastic frame	05112S	4	2,000	0,007
• Ditto, White SMD 36 LED	05112SLS	4		
• 2" threaded body, plastic frame	05112T	4	2,100	0,007
• Ditto, White SMD 36 LED	05112TLS	4		



05112S

Housing for Mini 2001 for Liner Pools.

For fixing the light to the pool wall. Complete with the "no-leak" cable adaptor, flange, screws and gaskets.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Housing	04260A	20	11,800	0,060
Ditto, brass cavities	04260AB	20	11,800	0,060



"Standart 2002" Underwater Light Colored Frame

Made of ABS. Different Color options can be adapted to all Standart 2002 Models. For Frame with "Locking Mechanism" Please the sixth digit of the code from "4" to "5". Price only includes the frame, not the complete light.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Anthracite - RAL 7016	051114011A	1		
• Beige - RAL 1015	051114011B	1		
• Gray - RAL 7004	051114011G	1		



143

Electrical Equipments_____



Technical Table For PAR56 LED Bulbs - Single Color

Code	Description	LED Type	# of LED	Voltage (V)	AC V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	Case
0541101	Slim 252 SMD LED - White	SMD	252	12	50	3536	120°	Policarbonate
0541102	Slim 252 SMD LED - Daylight	SMD	252	12	50	3536	120°	Policarbonate
0541103	Slim 252 SMD LED - Turquoise	SMD	252	12	36	1011	120°	Policarbonate
0541104	Slim 252 SMD LED - Blue	SMD	252	12	36	1011	120°	Policarbonate
0541105	Slim 252 SMD LED - Red	SMD	252	12	36	1011	120°	Policarbonate
0541106	Slim 252 SMD LED - Green	SMD	252	12	36	1011	120°	Policarbonate
0541111	Slim 81 SMD LED - White	SMD	81	12	35	2739	120°	Policarbonate
0541112	Slim 81 SMD LED - Daylight	SMD	81	12	35	2739	120°	Policarbonate
0541113	Slim 81 SMD LED - Turquoise	SMD	81	12	30	1241	120°	Policarbonate
0541114	Slim 81 SMD LED - Blue	SMD	81	12	30	1241	120°	Policarbonate
0541115	Slim 81 SMD LED - Red	SMD	81	12	30	1241	120°	Policarbonate
0541116	Slim 81 SMD LED - Green	SMD	81	12	30	1241	120°	Policarbonate
051130ER	ECOSIim 72 SMD LED - White	SMD	72	12	24	1614	120°	Policarbonate
051131ER	ECOSlim 72 SMD LED - Daylight	SMD	72	12	24	1614	120°	Policarbonate
051132ER	ECOSlim 72 SMD LED - Turquoise	SMD	72	12	20	671	120°	Policarbonate
051133ER	ECOSlim 72 SMD LED - Blue	SMD	72	12	20	671	120°	Policarbonate
051134ER	ECOSlim 72 SMD LED - Red	SMD	72	12	20	671	120°	Policarbonate
051135ER	ECOSlim 72 SMD LED - Green	SMD	72	12	20	671	120°	Policarbonate
051160E	MIDI-Clicker 72 SMD LED - White	SMD	72	12	10	562	120°	Policarbonate
051161E	MIDI-Clicker 72 SMD LED - Daylight	SMD	72	12	10	562	120°	Policarbonate
051162E	MIDI-Clicker 72 SMD LED - Turquoise	SMD	72	12	9	181	120°	Policarbonate
051163E	MIDI-Clicker 72 SMD LED - Blue	SMD	72	12	9	181	120°	Policarbonate
051164E	MIDI-Clicker 72 SMD LED - Red	SMD	72	12	9	182	120°	Policarbonate
051165E	MIDI-Clicker 72 SMD LED - Green	SMD	72	12	9	183	120°	Policarbonate
051180	MINI-Clicker 36 SMD LED - White	SMD	36	12	7	550	120°	Policarbonate
051181	MINI-Clicker 36 SMD LED - Daylight	SMD	36	12	7	550	120°	Policarbonate
051181	MINI-Clicker 36 SMD LED - Turquoise	SMD	36	12	4	92	120°	Policarbonate
051183	MINI-Clicker 36 SMD LED - Blue	SMD	36	12	4	92	120°	Policarbonate
051184	MINI-Clicker 36 SMD LED - Red	SMD	36	12	4	92	120°	Policarbonate
051185	MINI-Clicker 36 SMD LED - Red MINI-Clicker 36 SMD LED - Green	SMD	36	12	4	92	120°	Policarbonate
051105	Single color PAR56 SMD with 63 LED - White	SMD	63	12	20	1404	120°	Policarbonate
	•	SMD	63	12	20		120°	
0531102	Single color PAR56 SMD with 63 LED - Daylight					1404 550	120°	Policarbonate Policarbonate
0531103	Single color PAR56 SMD with 63 LED - Turquoise	SMD	63	12	16	550		
0531104	Single color PAR56 SMD with 63 LED - Blue	SMD	63	12	16	550	120°	Policarbonate
0531105	Single color PAR56 SMD with 63 LED - Red	SMD	63	12	16		120°	Policarbonate
0531106	Single color PAR56 SMD with 63 LED - Green	SMD	63	12	16	550	120°	Policarbonate
0531111	Single color PAR56 SMD with 252 LED - White	SMD 2835	252	12	40	3059	85°	Policarbonate
0531112	Single color PAR56 SMD with 252 LED - Daylight	SMD 2835	252	12	40	3059	85°	Policarbonate
0531113	Single color PAR56 SMD with 252 LED - Turquoise	SMD 2835	252	12	31	900	80°	Policarbonate
0531114	Single color PAR56 SMD with 252 LED - Blue	SMD 2835	252	12	31	900	80°	Policarbonate
0531115	Single color PAR56 SMD with 252 LED - Red	SMD 2835	252	12	31	900	80°	Policarbonate
0531116	Single color PAR56 SMD with 252 LED - Green	SMD 2835	252	12	31	900	80°	Policarbonate
0532311	Single color PAR56 with 9 OSRAM Power LED-White	OSRAM POWER	9	12	20	2409	80°	Policarbonate
0532312	Single color PAR56 with 9 OSRAM Power LED-Daylight	OSRAM POWER	9	12	20	2409	80°	Policarbonate
0532313	Single color PAR56 with 9 OSRAM Power LED-Turquoise	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532314	Single color PAR56 with 9 OSRAM Power LED-Blue	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532315	Single color PAR56 with 9 OSRAM Power LED-Red	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532316	Single color PAR56 with 9 OSRAM Power LED-Green	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532111	Single color PAR56 with 18 Power LED - White	POWER	18	12	24	1690	140°	Policarbonate
0532112	Single color PAR56 with 18 Power LED - Daylight	POWER	18	12	24	1690	140°	Policarbonate
0532113	Single color PAR56 with 18 Power LED - Turquoise	POWER	18	12	24	848	140°	Policarbonate
0532114	Single color PAR56 with 18 Power LED - Blue	POWER	18	12	24	848	140°	Policarbonate
0532115	Single color PAR56 with 18 Power LED - Red	POWER	18	12	24	848	140°	Policarbonate
0532116	Single color PAR56 with 18 Power LED - Green	POWER	18	12	24	848	140°	Policarbonate
05321111	Single color PAR56 with 27 Power LED - White	POWER	27	12	36	1038	140°	Policarbonate
05321121	Single color PAR56 with 27 Power LED - Daylight	POWER	27	12	36	1038	140°	Policarbonate
05321131	Single color PAR56 with 27 Power LED - Turquoise	POWER	27	12	36	1038	140°	Policarbonate
	J							

Technical Table For PAR56 LED Bulbs - Single Color

Code	Description	LED Type	# of LED	Voltage (V)	AC V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	Case
05321141	Single color PAR56 with 27 Power LED - Blue	POWER	27	12	36	1038	140°	Policarbonate
05321151	Single color PAR56 with 27 Power LED - Red	POWER	27	12	36	1038	140°	Policarbonate
05321161	Single color PAR56 with 27 Power LED - Gren	POWER	27	12	36	1038	140°	Policarbonate
0532211	Single color PAR56 with 18 Power LED - White	POWER	18	24	46		140°	Aluminium
0532212	Single color PAR56 with 18 Power LED - Daylight	POWER	18	24	46		140°	Aluminium
0532213	Single color PAR56 with 18 Power LED - Turquoise	POWER	18	24	46		140°	Aluminium
0532214	Single color PAR56 with 18 Power LED - Blue	POWER	18	24	46		140°	Aluminium
0532215	Single color PAR56 with 18 Power LED - Red	POWER	18	24	46		140°	Aluminium
0532216	Single color PAR56 with 18 Power LED - Green	POWER	18	24	46		140°	Aluminium
05322111	Single color PAR56 with 27 Power LED - White	POWER	27	12	70	4225	140°	Aluminium
05322121	Single color PAR56 with 27 Power LED - Daylight	POWER	27	12	70	4225	140°	Aluminium
05322131	Single color PAR56 with 27 Power LED - Turquoise	POWER	27	12	70	4225	140°	Aluminium
05322141	Single color PAR56 with 27 Power LED - Blue	POWER	27	12	70	4225	140°	Aluminium
05322151	Single color PAR56 with 27 Power LED - Red	POWER	27	12	70	4225	140°	Aluminium
05322161	Single color PAR56 with 27 Power LED - Green	POWER	27	12	70	4225	140°	Aluminium

Technical Table For PAR56 LED Bulbs - RGB

Code	Description	_ED Type	# of LED	Voltage (V)	AC V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	Case
05115301	Slim 252 SMD LED Built-in Control	SMD	252	12	36	1011	120°	Policarbonate
05115501	Slim 252 SMD LED Centrally Control	SMD	252	12	36	1011	120°	Policarbonate
0541201	Slim 90 SMD LED Built-in Control	SMD	90	12	36	1081	120°	Policarbonate
0541202	Slim 90 SMD LED Centrally Control	SMD	90	12	36	1081	120°	Policarbonate
05115601	Slim 81 SMD LED Built-in Control	SMD	81	12	30	1241	120°	Policarbonate
05115701	Slim 81 SMD LED Centrally Control	SMD	81	12	30	1241	120°	Policarbonate
051150ER	ECOSlim 72 SMD LED Bulbs with Built-in Control	SMD	72	12	20	671	120°	Policarbonate
051151ER	ECOSlim 72 SMD LED Bulbs with Central Control	SMD	72	12	20	671	120°	Policarbonate
051236	MAXI-Clicker 72 SMD LED Bulbs with Built-in Control	SMD	72	12	30	774	120°	Policarbonate
051237	MAXI-Clicker 72 SMD LED Bulbs with Central Control	SMD	72	12	30	774	120°	Policarbonate
0512361	MAXI-Clicker 72 SMD LED Bulbs with Built-in Control	SMD	72	12	20	671	120°	Policarbonate
0512371	MAXI-Clicker 72 SMD LED Bulbs with Central Control	SMD	72	12	20	671	120°	Policarbonate
0532523	MIDI-Clicker 72 SMD LED Bulbs with Built-in Control	SMD	72	12	9	184	120°	Policarbonate
0532524	MIDI-Clicker 72 SMD LED Bulbs with Central Control	SMD	72	12	9	185	120°	Policarbonate
0532631	MINI-Clicker 36 SMD LED Bulbs with Built-in Control	SMD	36	12	4	92	120°	Policarbonate
0532622	MINI-Clicker 36 SMD LED Bulbs with Central Control	SMD	36	12	4	92	120°	Policarbonate
0531201	RGB PAR56 SMD with 54 LED - Built-in Control System	SMD	54	12	16	550	120°	Policarbonate
0531202	RGB PAR56 SMD with 54 LED - Central Control System	SMD	54	12	16	550	120°	Policarbonate
0531211	RGB PAR56 SMD with 252 LED - Built-in Control System	SMD	252	12	31	900	120°	Policarbonate
0531212	RGB PAR56 SMD with 252 LED - Central Control System	SMD	252	12	31	900	120°	Policarbonate
0532321	PAR56 9 OSRAM Power LED Centrally Control	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532322	PAR56 9 OSRAM Power LED Built-in Control	OSRAM POWER	9	12	23	893	80°	Policarbonate
0532121	PAR56 18 Power LED Bulbs with Built-in Control	POWER	18	12	24	848	140°	Policarbonate
0532721	PAR56 18 Power LED'li Bulbs with Central Control	POWER	18	12	24	848	140°	Policarbonate
0532221	PAR56 with 18 Power LED - Built-in Control System with Alu. Body	POWER	18	12	46	2226	140°	Aluminium
0532222	PAR56 with 18 Power LED - Central Control System with Alu. Body	POWER	18	12	46	2226	140°	Aluminium
0532122	PAR56 27 Power LED Bulbs with Built-in Control	POWER	27	12	36	1038	140°	Policarbonate
0532722	PAR56 27 Power LED Bulbs with Central Control	POWER	27	12	36	1038	140°	Policarbonate
0532123	RGBW PAR56 30 Power LED Built-in Control	POWER	30	12	31	1779	120°	Policarbonate
0532223	RGB PAR56 with 27 Power LED - Built-in Control System with Alu. Body	POWER	27	12	70	4225	140°	Aluminium
0532224	RGB PAR56 with 27 Power LED - Central Control System with Alu. Body	POWER	27	12	70	4225	140°	Aluminium
0532226	RGBW PAR56 with 50 Power LED - Built-in Control System	POWER	30	12	50	2525	120°	Policarbonate



SlimLED Bulbs for PAR56 Replacement - Single Color





120° Light Spectrum



"SlimLED" Underwater Light Bulb - Replacement - Single Color.

Embedded into special transparent silicone, polycarbonate light body with 252 LED, 2 x 1,5 cable of 2,5 m length 120° IP68. Complete with adapter set.

2-year leakage warranty. Can be used for the replacement of any existing PAR56 bulb on the market. 50.000 hours of life. **Max. operating temperature 30°**.

"SLIMLED" BULBS									
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle					
White	252	50	3536	120°					
Daylight	252	50	3536	120°					
Turquoise	252	36	1011	120°					
Blue	252	36	1011	120°					
Red	252	36	1011	120°					
Green	252	36	1011	120°					

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	0541101	1		
Daylight	0541102	1		
• Turquoise	0541103	1		
• Blue	0541104	1		
• Red	0541105	1		
• Green	0541106	1		





"SlimLED" Underwater Light Bulb - Replacement - Single Color.

Embedded into special transparent silicone, polycarbonate light body with 81 LED, 2 x 1,5 cable of 2,5 m length 120° IP68. Complete with adapter set. **2-year leakage warranty**. Can be used for the replacement of any existing PAR56 bulb on the market. 50.000 hours of life. **Max. operating temperature 30°**.

"SLIMLED" BULBS									
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle					
White	81	35	2739	120°					
Daylight	81	35	2739	120°					
Turquoise	81	30	1241	120°					
Blue	81	30	1241	120°					
Red	81	30	1241	120°					
Green	81	30	1241	120°					

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	0541111	1		
 Daylight 	0541112	1		
• Turquoise	0541113	1		
• Blue	0541114	1		
• Red	0541115	1		
• Green	0541116	1		





"New Generation"

120° Light Spectrum

ECOSlimLED Bulbs for PAR56 Replacement - Single Color

"ECOSlimLED" Underwater Light Bulb - Replacement - Single Color.

Polycarbonate light body complete with 72 SMD LED, epoxy PCB.

2 x 0,75 cable of 1,5 m length 120° IP68. Complete with adapter set. 2-year leakage warranty. Can be used for the replacement of any existing PAR56 bulb on the market. 50.000 hours of life. Max. operating temperature 30°.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	051130ER	1		
 Daylight 	051131ER	1		
• Turquoise	051132ER	1		
• Blue	051133ER	1		
• Red	051134ER	1		
• Green	051135ER	1		

	"ECOSLIMLED" BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	
White	72	24	1614	120°	
Daylight	72	24	1614	120°	
Turquoise	72	20	671	120°	
Blue	72	20	671	120°	
Red	72	20	671	120°	
Green	72	20	671	120°	

PAR56 LED Bulbs - Single Color - with SMD LED

120° Light Spectrum

Single Color PAR56 with 63 SMD LED - 120°.
Polycarbonate body, AC-DC 11-14 V. 50.000 hours long life.
2-year leakage warranty.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	0531101	1		
• Daylight	0531102	1		
• Turquoise	0531103	1		
• Blue	0531104	1		
• Red	0531105	1		
• Green	0531106	1		

63 "SMD" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	63	20	1511	120°
Daylight	63	20	1511	120°
Turquoise	63	16	550	120°
Blue	63	16	550	120°
Red	63	16	550	120°
Green	63	16	550	120°

Single Color PAR56 with 252, SMD LED - 120°.

Polycarbonate body, AC-DC 11-14 V. 50.000 hours long life.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	0531111	1		
 Daylight 	0531112	1		
• Turquoise	0531113	1		
• Blue	0531114	1		
• Red	0531115	1		
• Green	0531116	1		

252 "SMD" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	252	40	3059	120°
Daylight	252	40	3059	120°
Turquoise	252	31	900	120°
Blue	252	31	900	120°
Red	252	31	900	120°
Green	252	31	900	120°

Note: Bulbs with "Flat Transparent Glass" fronts are available, please add F to the end of the above product codes.



PAR56 LED Bulbs -Single Color - With OSRAM LED



OSRAM Single Color PAR56 9 Power LED Bulb.

Polycarbonate body, AC-DC 11-14 V. 50.000 hours long life. All bulb circuits have heat sensitive **Automatic Current Control** to ensure long life. **2-year leakage warranty**.



80° Light Spectrum

9 PAR56 "POWER" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	9	20	2409	80°
Daylight	9	20	2409	80°
Turquoise	9	23	893	80°
Blue	9	23	893	80°
Red	9	23	893	80°
Green	9	23	893	80°

Description	Code	Pieces/ Weight Volume box Kg m ³
• White	0532311	1
 Daylight 	0532312	1
• Turquoise	0532313	1
• Blue	0532314	1
• Red	0532315	1
• Green	0532316	1

PAR56 LED Bulbs -Single Color - With Power LED





Single Color PAR56 Lamp with 18 Power LED.

Polycarbonate body, AC-DC 11-14V. 50.000 hours - long life. To ensure longer life, all the light circuits has heat sensitive **Automatic Current Control. 2-year leakage warranty**.



140° Light Spectrum



18 PAR56 "POWER" LED BULBS					
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	
White	18	24	1690	140°	
Daylight	18	24	1690	140°	
Turquoise	18	24	848	140°	
Blue	18	24	848	140°	
Red	18	24	848	140°	
Green	18	24	848	140°	

Description	Code	Pieces/ Weight Volume box Kg m³
• White	0532111	1
 Daylight 	0532112	1
• Turquoise	0532113	1
• Blue	0532114	1
• Red	0532115	1
Green	0532116	1

PAR56 LED Bulbs - Single Color - With Power LED

Single color PAR56 with 27 Power LED Bulb.

Polycarbonate body, AC-DC 11-14V. 50.000 hours-long life. To ensure longer life, all the light circuits has heat sensitive **Automatic Current Control. 2-year leakage warranty**.

140° Light Spectrum







 $(\epsilon$

Description	Code	Pieces/ Weight Volume box Kg m³
• White	05321111	1
 Daylight 	05321121	1
 Turquoise 	05321131	1
• Blue	05321141	1
• Red	05321151	1
• Green	05321161	1

27 PAR56 "POWER" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	27	36	1038	140°
Daylight	27	36	1038	140°
Turquoise	27	36	1038	140°
Blue	27	36	1038	140°
Red	27	36	1038	140°
Green	27	36	1038	140°

Single color PAR56 with 27 Power LED Bulb.

Polycarbonate glass - **Aluminum injection body**, AC-DC 22-26V. 50.000 hours-long life. To ensure longer life, all the light circuits has heat sensitive **Automatic Current Control. 2-year leakage warranty**.





Description	Code	Pieces/ box	Weight Kg	Volume m ³
• White	05322111	1		
 Daylight 	05322121	1		
• Turquoise	05322131	1		
• Blue	05322141	1		
• Red	05322151	1		
• Green	05322161	1		

27 PAR56 "POWER" LED BULBS					
Color	# of LED	AC 24 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle	
White	27	70	4225	140°	
Daylight	27	70	4225	140°	
Turquoise	27	70	4225	140°	
Blue	27	70	4225	140°	
Red	27	70	4225	140°	
Green	27	70	4225	140°	



PAR38 LED Bulbs - Single Color - With SMD LED



Single Color 72 SMD LED bulb.

Polycarbonate body, AC-DC 11-14V. 2-year leakage warranty.



30° Light Spectrum Automatic Current Control

63 "SMD" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	72	10	562	30°
Daylight	72	10	562	30°
Turquoise	72	9	181	30°
Blue	72	9	181	30°
Red	72	9	182	30°
Green	72	9	183	30°

Description	Code	Pieces/ Weight box Kg	Volume m ³
• White	0532711	1	
 Daylight 	0532712	1	
• Turquoise	0532713	1	
• Blue	0532714	1	
• Red	0532715	1	
• Green	0532716	1	

Mini LED Bulbs - Single Color - With SMD LED



Single Color 36 SMD LED Lights.

AC-DC 11-14V. Bare Circuit Bulb. 50,000 hours-long life. 2-year leakage warranty.



90° Light Spectrum

36 "SMD" LED BULBS				
Color	# of LED	AC 12 V Power (W)	Light Intensity (lux=lm/m²)	Light Angle
White	36	7	550	140°
Daylight	36	7	550	140°
Turquoise	36	4	92	140°
Blue	36	4	92	140°
Red	36	4	92	140°
Green	36	4	92	140°

	Description	Code	Pieces/ Weight Volume box Kg m³	
	• White	0532822	1	
-	 Daylight 	0532821	1	
-	• Turquoise	0532824	1	
-	• Blue	0532823	1	
	• Red	0532825	1	
	• Green	0532826	1	

Underwater STRIP LED Lights - IP68





Single Color LED Strip Lighting.

12 V strip IP68 LED 12 W. Width 10 mm, Thickness 5 mm. Standard roll Length is 5 m. Price below is per metre. Special sealed cable connection possible.

	Description	Code	Pieces/ box	Weight Kg	Volume m ³
	White - price per meter	0534111			
	Daylight - price per meter	0534112			
	Blue - price per meter	0534113			
3	RGB - price per meter	0534121			
	Aluminium Mounting Strip, w/opaque cover	0534111C			
	Aluminium Mounting Strip, cap	0534111CC			

Note: LED Strip Light can be pre-assembled into the overflow channel profile. Please ask for price.






SlimLED Bulbs for PAR56 Replacement - RGB

"SlimLED" Underwater Light Bulb - Replacement Kit - RGB changing Color.

Polycarbonate light body with a choice of LED quantities and powers embedded into a special transparent silicone. Complete with 2 x 1,5 mm cable of 2,5 m length and adapter set. 120° - IP68. For built in PCB models there are 13 different lighting patterns. For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). **2-year leakage warranty**. The light can be used as a replacement bulb for LED conversion of all PAR56 products available on the market. 50,000 hours life.

Max. operating temperature 30°.

120° Light Spectrum



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 252 Built-in Control replacement kit	05115301	1		
• 252 Central Control replacement kit	05115501	1		
• 90 Built-in Control replacement kit	0541201	1		
• 90 Central Control replacement kit	0541202	1		
81 Built-in Control replacement kit	05115601	1		
81 Central Control replacement kit	05115701	1		

"SLIMLED" BULBS						
Color	of LED	AC Power (W)	Light Intensity (lux=lm/m²)	Light Angle		
RGB B.I.	252	36	1011	120°		
RGB C.I.	252	36	1011	120°		
RGB B.I.	90	36	1081	120°		
RGB C.I.	90	36	1081	120°		
RGB B.I.	81	30	1241	120°		
RGB C.I.	81	30	1241	120°		

"New Generation"

"ECOSlimLED" Bulbs for PAR56 Replacement Kit - RGB


"ECOSlimLED" Underwater Light Bulb - Replacement Kit - RGB changing Color. Complete with 72 SMD LEDs: Polycarbonate light body, epoxy PCB and 2 x 0,75 mm cable of 1,5 m length and adapter kit. 120° - IP68. For built in PCB models there are 13 different lighting patterns. For central PCB models there are 16 different lighting patterns. Lighting patterns are changed by remote control (optional). The light can be used as a replacement bulb for LED conversion of

Max. operating temperature 30°.

all PAR56 products available on the market.

2-year leakage warranty.

120° Light Spectrum



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 Built-in Control replacement kit	051150ER	1		
• 72 Central Control replacement kit	051151ER	1		
72 Self Control replacement kit	051150ERSC	1		

"ECOSLIMLED" BULBS						
Color	# of LED	AC Power (W)	Light Intensity (lux=lm/m²)	Light Angle		
RGB B.I.	72	20	671	120°		
RGB C.I.	72	20	671	120°		
RGB S.C.	72	20	671	120°		










PAR56 LED Bulbs - RGB - With SMD LED





Rainbow PAR56 LED bulb.

Polycarbonate body. For built-in PCB models RGB 13, for central PCB models RGB 16 different lighting patterns. Changing programs with switch on and off. For built-in control bulbs two-core cable infrastructure and for central PCB bulbs four-core or twocore cable infrastructure together with a central control pannel is required. It is recommended to use central control models to avoid syncronization problems in systems with more than 10 lamps, 50.000 hours long life. To ensure longer life, all the light circuits has heat sensitive **Automatic Current Control. 2-year leakage warranty.**

PAR56 "SMD" LED BULBS					
Color	# of LED	AC Power (W)	Light Intensity (lux=lm/m²)	Light Angle	
RGB B.I.	54	16	550	120°	
RGB C.I.	54	16	550	120°	

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rainbow 54 Built in Control	0531201	1		
 Rainbow 54 Central Control 	0531202	1		



120° Light Spectrum

Rainbow PAR56 LED bulb. Polycarbonate body. For built-in PCB models RGB 13, for central PCB models RGB 16 different lighting patterns. Changing programs with switch on and off. For built-in control bulbs two-core cable infrastructure and for central PCB bulbs four-core or twocore cable infrastructure together with a central control panel is required. It is recommended to use central control models to avoid syncronization problems in systems with more than 10 lamps, 50.000 hours long life. Self RCU control models has a built in PCB system with inside remote control reciever. With one remote, max 6 lights can work with synchronization. Remote control i not included in price of the bulb. To ensure longer life, all the light circuits has heat sensitive Automatic Current Control. 2-year leakage warranty.

P.	AR56 "	SMD" LED	BULBS	
Color	# of LED	AC Power (W)	Light Intensity (lux=lm/m²)	Light Angle
RGB B.I.	252	31	900	120°
RGB S.C.	252	31	454	120°
RGB C.I.	252	31	900	120°

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rainbow 252 Built in Control	0531211	1		
Rainbow 252 Self RCU Controlled	0531211SC	1		
Rainbow 252 Central Control	0531212	1		

Note: Bulbs with "Flat Transparent Glass" fronts are available, please add F to the end of the above product codes.



PAR56 LED Bulbs - RGB - Power LED

80° Light Spectrum

Rainbow PAR56 LED bulb.

Polycarbonate body. For built-in PCB models RGB 13, for central PCB models RGB 16 different lighting patterns. Changing programs with switch on and off. For built-in control bulbs two-core cable infrastructure and for central PCB bulbs four-core or twocore cable infrastructure together with a central control pannel is required. It is recommended to use central control models to avoid syncronization problems in systems with more than 10 lamps, 50.000 hours long life. To ensure longer life, all the light circuits has heat sensitive Automatic Current Control. 2-year leakage warranty.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rainbow 9 Built-in Control	0532322	1		
• Rainbow 9 Central Control	0532321	1		

P	AR56 "	POWER" L	ED BULBS	
Color	# of LED	AC Power (W)	Light Intensity (lux=lm/m²)	Light Angle
RGB B.I.	9	23	893	80°
RGB C.I.	9	23	893	80°

Note: Bulbs with "Flat Transparent Glass" fronts are available, please add F to the end of the above product codes.

140° Light Spectrum

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rainbow 18 Built in Control	0532121	1		
Rainbow 18 Central Control	0532721	1		



PAR56 "POWER" LED BULBS					
Color # AC Light Intensity (lux=lm/m²)				Light Angle	
RGB B.I.	18	24	848	140°	
RGB C.I.	18	24	848	140°	

140° Light Spectrum

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rainbow 27 Built in Control	0532122	1		
Rainbow 27 Central Control	0532722	1		
Rainbow 27 Built in Control - Alu. Body	0532223	1		
Rainbow 27 Central Control - Alu. Body	0532224	1		
Note: Bulbs with "Flat Transparent Glass" fronts a	are available, plea	se add F to the end of t	he above pr	oduct codes.



PAR56 "POWER" LED BULBS				
Color	olor # AC Light of LED Power Intensity (W) (lux=lm/m²)			
RGB B.I.	27	36	1038	140°
RGB C.I.	27	36	1038	140°
RGB B.I.	27	70	4225	140°
RGB C.I.	27	70	4225	140°



140° Light Spectrum

PAR 56 LED BULBS - RGB Single and Multi Color with Power LED

Brand New Concept.



White and RGB together

Rainbow 30 and Rainbow 50 PAR 56 LED Bulb - 140°.

Made of 18 RGB plus 12 white led. The Light can work not only with RGB led programs, but also with only white led lights. It also has an option to light the white leds, with RGB leds all together. In this case, the white light intensity can be maximized. Polycarbonate body. In Built-in PCB system, it is RGB 13+1 white, in Central PCB system, it is RGB 16+1 white different light patterns. On-off, enables changing the program. For built-in PCB systems 2 core cable, for Central PCB systems 4 core cable and central control panels are required. When there is more than 10 LED Bulbs, not to have problems in synchronisation during long hours of working, Central PCB Systems model should be chosen. To ensure longer life, all light circuits have heat sensitive **Automatic Current Control**. Light specificatioms on the table are with RGB and white leds working at the same time.

PAR56 "POWER" LED BULBS				
Color	color # AC Light of LED Power Intensity (W) (lux=lm/m²)			Light Angle
RGBW B.I.	30	31	1779	140°
RGBW B.I.	30	50	2525	140°

Built in Control System Led Bulbs				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Rainbow 30	0532123	1		
Rainbow 50 - Aluminium Body	0532226	1		

Power LED Bulb Lens



Power LED Lenses.



Description	Code	Pieces/ \ box	Neight Kg	Volume m ³
• 30° Lens	0532001	1		
• 45° Lens	0532002	1		
• 60° Lens	0532003	1		

PAR38 LED Bulbs - RGB - SMD LED





120° Light Spectrum

Rainbow PAR38 72 SMD LED Bulb.

Polycarbonate body, RGB 16 different light alternatives, changing programmes with switch on and off.

50.000 hours long life. To ensure longer life, all the light circuits have heat sensitive **Automatic Current Control**. **2-year leakage warranty**.

72 PAR38 "SMD" LED BULBS					
Color	$ \begin{array}{cccc} \text{Color} & \# & \text{AC 12 V} & \text{Light} & \text{L} \\ \text{of LED} & \text{Power} & \text{Intensity} & \text{A} \\ \text{(W)} & (\text{lux} = \text{Im/m}^2) \\ \end{array} $				
RGB B.I.	72	8	316	120°	
RGB C.I.	72	8	316	120°	

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Built-in Control - 8 W	0532523	1		
Central Control - 8 W	0532524	1		

Mini LED - RGB - SMD LED 120° Light Spectrum


Rainbow 36 SMD LED bulbs. Different RGB light modes, AC-DC 11-14V. (Central control panel is obligatory for applications with multiple bulbs.)

36 "SMD" LED AMPULLER				
Color # AC 12 V Light Intensity Angle (W) (lux=lm/m²)				
RGB B.I.	36	6	75	120°
RGB C.I.	36	6	75	120°

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Built-in Control - 6 W	0532631	1		
Central Control - 6 W	0532622	1		

Single Color LED Bulbs - Control Systems

Single color LED lights used in swimming pools can be controlled with remote control systems. The control devices in question are divided into 2 main groups, with and without transformer. Transformer receivers (Modulator) can be analog or electronic transformers. Transformers are inside the antenna receiver unit. In cases where the capacity is not enough, the increase in capacity can be achieved with the help of additional transformers. There is an analog transformer control system on our list. An electronic transformer system can be made upon request.



Single Color Bulb Control Panels and Remote Controls

"Modulator for Single Color LED Light" complete with 220 V input, 12 V output, radio wave-antenna remote control receiver, 200 W analog transformer and 2 key remote control switch. It can be connected in parallel with the conventional transformer for added power. It is installed with two-core cable.

Description	Code	Pieces/ Weight Volume box Kg m ³
Modulator for Single Color LED Light	05092A1	1



REMOTE CONTROL DEVICES FOR SINGLE COLOR LED LIGHTS

Remote Control. Used for LED lights with built-in PCB. Changes the program of a group of light easily by switching on and off, without going to the engine room. The reach of the model is 30 m without the antenna and 80 m with antenna. Power capacity for all of the models is 1,1 kW.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Receiver with the plug + remote control key	05090	1	0,200	
• In-line receiver + remote control key	05091	1		
• 05091, with antenna	05091A	1		
Remote Control Unit	05091AY01	1		
• Two Terminal Panel 2 with 4 button Remote Control	05092A3	1		
05092A3's Panel Type	05092A3P	1		







155



RGB LED Bulbs - Control Systems



05073231

LED lights with changing RGB colors and light attractions can be installed with different techniques. The basic difference between the lights is the method it uses to control the light changes and the harmony in the light attractions. This control can be maintained separately for every light by an integrated PCB (printed circuit board) as in built-in PCB models. Alternatively, there can be a central PCB installed in a central control panel, to regulate all the lights centrally.

Central PCB models are the definite solution to the synchronization problems that occur in multi-light systems (>10 lamps) in long time operation. Hence they are recommended in multi-light systems. These kind of control panels are suitable for a limited number of lights. For larger quantities, adequate number of satellite panels should be installed.

Changing the light program of the lights is realized by switching the system on and off with a remote control. Before doing this, the system should be operating for at least 1-2 minutes. In lights with built-in PCB, all the lights are tied to a plug with remote control receiver

- (1) or a board with a receiver
- (2). These receivers make sure that the light program has changed for all the lights by switching them on and off with the command from the remote control. As the distances between the PCBs in the lights and the receiver are different, synchronization problem may occur in operations longer than 2 hours. In case of this problem, the system should be switched off, and be switched on again after 7-13 seconds. After this, all lights continue working simultaneously with the same program. There is also a special board
- (3) that facilitates this synchronization. This board also has a remote control and receiver, and can control back and forth movement between light programs. An external timer can also be installed in this panel.

In central PCB systems receiver is installed within the board and controls a single central PCB. In this systems, the synchronization of the light programs never spoil.




05073221

BUILT-IN PCB SYSTEM CONNECTION DIAGRAM Option 2 Option 3 05073231 Option 1 05090 05091/05091A 70 日日 (1) Receiver with plug and remote control + Remote Control + Remote control + syncronization changing programs with the remove changing programs on the board + changing programs with note control + external timer connect

CENTRAL PCB SYSTEN CONNECTION DIAGRAM



05073221S



RGB LED Lights Control Panels and Remote Control Devices

Light Modulator for RGB Color and Single Color Led Lights. Complete with 220 V input, 12 V output, radio remote control receiver, antenna and 4-key remote-control switch. Synchronization with one button, on-off button, reset button, program change buttons via control switch. It is a 200 W Analog Transformer, it can be connected in parallel with a conventional transformer for additional power. Installed with two-core cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• LED Modulator, for RGB LED	05092A	1		
• 4- Button Remote Control, for RGB LED	05092A3Y01	1		



Built-in Two-terminal Light modulators for RGB changing Color LED.

Complete with 220 V input-output, radio remote control receiver, antenna and 4-button remote control. Synchronization with a single button on the panel and the remote control (Panel 1) or only on the remote control (Panel 2). On-Off button, reset button, program change buttons. Connections for an external timer. Installed with two-core cable. There is no Transformer on the panel, can be installed with analog or electronic transformers (= Satellite Panel).

Description	Code		Weight Kg	Volume m ³
• Two Terminal Panel 1 with 4 button Remote Control	05073231	1		
• Two Terminal Panel 2 with 4 button Remote Control	05092A3	1		
05092A3's Panel Type	05092A3P	1		



05073231





Central Control Panel with Four Terminals for RGB LED Bulbs:

LED light control panel complete with 200 V inlet / 12 V outlet, **200 W electronic transformer**, remote control and radio wave receiver. Central control with 16 different light programs. Connections for external timer. **To be established with four core cable infrastructure**.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Board I with four terminals	05073221	1		
• Satellite board*, for four terminals	05073221S	1		

^{*} Electronic transformer.



CE THE PROPERTY OF THE PROPERT

05073221

05073221S



Transformers - 230/12V



300 W / 230 - 12 V Outlet Transformer.

Housing made of heat resistant plastic. Gasket sealed lid. Input with glass fuse, outlet with special connection terminal. Complete with hardware necessary for fixing on the wall. Winding is completely sealed in polyurethane for humid rooms. IP65.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
IP65 300 W / 230 - 12 V Outlet	05073	1	4,000	0,003

100 W / 230 - 12 V Outlet. Plastic housing, polyurethane isolation.

Description	Code	Pieces/ W box	eight Volume Kg m³
IP65 100 W / 230 - 12 V Outlet	05067	1	0,007

50 W / 220 - 12 V Outlet.

Description	on	Code	Pieces/ box	Weight Kg	Volume m ³
IP65 50 W	/ / 220 - 12 V Outlet	05069			

300 W / 230 - 12 V Outlet. Housing made of resistant plastic. 220 V input with glass fuse.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• IP20 300 W / 230 - 12 V Outlet	05074	1	5,050	0,007
 Ditto, w/polyester isolation, IP65 	05074P	1	6,250	0,007
• 400 W / 230 - 12 V Outlet	05078P	1		



2 X 300 W = 600 W / 230 - 12 V Outlet.

Housing made of heat resistant plastic. Two 300 W/12 V underwater lamp can be connected.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
IP65, w/polyester isolation	05063	1	7,200	0,008

300 W / 230 - 13-14-15-16 V with cascade output. (No load through transformer).

Housing made of heat resistant durable plastic. Connection compartment has a sealed cover. Outlet with special connection terminals, 230 V input with glass fuse. Supplied with bolts + plugs to hang on the wall and spare glass fuse. Designed for installations where the lamp and transformer are remote. 2 x 6 cable type allows for connection up to 50 meters apart. Model 05062P is for highly humid engine rooms.

Winding is completely insulated with polyurethane. (See Selection Chart)

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	05062	1	6,100	0,007
Fully insulated	05062P	1	7,800	0,007

300 W-220/13"14"15"16" V OUTPUT, SELECTION TABLE FOR OUTPUT VOLTAGE (VOLTS) FOR CASCADE TRANSFORMER

CABLE TYPE	DISTANCE BETWEEN TRAFO & LAMPS (m)							
	3-6-9	12	15	18	21	24	27	30
2 x 4	13	15	15	16	16	-	-	-
2 x 6	-	13	13	14	14	15	16	16



Transformers - 230/24V

230 V - 24 V Outlet Transformer. Plastic box, wall mounted.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 150 W - IP20	05064	1	4,600	0,007
• 300 W - IP20	05065	1	5,900	0,007



600 W / 230 - 24 V Outlet Transformer. Plastic box, wall mounted.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
IP20 600 W / 230 - 24 V Outlet	05066	1	7,400	0,008

Bulbs for Underwater Lights

PAR38 - 150 W/24 V Bulb.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
PAR38 - 150 W/24 V Bulb	05021001	12	4,916	0,003



100 W/12 V Halogen Bulb.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
100 W/12 V Halogen Bulb	05113002			

05021001

50 W/12 V Halogen Bulb.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
50 W/12 V Halogen Bulb	0511207	50	2,000	0,007



0511207

Sandwich Gasket for Underwater Lights

Sandwich gasket for underwater lights.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
For Standard 2002 Underwater light	05211401S	1	0,800	





Installation Equipment for Underwater Lights



Junction Box.

Made of white ABS plastic. Connections are for "05051" conduits. Two main and two back-up connections.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Junction Box	05040	8	2,610	0,016



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Hose Conduit	05051	50	9,100	0,070
• Ditto, with threaded ends.	05051T	50		

Hose Conduit.

Spiral wounded-transparent and blue PVC hose of 3/4".

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Transparent- price per meter	05053	50	9,100	0,070
Blue- price per meter	05054	50	5,200	



Underwater Light Cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2 x 1,5 TTR price per meter	05111062	100 m		
• 2 x 4 TTR price per meter	0511106	100 m	21,200	
• 2 x 6 TTR price per meter	05111061	100 m	30,400	





Special tube used for underwater joints of the lamp cables.

Can be used with cables with a diameter between 1,2 - 3 mm. After the copper joint, the cable should be wrapped with electric band, and then be isolated with the underwater tube by heat treatment.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
For Ø1,2 - 3 mm cables, price per meter	050831	1		

Electronic Switches

Flow Switch, 1,5 m cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Flow Switch 1 (Floater Type)	05081	1		
• Flow Switch 2 (Paddle Type)	05083	1		

Note: Flow Switch 1 'Floater' gives a 'no flow' signal when the floater is in the horizontal position.



Floater Switch.

Made of PP. For on-off control of the level controlled device. 30 cm cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Floater switch	05082	1		



Pneumatic Switch.

Up to 1 HP. Detects air flow or the absence of air flow through the button.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pneumatic Switch	156871	1		



156871

Wired and Wireless Remote Controls

Pneumatic Switch Board.

For threephase pumps up to 4 kW (excluding). Complete with contactor and fuse. Ready installed in plastic box.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pneumatic switch board	05080	1	0,748	0,003



05080

Pneumatic Button For Underwater Installations Through the Wall:

For the control of electrical equipment inside the pool. Complete with special wall conduit + cable outlet. Can be used with 05080 to be effective up to 30 m.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pneumatic Button For Underwater	05080B	1	0,650	0,004



05080B

Wired Remote Control for Lighting and / or Pool Equipment.

Used for remote wired control of lights, pumps, heaters or similar equipment. It has three outputs. Max for each output power capacity is 1.15 kW / 5 A. Cable distance is 3.0 m standard. Order for longer distances.

9				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Three Function Button + Driver	15233	1		
Three Function Button	15231	1		
• Single Function Button + Driver	15234	1		
Single Function Button	15232	1		
• Driver	15230	1		





Wired and Wireless Remote Controls



Remote Controls for Led Lights or Pool Equipment.

Used for remote control of lamps, pumps, heaters or similar equipment. Single output. Max. power capacity is 1,15 kW / 5 A. Control range is 80 m in open air. There may be a reduction in range in underground engine rooms. Does not include a transformer.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• In-Line Receiver and Remote Control	05091A	1		
• Remote Control Handset only (2 button)	05091AY01	1		



RS585-Wi-fi Modul

Used for remote wired control of lights, pumps, heaters or similar equipment. It has two outputs. Max for each output power capacity is 1,15 kW / 5 A. The control range is limited through internet browser by the Wi-Fi range. Controlled via screen commands with computers or smartphones through internet browser.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
RS485-Wi-Fi Modul	050701	1		

Electrical Control Boards



With contactor. Electric control

Electric control board; made of injection plastic, resistent to dust and impacts, closed type board with decorative look. For threephase and monophase pumps of up to 4 kW (exclusive). All boards have Siemens contactors and thermal magnetic switch board protection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 triphase pump + 1 group of lights	050711	1	3,300	0,017
• Ditto, w/timer	050711T	1	3,500	0,017
• Ditto, w/200 W Analog Transformer	050711TT	1		0,017
• 1 triphase pump + 2 groups of lights	050712	1	3,594	0,017
Ditto, w/timer	050712T	1	3,725	0,017
• 2 triphase pumps + 2 groups of lights	050713	1	4,382	0,017
Ditto, w/timer	050713T	1	4,580	0,017

Note: Please ask for the price for your special boards.



050722T

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 Monophase Pump + 1 group of lights	050721	1	3,300	0,017
• Ditto, w/timer	050721T	1	3,500	0,017
Ditto, w/200 W Analog Transformer	050721TT	1		0,017
• 1 Monophase Pump + 2 group of lights	050722	1	3,594	0,017
Ditto, w/timer	050722T	1	3,725	0,017
• 2 Monophase Pump + 2 group of lights	050723	1	4,382	0,017
Ditto, w/timer	050723T	1	4,580	0,017

Note: For special panels with phase protection and circuit breakers etc, please ask for price.





Pool Control Mono/Tri - Electronic Control Boards

"POOL CONTROL MONO". Fully electronic, 7 segment display, pool electrical control panel. It controls single-phase pumps from 0.33 Hp to 2.0 Hp and 1 group of 100 W / 12 V lights (up to 4 pieces). Complete with 100 W or 200 W / 12 V Analogue transformer.

"POOL CONTROL TRI". Fully electronic, 7 segment display, pool electrical control panel. It controls tri-phase pumps up to 0.33 Hp and 1 group of 100W / 12V lights (up to 4 pieces). Complete with 100 W or 200 W / 12 V Analogue transformer.

Technical Specifications:

- Controlled automatic operation is possible for pumps and lights. While the system is operating, it can pass from automatic control to manual or manual control to automatic without interrupting the system.
- Wrong Connection Protection: In case of a wrong connection in the connection box of the motor, it gives a short circuit warning and prevents the motor from starting. It stops the motor in case of a short circuit in the motor windings for any reason. (For example, the motor is submerged)
- Thermal Current Protection: The current drawn by the motor can be defined with a precision between 10% and 50%. In case of excessive current out of tolerance, the motor is disabled.
- Closed Valve Protection: It deactivates the motor using current control if the valves in the pump suction and / or discharge lines are closed by error. Thus, it eliminates the risk of damage caused by overheating.
- Ampere Reading: It allows seeing the current drawn by the pump motor at any time. All controls are disabled in this mode.
- Working Time: Possibility to see the total working time as year-month-day-hour-minute on the indicator from the first commissioning of the pump. Also uninterrupted working time display from last on.
- Time Counter: Possibility to start-stop the pump automatically for the desired time with the help of the meter.
- Light Control and Toroidal Transformer: 1 group 100 W or 200 W / 12 V light output and Toroidal transformer.
- Spare Pump Connection: Possibility of conversion to spare pump with a button.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pool Control Mono; (Max. 100 W)	0507311	1		
• 1 Pump (+1 spare)+1 Gr. Light				
• 050731, (Max. 200 W)	0507312	1		
 Pool Control Tri; (Max. 100 W) 	0507311T	1		
• 1 Pump (+1 spare)+1 Gr. Light				
• 0507311T, (Max. 200 W)	0507312T	1		
Modul Control	050731101	1		
• Modul Control w/smartphone Wi-Fi app.	050731101WF			

"IF THE POOL CONTROL MONO / TRI IS PURCHASED AND INSTALLED WITH GEMAS MONOPHASE PUMPS, THE PUMP WARRANTY PERIOD IS EXTENDED FOR 2 YEARS FREE OF CHARGE."







050731101



ISAVER - Pool Pump Frequency Inverter


"New Inverter Technology"






GEMAS "ISAVER" is the first "Touch Screen" frequency-inverter manufactured in the pool industry. By adjusting the running speed of the pool pump, it provides significant energy savings and operates silently. Additionally, it allows for automatic operation adjustment with different cycles within four time intervals throughout the day. The screen displays power consumption values corresponding to the set revolutions. It also offers the ability to adjust the speed during operation. Different models of the device are available for three-phase and single-phase motors (refer to the table for details). Max. capacity is 2,2 kW. The device includes dry contacts for various types of external controls. **PROVIDES SUBSTANTIAL ENERGY SAVINGS.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• ISAVER 1100	0111INV1100	1		
• ISAVER 1100C	0111INV1100C	1		
• ISAVER 2200	0111INV2200	1		
• ISAVER 2200C	0111INV2200C	1		





MODEL ISAVER 1100

MODEL	ISAVER 1100	ISAVER 2200	ISAVER 1100C	ISAVER 2200C	
Operating Temp.	-10 ~ 40°C	-10 ~ 40°C	-10 ~ 40°C	-10 ~ 40°C	
Input Power	1ph AC	1ph AC	1ph AC	1ph AC	
Input Voltage	220V~240V	220V~240V	220V~240V	220V~240V	
Frequency	50 Hz	50 Hz	50 Hz	50 Hz	
Output Voltage	Mono, 0~240V	Mono, 0~240V	Tri, 0~240V	Tri, 0~240V	
Output Power	Max 1.1kW	Max 2.2kW	Max 1.1kW	Max 2.2kW	
Output Current	Max 6A	Max 12A	Max 4.5A	Max 8A	
Pump Type	Monophase	Monophase	Triphase	Triphase	
Speed Range	1200 ~ 2900 rpm				



Control Boards - Level Control

LEVEL CONTROL BOARD; Full electronic balance tank level regulator control system. Complete with electronic floater.

Technical Characteristics:

- Overflow Control: In case of an overflow of balance tank, sends signal to sound alarm system and/or balance tank suction motorised valve, alarms and/or prevents the overflow.
- Lower Level Control: When there is no water in the balance tank, sends signal to pump contactor and terminates the pump operation.
- **Upper Level Control:** In case a water shortage in the balance tank, device controls the selenoid valve of the main water line and automatically delivers water to the system.



MODELS:

Level Control I, Automatic water top up.

Complete with 3/4" selenoid valve and 1 electronic floater.

Level Control II, Automatic water top up and overflow alarm.

Complete with 3/4" selenoid valve, 2 electronic floater and sound alarm.

Level Control III, water top up, lower level and overflow alarm.

3/4" selenoid valve, 3 electronic floaters and sound alarm.

Overflow Control, Can be supplied by Ø50 or Ø63 motorized ball valve addition.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Level Control I	050741	1	0,500	0,002
Level Control II	050742	1		
Level Control III	050743	1		
For Overflow Control;				
Ø50 mm motorized ball valve	131115M	1		
 Ø63 mm motorized ball valve 	131116M	1		











Automatic pH - Redox Controller



06311N

GEMAS POOL DIRECTOR 2023 (Automatic pH-Redox Controller).

Complete with electrodes, electrode cables, flow cell and buffer solutions. Microprocessor controlled. Installed on a 507x705 plastic panel which has reservations for dosing pumps. Dosing pumps are not included in the price. Please order dosing pumps with necessary capacities additionally.

Technical Features:

- Microprocessor technology
- Touch-operated keypad
- ON-OFF and rational operation modes can be selected for pH and ORP separately
- Automatic calibration with chosen calibration solution
- Optional heat sensor
- Optional dosing pump level control
- Optional flow switch for flow control
- RS232 or RS485 outlets for optional DATA transfer



05083



05082



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pool Director - with board	06311N	1		
 Pool Director - w/out board 	06312N	1		
Additional heat sensor	063212N	1		
Additional dosing pump level control	05082	1		
Additional flow switch	05083	1		

GEMAS POOL DIRECTOR 2023 ECO (Automatic pH-Redox Controller)

Complete with two 1.5 lt/h or 3,0 lt/h - 1 bar peristaltic dosing pumps, electrodes, electrode cable, sensor holder, fixing accessories and buffer solutions. Microprocessor controlled.



06311E

Sensor holder

Description	Code	Pieces/ Weight Volume box Kg m³
• Pool Director Eco, 1,5 lt/h	06310E	1
 Pool Director Eco, 3,0 lt/h 	06311E	1
 Additional heat sensor 	063212N	1
 Additional dosing pump level control 	05082	1
 Additional flow switch 	05083	1

Free-Chlorine and pH Controller



GEMAS pH and Free Chlorine Controller. Free-chlorine and pH electrode fully assembled on the panel. Complete with flow switch, flow meter with proximity switch, acrylic Flow Cell, pHFree Chlorine - Temperature Sensors, Calibration solutions and Mounting Kit. IP65 protection, Residual chlorine ppm (=mg/l), redox (=mV) and pH measurement and control system. It can be remotely controlled from the mobile phone with the optional Wi-Fi module. It also shows instant water temperature. Dosage pumps can be mounted on the panel. Dosing pumps are not included in the price. Please order dosing pumps with necessary capacities additionally.

Description	Code	Pieces/ box	Weight Kg	Wolume m ³
	06420	1		

Free chlorine and pH in public swimming pools according to DIN 19643 (additionally REDOX should be preferred.) Automatic Control System is compulsory. FCL sensor is amperometric. Ionselective sensor can be produced upon request.



Free-Chlorine and pH Controller

GEMAS pH, Redox and Free Chlorine Controller.

Free-chlorine and pH electrode fully assembled on the panel. Complete with flow switch, flow meter with proximity switch, acrylic Flow Cell, pH-Redox - Free Chlorine - Temperature Sensors, Calibration solutions and Mounting Kit. IP65 protection, Residual chlorine ppm (=mg/l), redox (=mV) and pH measurement and control system. It can be remotely controlled from the mobile phone with the optional Wi-Fi module. It also shows instant water temperature. Dosage pumps can be mounted on the panel. Dosing pumps are not included in the price. Please order dosing pumps with necessary capacities additionally.

	Code	Pieces/ box	Weight Kg	Wolume m ³
Description	06422	1		

Free chlorine and pH in public swimming pools according to DIN 19643 (additionally REDOX should be preferred.) Automatic Control System is compulsory. FCL sensor is amperometric. Ionselective sensor can be produced upon request.




Monoblock Automatic Control Systems with Dosing Pumps

GEMAS Monoblock Measurement and Dosing Unit. IP65 digital indicator, Complete with 10 l/h - 2 bar dosage pump integrated pH and ORP dosage units, sensors, sensor holders, calibration solutions. Assembled on panel.

Technical Specifications:

- Microcontroller technology
- Automatic calibration with the selected calibration fluid
- Optional dosing pump level controls
- "Flow Switch" for optional flow control

Description	Code	Pieces/ box	Weight Kg	Wolume m ³
	065MD03	1		



holders, calibration solutions. PVC pump body, seramic valve.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• pH	065MD01	1	3,164	0,009
• ORP	065MD02	1	3,156	0,009





GEMAS Selenoid Dosing Pumps

GEMAS ANALOGUE SOLENOID DOSING PUMP

GEMAS Solenoid Dosing Pump 10 lt/5 bar. Membrane- Analog. Manually adjustable from 10% to 100%.

GEMAS pH and ORP SOLENOID DOSING PUMP

GEMAS Solenoid Dosing Pump pH and ORP Control 10lt/5bar. 10LT/5 BAR Solenoid dosing pump. Complete with pH sensor, sensor holder, calibration solutions. Microcontroller technology, automatic calibration with calibration liquids, Optional dosing pump level controls, Flow Switch for optional flow control.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Analog Selenoid Dosing Pump	06GM1005	1		
• pH Selenoid Dosing Pump	065GM01	1		
ORP Selenoid Dosing Pump	065GM02	1		
J J		1		





Dosing Pumps



GEMAS Dosing Pump. Membrane type. Analogue. Manually adjustable from 10% to 100%.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2 lt / h - 12 Bar	06MD0212	1	3,092	0,009
• 3 lt / h - 11 Bar	06MD0311	1	3,092	0,009
• 5 lt / h - 9 Bar	06MD0509	1	3,092	0,009
• 8 lt / h - 5 Bar	06MD0805	1	3,092	0,009
• 10 lt / h - 4 Bar	06MD1004	1	3,092	0,009
• 15 lt / h - 2 Bar	06MD1502	1	3,092	0,009



GEMAS Vertical Dosing Pumps. Membrane type. Analoque. Manually adjustable from 10% to 100%. Easily mounted on the chemical container.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2 lt / h - 12 Bar	06T1202AB11	1	3,092	0,009
• 6 lt / h - 8 Bar	06T0806AB11	1	3,092	0,009
• 11 lt / h - 3 Bar	06T0311AB11	1	3,092	0,009
• 22 lt / h - 2 Bar	06T0222AB11	1	3,092	0,009



GEMAS Dosing Pump. Peristaltic type. Analogue. Manually adjustable from 10% to 100%.

Description	Code	Pieces/ Wei box K	ight Volume g m³
• 1,5 lt / h - 1 Bar	06PD0302	1	
• 3 lt / h - 1 Bar	06PD0301	1	

Dosing Pumps Capacity Calculation

Chosing the Dosing Pump:

A- Daily Chlorine Requirement:

- 1- Loss From Swimmers: The number of swimmers should be determined or estimated. This number should be considered according to busiest day. Daily loss per swimmer in meditarranean region is 10 gr/day.
- 2- Loss From Sun Light (The Destructive effects of UV light on chlorine): This loss is on average 2,5 gr per each pool m³ in meditarranean belt.

Daily Chlorine Requirement (gr) = The Number of Swimmers x 10 gr + Pool Volume (m³) x 2,5 gr For example: The Pool that 250 swimmer's daily use and 1000 m³ pool volume. Daily Chlorine Requirement = $250 \text{ x } 10 \text{ gr} + 1000 \text{ m}^3 \text{ x } 2,5 \text{ gr/m}^3 = 5000 \text{ gr}$

B- Determining The Capacities of Chlorine and Dosing Pumps:

* Minimum Dosing Pump Capacity (I/h) = Daily Chlorine Requirement (gr/day) x 0,0015 It depends on the fact that the determined capacity equals to the daily need of chlorine with %12 sodium hypoclorid get dosed 12 hours period. If dosing period is wanted to be shortened, the capacity should be increased with same level of shortining. For example; dosing period is chosen at 8 hours, total capacity 12/8 = 1,5 times increased. The same capacity is also enough for PH pump. Pump pressure loss should be chosen minimum 2 bars.

C- Determining The Capacity of Flocculant Dosing Pump:

Flocculant should be dosed as far as possible from filter. It's suggested to be dosed from pump outlet.

* Minimum Capacity of Dosing Pump: Pool Circulation Flow (m^3/h) x 0,002 The dosing that technically required is to give enough quantity continuously. Too much and too fast dosing would cause blur of the pool water. Pump pressure loss should be chosen minimum 2 bars. For example; a pool which has 100 m^3 flow, flocculant dosing pump capacity (l/h) = 100 m^3/h x 0,002 = 0,2 l/h. In this case the dosing pump which has 2 l/h capacity should work with 10%.



Chemical Drums

Polythene Chemical Drums.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 100	06811	1	5,086	0,145
• 200	06812	1	8,110	0,285



Chemical Drum Mixers

Manual Mixer. Made of PVC Plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06831	1	0,260	0,001

Motorized Fast Mixer. Made of PVC plastic. 1400 rpm speed fast mixer.

0.18 KW / 220 V / 50 Hz. Shaft length: 600 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Fast Mixer	06832	1	10,260	0,137

Motorized Slow Mixer. Made of PVC plastic. 70 rpm speed slow mixer. 0.13 KW /220 V / 50 Hz. Shaft length: 600 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slow Mixer	06833	1		

Spare Parts for Control Systems - Sensors

pH ELECTRODE: Complete with cable and, BNC socket.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06611	1	0,124	0,0006



REDOX ELECTRODE: Complete with cable and, BNC socket.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06612	1	0,920	0,0006



Free Chlorine Electrode, ion selective. 0 - 5 ppm measuring range.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• F.C. Electrode Amperometric (Open cell)	0642004	1		






Spare Parts for Control Systems - Others



Heat sensor with 1,5 m cable





PVC FLOW CELL: Ø20 mm, single.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06631	1	0,048	



Electrode Cell, Double.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Single	06632	1		
• Double	06633	1	0,980	



Electrode Chamber for FCL

Electrode Chamber, Made of injected, triple - Flow Rate Controlled - Complete w/proximity switch. Pieces/ Weight Volume Description Code box Κğ 0642015 · Electrode Chamber for flow, pH, ORP

0642016



Sensor Holder Made of PVC. Easy connection Ø63 PVC Tube by Ø63 Tee. Also includes Ø63-Ø50 mm reducer for Ø50 mm pipe installation.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Sensor Holder for pH and ORP sensors	0642017	1		



Redox Buffer Solution

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 220 mv - 50 cc	06511	1	0,032	
• 468 mv - 50 cc	06512	1	0,032	



pH Buffer Solution

p =				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
• pH 4 - 50 cc	06521	1	0,032	
• pH 7 - 50 cc	06522	1	0.026	



Dosing pump level control with 1,5 m cable

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	05082	1		



Flow switch, 1,5 m cable

Description	Code	Pieces/ Weight Volume box Kg m³
• Flow Switch 1 (Floater type)	05081	1
• Flow Switch 2 (Paddle type)	05083	1



PS. 05081 Can be used as floater swicth. It will give signal only on open mode not on vertical mode.



Tablet Chlorine Dosing Systems

CHLORINE DISPENSERS

Made of ABS plastic, floating type tablet chlorine dosing float. Adjustable dosing amount.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Chlorine Dispenser Model 1-7 Tablet	0619027	1	0,290	0,004
• Chlorine Dispenser Model 2-6 Tablet	0611504	1	0,358	0,008
Chlorine Dispenser Model 3-6 Tablet	06190701	1		
Chlorine Dispenser Model 4-6 Tablet	06190701T	1		
With thermometer.				



06190701T

GEMAS CLT-167 CHLORINATOR. ABS body, 2 kg tablet capacity. Dosage adjustment on the device. Used for pools of maximum 95 m³ capacity. Off-line model can be installed in the pool circulation line with an easy by-pass.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Off - Line	069CLT167A	1	1,130	0,012
• On - Line	069CLT167B	1	0,962	0,012
• Chlorinator Base, Inox for wall mounting	069CLT01	1		


GEMAS CLT-168 CHLORINATOR. ABS body, 4 kg tablet capacity. Dosage adjustment on the device. Used for pools of maximum 150 m³ capacity. Off-line model can be installed


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Off - Line	069CLT168A	1	1,748	0,017
• On - Line	069CLT168B	1	1.626	0.017

in the pool circulation line with an easy by-pass.



069CLT167B







171



Chemical Drums

Polythene Chemical Drums.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 100	06811	1	5,086	0,145
• 200	06812	1	8,110	0,285



Chemical Drum Mixers

Manual Mixer. Made of PVC Plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06831	1	0,260	0,001

Motorized Fast Mixer. Made of PVC plastic. 1400 rpm speed fast mixer. 0.18 KW / 220 V / 50 Hz. Shaft length: 600 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Fast Mixer	06832	1	10,260	0,137

Motorized Slow Mixer. Made of PVC plastic. 70 rpm speed slow mixer. 0.13 KW /220 V / 50 Hz. Shaft length: 600 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slow Mixer	06833	1		



Spare Parts for Control Systems - Sensors

pH ELECTRODE: Complete with cable and, BNC socket.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06611	1	0,124	0,0006



REDOX ELECTRODE: Complete with cable and, BNC socket.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	06612	1	0,920	0,0006



Free Chlorine Electrode, ion selective. 0 - 5 ppm measuring range.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Membrane Replacement	06420011	1		
Membrane Electrolite, 50 cc Free	06420012	1		
Chlorine Electrode ion selective	0642001	1	0,920	0,0006
• F.C. Electrode Amperometric (Open cell)	0642004	1		



06420001



Puritron GSCN Salt-Water Chlorinators



Salt Water Chlorinators produce chlorine by electrolysis of pool water with salinity of teardrop. The device has a periodic cleaning cycle process (by switching polarity) against calcification inside electrode cell. Numerical screen shows the operation power by percentage and current value in ampers. According to total hardness of the pool water, Switching Polarity Cycle could be set from 1 to 8 hours. Factory Setting is once in every 6 hours. Device saves the total operation time as well as measuring and showing salinity level. New design box facilitates easy access at the front panel for service. Wifi control over MODBUS is possible optionally by means of auxiliary connection. Electrodes are made of titanium and have a 14.000 hours long life. It can be installed to every existing pool. All models can be used in seawater. The recommended salinity rate is 4000 ppm (4kg/m³). The approximate salinity in sea water is 35.000 ppm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Puritron GSCN-10, 10 g/h	064253	1		
• Puritron GSCN-15, 15 g/h	064243	1		
• Puritron GSCN-20, 20 g/h	064263	1		
• Puritron GSCN-30, 30 g/h	064273	1		
• Puritron GSCN-50, 50 g/h	064293	1		

Model	Pool Volume (m³)	Cl Prod. (g/h)	Salt (kg/m³)	Voltage (VAC)	Voltage (VDC)	Current DC (A)	Energy Consumption (W)
Puritron GSCN - 10	0 - 50	10	4,0	220	24	2,0	50
Puritron GSCN - 15	15 - 75	15	4,0	220	24	3,0	75
Puritron GSCN - 20	40 - 100	20	4,0	220	24	4,0	100
Puritron GSCN - 30	90 - 150	30	4,0	220	24	6,0	150
Puritron GSCN - 50	150 - 250	50	4,0	220	24	10,0	250



pH Kontrollü

In addition to above Salt Chlarinator specifications, the required software are added to enable automatic pH control. The new compact design allows a monobloc peristaltic pH dosing pump (1.5 lt/h-1 bar) embedded to chlorinator unit. Complete with sensor holder pH sensor and required pipe fittings. 2 X 16 LCD screen, water tempeture measurement options.. Please ask price for larger capacity dosing pumps.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Puritron GSCN-101, pH Control	0642532	1		
• Puritron GSCN-151, pH Control	0642432	1		
• Puritron GSCN-201, pH Control	0642632	1		
• Puritron GSCN-301, pH Control	0642732	1		
• Puritron GSCN-501, pH Control	0642932	1		



pH Control Panel

Supplied as a complete system, including an integrated pH control Membrane-type dosing unit with preferred capacity, pH sensor, sensor holder, calibration solutions, all pre-assembled and mounted on a panel.

Description	Code	Pieces/ box
Puritron GSCN-101, pH Control Panel	064153	1
• Puritron GSCN-151, pH Control Panel	064143	1
• Puritron GSCN-201, pH Control Panel	064163	1
• Puritron GSCN-301, pH Control Panel	064173	1
Puritron GSCN-501, pH Control Panel	064193	1



Puritron GSCN Salt-Water Chlorinators

pH & Redox Control

In addition to Salt Chlorinator specifications, the required software are added to enable automatic pH and ORP control. The new compact design allows a monobloc peristaltic pH dosing pump embedded to chlorinator unit. Complete with sensor holder pH and ORP sensor and required pipe fittings. 4 X 20 LCD screen, water tempeture measurement options. Please ask price for larger capacity dosing pumps. (0642932 model is produced with 3lt/h - 1bar pump)

Ürün	Kod	Stand. Paket	Ağırlık Kg	Hacim m ³
Puritron GSCN-102, pH & Redox Control	064254	1		
• Puritron GSCN-152, pH & Redox Control	064244	1		
Puritron GSCN-202, pH & Redox Control	064264	1		
• Puritron GSCN-302, pH & Redox Control	064274	1		
Puritron GSCN-502, pH & Redox Control	064294	1		





Sensor holder

pH & Redox Control Panel

Complete with integrated pH and ORP dosing unit with preferred dosing pump, pH sensor, sensor holder, calibration solutions. Mounted on the panel.

Description	Code	Pieces/ box
Puritron GSCN-102, pH & Redox Control Panel	064154	1
• Puritron GSCN-152, pH & Redox Control Panel	064144	1
Puritron GSCN-202, pH & Redox Control Panel	064164	1
Puritron GSCN-302, pH & Redox Control Panel	064174	1
Puritron GSCN-502, pH & Redox Control Panel	064194	1





For electrode 50g/h models



For electrode 10-15-20-30 gr/h models



Puritron On-Line Salt-Water Chlorinators






"On-Line" devices with a monobloc body that produce chlorine from salt using electrolysis, providing salt concentration in the pool water at the same rate as tear salinity. The device has self-clean feature in order to clean electrode against calcification at periodic intervals. Digital screen; temperature value of water; LED display screen shows the working percentage rate. Automatic polarity changing of the electrodes for cleaning purposes which can be adjusted between 1-8 hours according to the hardness level of the water. The factory setting is every 6 hours. During operation, the flow cell is illuminated by colored LEDs. LEDs change color during polarity change. In the event of an alarm, the red-light flashes. The device records the total working hours in its memory.

Electrodes are made of titanium and have an average life of 14,000 hours. It can be easily installed in any existing pool. The device can be mounted on the right or left side, depending on preference. All models can also be used with seawater. Recommended min. salinity rate is 4,000 ppm (4 kg/m³). The salinity rate in sea waters is 35.000 ppm on average.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Puritron GSCOL-10	0642500L	1	5,650	0,035
• Puritron GSCOL-15	0642550L	1	5,650	0,035
• Puritron GSCOL-20	0642600L	1	5,650	0,035
• Puritron GSCOL-30	0642700L	1	5,650	0,035

Model	Pool Volume (m ³)	CI Prod (g/h)	Salt (kg/m ³)	Voltage (VAC)	Voltage (VDC)	Current DC (A)	Energy Consumption (W)
Puritron GSC, GSCOL-10	0 - 50	10	4,0	220	24	2,0	50
Puritron GSC, GSCOL-15	15 - 75	15	4,0	220	24	3,0	75
Puritron GSC, GSCOL-20	40 - 100	20	4,0	220	24	4,0	100
Puritron GSC, GSCOL-30	90 - 150	30	4,0	220	24	6,0	150

INSTALLATION DIAGRAM:



Salt for Salt-Chlorine Generators



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Granule Salt, 25 kg	02317	1		
 Tablet Salt, 25 kg 	02318	1		



Puritron Salt-Water Chlorinators

Designed for midsize hotel and apartment complex pools. The device produces chlorine by electrolysis of pool water with salinity of teardrop. It has a standart cleaning cycle process against calcification. **Electrodes are made of titanium and have a 20.000 hours long life**. Corrosion resist stainless steel body. Electrods cell made of methacrylate and transparent. It has a LCD screen. Device is switched mode. All models can be used with seawater.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Puritron GSC - 75	06435	1	15,000	
• Puritron GSC - 100	06436	1	20,000	
• Puritron GSC - 150	06437	1	25,000	

Model	Pool Volume	Chlorine	Voltage	Voltage	Current	Power	PVC Pipe	Weight	Device	Cell
	(m^3)	Production	(VAC)	(VDC)	(A)	Consumption	n (mm)	(kg)	Dimensions	Measurements
	` '	(g/h)	` '	, ,	` ′	(W)	, ,	. 0,	(mm)	(mm)
GSC75	200 - 250	75	220	24 max.	100	350	63	15	300 x 250 x 150	0 140 x 531
GSC100	250 - 300	100	220	24 max.	150	500	90	20	300 x 250 x 150	0 140 x 531
GSC150	300 - 350	150	220	24 may	200	670	90	25	300 x 250 x 150	140 x 531



Note: The above pool capacities have been calculated with the principle that the pool operates for 12-14 hours per day.

INSTALLATION DIAGRAM:





Salt - Water Chlorinator Capacity Measurement:

A- Daily Chlorine Requirement:

- 1- Loss From Swimmers: The number of swimmers should be determined or estimated. This number should be considered according to busiest day. Daily lost per swimmer in meditarranean Region is 10 gr/day.
- 2- Loss From Sun Light (The Destructive effects of UV light on chlorine): This lost is on average 2,5 gr per each pool m^3 in meditarranean belt.

Daily Chlorine Requirement (gr)=The Number of Swimmers x 10 gr+Pool Volume (m³) x 2,5 gr For example: The Pool that 250 swimmer's daily use and 1000 m³ pool volume. Daily Chlorine Requirement = 250 x 10 gr + 1000 m³ x 2,5 gr/m³ = 5000 gr

With 12 hours filtration = $5000 \text{ gr}/12h = 416 \text{ gr/h} \triangleright \text{GSC } 500$ With 24 hours filtration = $5000 \text{ gr}/24h = 200 \text{ gr/h} \triangleright \text{GSC } 250$





Puritron-GSC Salt - Water Chlorinators

Designed for large public and competition pools. The device produces chlorine by electrolysis of pool water with salinity of teardrop. It has a standart cleaning cycle process against calcification. **Electrods are made of titanium and have 20.000 hours long life**. Corrosion resistant stainless steel frame. Transparent electrode cells made of PVC. It has a graphical LCD screen. Device is switched mode. All models can be used with seawater. In addition to all above specifications, this device has electronic current control as well as heat and flow control.

Description	Code	box	weignt Kg	volume m³
• Puritron GSC - 250	06438	1	40,000	
• Puritron GSC - 500	06439	1	60,000	
• Puritron GSC - 750	06440	1	80,000	
• Puritron GSC - 1000	06446	1	100,000	

Model	Chlorine Production (g/h) (5kg/m³ salt)	Voltage (VAC)	Voltage (VDC)	Current (A)	Power Consumption (W)	PVC Pipe (mm)	Cell Measurements (mm)
GSC250	250	220	24 max.	50	1.350	63	750 x 450 x 900
GSC500	500	220	24 max.	100	2.540	63	1000 x 450 x 900
GSC750	750	220	24 max.	150	3.900	90	1250 x 450 x 900
GSC1000	1000	220	24 max.	200	5.000	90	1500 x 450 x 900









Electrode cells made of transparent PVC tube







Galatasaray Kalamis Facilities Indoor Swimming Pool, Sponsored by Gemas; Automatically controlled with a Gemas Puritron & "GSC 500" and "Pool Director"







Salt-Water Chlorinators - Anodic Protection


In pools using salt-chlorine generators, installation of this device is used to prevent electrolytic corrosion of stainless-steel materials. The electric connection is made to the pump's control panel ground/earth point.



- Easy to install.
- Provides "Electric Shock" protection in fiberglass pools.
- Maximum 4 bars 63 body
- Transparent cover for anode control
- Pure zinc, its average life is 3 years


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø 63 Anodic Protection	06423	1		





TYPE		DIMENSIONS							
		CONECTION	Α	В	С				
GDF50-	-1E	63 mm	Ø63	129	190				

INSTALLATION DIAGRAM:



Salt-Water Chlorinators - Electrode Cleaning



"SCALEX" Anti-Lime for Salt Chlorine Generators. One of the common problems in pools using a salt-chlorine generator is calcification on the electrode. This problem is often encountered especially in pools using hard water or sea water. In such cases, regular use of SCALEX provides a definitive solution.

Initial dose: 2,5 I/100 m³ pool water.

This dose should be doubled in pools using hard water.

Consecutive use dose 2,5 I/6 months.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	075327	1	5,000	0,001
• 10	075328	1	10,000	0,007
• 20	075329	1	20,000	0,028



Salt-Water Chlorinators - Spare Parts

Descriptio	n	Code	Pieces/ box
0	GSC10 Bipolar Electrode (Old)	06430YE01	1
0	GSC15 Electrode Cell-Yellow Solid Electrode Connection (Old)	06428YE01	1
0	GSC20 Bipolar Electrode (Old)	06425YE01	1
0	GSC30 Bipolar Electrode (Old)	06426YE01	1
0	GSC Electrode Housing Nut (Old)	0643103	1
	GSC Electrode Oring (Old)	0643105	1
-	GSC Electrode Connection Cable (Old)	0643113	1
0	GSC10 Bipolar Electrode (with Pin) (New)	06430YE	1
6	GSC15 Electrode Cell-Yellow (with Pin) Electrode Connection (New)	06428YE	1
0	GSC20 Bipolar Electrode (with Pin) (New)	06425YE	1
0	GSC30 Bipolar Electrode (with Pin) (New)	06426YE	1
0	GSC Electrode Housing Nut (New)	0643117	1
0	GSC Electrode Oring (New)	860488	1
0	GSC Electrode Connection Cable (New)	0643104	1
60	GSC 10-20-30 Electrode Housing	0643102	1
53	GSC 230 VAC Cable	EB71549	1
	GSC 50 Electrode	0643401	1
9	GSC 75 Electrode	0643501	1
3	GSC 100 Electrode	0643601	1
9	GSC 150 Electrode	0643701	1
9	GSC 250-500 Electrode	0643801	1
	GSC 50-100 Electrode Housing	0643402	1
8	GSC 75-150 Electrode Housing	0643403	1



Old Electrode



Nut for Old Electrode



New Electrode



Nut for New Electrode



Ultraviolet UV-C Disinfection Systems



Ultraviolet disinfection systems work with the principle of lethal effects of 220-280 nm wave length ultraviolet lights on living organisms. This wave-length ultraviolet lights require a certain contact time to kill microorganisms by destroying their cell walls. The UV devices are designed to provide this contact time according to the given flow rate.

UV radiation is considered in 4 spectrum: UV-A, UV-B, UV-C and vacuum UV. UV-C spectrum is used for water disinfection with the wave length as specified above.


Advantages of UV-C System:

- Reduces Chlorine and chemical consumption by 50% 80%.
- Effective for all microorganisms.
- Eliminates all the side effects caused by chlorine (skin irritation, eye burn, allergy, asthma and similar side effects)
- Destroys all bound chlorine compounds (=chloramines) and other harmful organic compounds.
- Reduces all chemical usage and leaves no harmful waste in water.
- · Low operating cost, and eco-friendly technology.

Devices below are designed for private pools.

All models are 316L quality stainless steel body and enables + 35% radiation efficiency. Devices are complete with **timers** that shows bulb operating life. Device gives warning when bulb completes their lifespan. Also, there is a **flow switch (circuit breaker)** at the outlet of 130 watt device that disables the bulb when pool circulation stops. The **AMALGAM** bulb that provides the most effective UV-C radiation is used in this model. Max. operating pressure is 2 bar. Bulb lifespan is 9.000 hours.

Description	Code	Pieces/ box
• Pool UV-C 40 Device with Timer up to 40 m ³	06NTUV40T	1
• Pool UV-C 75 Device, with Timer up to 75 m ³	06NTUV75T	1
• Pool UV-C 130 Device, with Timer, Flow Switch up to 150 m ³	06NTUV130TF	1
·		1 1





06NTUV130TF




Ultraviolet UV-C Disinfection Systems





This UV-C device is designed for Water Tanks. It's complete with 10 meters cable and installation kit. In case of any problem of installation to wall, it can be placed freely into water tank. It is resistant to sea water. Tank connection set is not included in price.

Description	Code	Pieces/ box	Weight Kg	Volume m³
UV-C Device, for Water Tanks	06C100120	1		
UV-C Device Montage Kit	06C100121	1		



Technic Specifications	B714404039581
Diameter (mm)	35
Length (cm)	80
Electronic Ballast	230V AC 50/60Hz
Max. Current (Amp)	0,57
Bulb Power (Watt)	75
Wave Length	253,7
Bulb Voltage (V)	97
Bulb Current (Amp)	0,80
UV-C 100h output (W)	25
μW/cm ² 1 meter distance	230
Bulb Type	Van Erp UV-C Budget 75 Watt
Weigh (Kg)	2
Package Size (mm)	70 x 220 x 840


Ozone Generators - CORONA DISCHARGE



GEMAS HYDROZONE Corona Discharge Ozone Generators. The ozone generated is vacuumed and introduced to the system by injector. Operates with free air suction. Complete with the injector with by-pass valve water trap, flow meter and active carbon filtration for discharge ozone (see.pg 186). Installation of static mixer is recommended. (see.pg 186).

Description	Code	Pieces/ box	Weight Kg	Volume m³
• HOZ CD-05, 5 gr/h	06421	1		
• HOZ CD-15, 15 gr/h*	06424	1		
• HOZ CD-08, 8 gr/h	06451	1		
• HOZ CD-25, 25 gr/h*	06452	1		

(* Must be installed with oxygen concentrator.)



necessary mechanical and election	rical installation. It	can be use with ox	ygen cor	ncentra
Description	Code	Pieces/ box	Weight Kg	Volum m ³
HOZ CD-05, 5gr/h Compact Unit	06421C	1		



Ozone Generators - CORONA DISCHARGE

GEMAS HYDROZONE Corona Discharge COMPACT Ozone Systems.

For 15 gr/h and higher models must be installed with; oxygen concentrator, ozone resistant deozonization contact tank, automatic gas discharge valve and excessive ozone-destructive filter. Below you can see the package systems that are easy to install existing pools. Required amount of quartz sand, and automatic pH and ORP control systems are included in the package price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• HOZ CDP-15, 15 gr/h-2" connection	06424P	1		
• HOZ CDP-20, 20 gr/h-2" connection	06425P	1		
• HOZ CDP-50, 50 gr/h-3" connection	06427P	1		



Oxygen Concentrator

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 l/h (for 5 - 20 gr/h devices)	064201	1		
• 10 I/h (for 50 gr/h devices)	064203	1		



Oxygen Cone

It can be used effectively in all application areas where oxygen need is critical (waste water treatment plants, dam lakes where water is supplied, rivers, lakes and ponds open to eutrophication and pollution in recreational areas, fish farming farms, which have a critical place in the food chain, etc.). It is a specially designed unit that can maximize the oxygenation level (super oxygenation) in the said environments at very high rates compared to its equivalents.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø900 mm Oxygen Cone Max Op. Pressure 2 bar	064400	1		
• Ø1000 mm Oxygen Cone Max Op. Pressure 2 bar	064401	1		
• Ø1200 mm Oxygen Cone Max Op. Pressure 2 bar	064402	1		
• Ø1400 mm Oxygen Cone Max Op. Pressure 2 bar	064403	1		
• Ø1600 mm Oxygen Cone Max Op. Pressure 2 bar	064404	1		



Ozone Injectors

Ozone Injectors. The ozone generated is vacuumed and introduced to the system by injectors. Operates with free air suction. It is made of PVDF materials and resistant to all kinds of chemicals.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Venture-3/4"-1/4", center 1-3 m ³ /h	06441	1		
• Venture-1"-1/2", center 3-10 m ³ /h	06442	1		
• Venture-1 1/4"-1/2", center 10-25 m3/h	06443	1		
• Venture-2"-1/4", center 30-50 m³/h	06444	1		



Pool Disinfection Systems



Ozone Generators - CORONA DISCHARGE




Ozone Capacity	Pool Flow Rate (m³/h)		Recommended Pool Volume (m³)		Contact + Deozonization	
(g/h)	Partial Flow	Full Flow	Partial Flow	Full Flow	Tank Diameter Ø (mm) - h (mm)	
15	75	15	375	75	Ø 615 - 1550	
25	150	25	750	150	Ø 1250 - 2500	
40	200	40	1000	200	Ø 1400 - 2500	
50	250	50	1250	250	Ø 1400 - 2500	
			(Average Circ 1	Time: 5 Hrs.)		

PS: Above values must increase 10% for indoor pools.

Full flow ozone system: with contact and deozonization tank



WATER TRAP (Pls. see 186)



- 1- Pool Circulation Pump
- 2- Sand Filters
- 3- Jet Pump 4- Ozone Injector
- 5- Water Trap 6- Ozone Generator
- 7- Static Mixer
- 8- Contact + Active Carbon Tank
- 9- Automatic Discharge Pump
- 10- Discharge Ozone Filter
- 11- Pool Heater 12- Pool Disinfection System

OZONE DOSAGE:

Partial Flowrate:


OLUME DOGMOL.	
UP to 32°C:	0,8 g/m³ per system flow (For middle busy pool)
	1,0 g/m³ per system flow (For busy pool)
Above 32°C:	1,2 g/m³ per system flow (For middle busy pool)
	1,5 g/m³ per system flow (For busy pool)
Ozone Contact Time:	2 min.
Active Carbon Dept:	Min. 500 mm

Partial flow ozone system: with contact and deozonization tank

20% of Total Flowrate



STATIC MIXER (Pls. see 186)



- 1- Pool Circulation Pump
- 2- Sand Filters 3- Jet Pump
- 4- Ozone Injector
- 5- Water Trap
- 6- Ozone Generator
- 7- Static Mixer
- 8- Contact + Active Carbon Tank
- 9- Automatic Discharge Pump
- 10- Discharge Ozone Filter 11- Pool Heater
- 12- Pool Disinfection System



Pool Disinfection Systems


Ozone Generators with UV Method

GEMAS HYDROZONE OZONE GENERATOR (With UV Method).

The ozone generated is vacuumed and introduced to the system by venturi. Complete with venturi + by-pass valve. Can be easily installed in existing swimming pools. Recommended for residential pools.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• HOZ-01, up to 90 m ³ - 0,248 g/h	06411	1	13,000	0,051
• HOZ-02, up to 150 m ³ - 0,437 g/h	06412	1	14,000	0,051





UV-Ozone Spare Bulb For GEMAS HYDROZONE Ozone Generator.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	064101	1	0,616	0,003

Water Trap for Ozone Generator. Prevents back flow of water to the device when the system is shut down.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	064102	1		
	064103	1		



Static Mixer. Provides evenly diffusion of ozone in water flow.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5"	0641031	1		
• 2"	0641032	1		
• 2,5"	0641033	1		
• 3"	0641034	1		



GEMAS CORONA Ozone Discharge Valve. Ozone resistant.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
0,5, 316 Inox Floater	0641041	1	0,616	0,003

0641031



Pool Disinfection Systems.



Ozone + Ultraviolet Combined Disinfection Systems




With the Ozone + UV Device; ozone generated inside special wave length UV bulb is vacuumed and introduced to the system by injector and transferred into pool circulation. On the other hand, it can execute the disinfection process by direct radiation to pool water from the same ozone bulb's quarts housing. Devices is complete with the bypass valve and injector. It can easily be installed into existing pool installations. Device body is 316L stainless steel.

It has timer, and gives signal when bulb's lifespan is over. Bulb power is 75 Watt, radiation power is 25 Watt, and Ozone output is 0,6 g/h.

The recommended pool capacity by the manufacturer is 75 m³. It can reduce the chlorine usage up to 90%. Ozone helps destroying sun cream, cosmetics, urine, and sweat in the water. After these process UV-C exposed pool water eliminates the residual ozone through disinfection.

Description	Code	Pieces/ box	Weight Kg	Volume m³
Ozon + UV-C Device (Gemas OEM)	06NTUV87TO	1	7,700	



Technic Specifications	NT-UV87-TO
Pool Volume (m ³)	90
Max. Flow Rate (m ³ /h)	25
Max. Working Pressure (bar)	3
Diameter (mm)	72
Length (cm)	100
Outlet Diameter (mm)	63
Stainless Steel	316L
Electronic Ballast	120-240V AC 50/60Hz
Max. Current (Amp)	0,60
Bulb Power (W)	87
Wave Length (nm)	253,7
Bulb Voltage (V)	97
Bulb Current (Amp)	0,90
UV-C 100 h outlet (W)	25
μ W/cm ² 1 meter distance	144
Bulb Type	Ozone lamp 87 W
Ozone	Exist - 0,6 gr/h
Setting Time	Exist
Bulb Change Warning	Exist
Chemical Usage Decrease	95%
Weigh (Kg)	7,7
Package Size (mm)	370 x 130 x 1110

Pool Disinfection Systems



Floating - Solar Copper Ionization System



Solar Clear, Copper + Zinc Alloyed Ionization System.

Works with solar battery. Max pool volume120 m³. Decreases the chlorine or equivalents oxidation disinfection requirement aproximately 80%. It can be used with UV and/or Dechloramin for Chlorine-Free applications in residential pools. It should not be used in liner/membrane pools due to Coppers dispersing agent impact on synthetic materials. It's not obliged to use flocculant or algecide, because Copper having positive effect on algea and flocculation. On the high degrees of water hardness, the product will act as a softening agent as it collects lime on its anode. But the anode must be cleaned periodically with wire brush inside the package. Complete with wire brush and strip copper test device. Ideal copper concentration is 0,5 ppm. Permanently use necessary on above 70 m³ pool but it can be used halftime on smaller pools. Min. Copper concentration must be 0,3 ppm. Electrode lifetime can be change by use aproximately 12 to 24 months.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Solar Clear	0601	1		

Solar Copper Ionization System Spares



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Anode	0601Y01	1		
• Filter	0601Y02	1		
• Screw	0601Y03	1		
Stripe Copper Test Kit	0834	1		
Wire Brush	0601Y04	1		



0601Y02

Dechloramin use recommended with SOLAR CLEAR

"DECHLORAMIN". Granulated active oxygen compound for chloramine destruction. After shocking, the pool can be used by bathers within a very short time. Alternative to the required small amount of chlorine in ozone pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 kg	07611	1	1,000	0,002
• 5 kg	07612	1	5,000	0,009
• 25 kg	07613	1	10,000	0,023



07613

DECLII ODANAINI	Non-chlorine	For Clarifying	100 gr/week to 10 m³ pool water (Residential pool)
DECHLORAMIN	Shock Treatment Agent	Pool Water	150 gr/week to 10 m³ pool water (Public pool)





Water Disinfection

"FASTCHLOR" Stabilized Dichlorine Granular, 56%.

Quick dissolving stabilized granular dichlorine with 56% or 60% chlorine content.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	071111	1	5,000	0,006
• 10 kg	071112	1	10,000	0,012
• 15 kg	071113	1	15,000	0,017
• 25 kg	071116	1	25,000	0,033
• 30 kg	071114	1	30,000	0,033
• 50 kg	071115	1	50,000	0,057

"FASTCHLOR 100" Stabilized Trichlorine Granular, 90%.

Slow dissolving stabilized granular trichlorine with 90% chlorine content.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	071131	1	5,000	0,006
• 10 kg	071132	1	10,000	0,012
• 15 kg	071133	1	15,000	0,017
• 25 kg	071136	1	25,000	0,033
• 30 kg	071134	1	30,000	0,033
• 50 kg	071135	1	50,000	0,057

"TABCHLOR" Stabilized Trichlorine Tablet, 200 gr 90%.

Slow dissolving stabilized trichlorine with 90% chlorine content in 200 gr tablet form.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	0712311	1	5,000	0,006
• 10 kg	0712312	1	10,000	0,012
• 15 kg	0712313	1	15,000	0,017
• 20 kg	0712314	1	20,000	0,022
• 50 kg	0712315	1	50,000	0,057

"TABCHLOR-Multi" Stabilized Trichlorine Tablet, 200 gr.

Slow dissolving stabilized Trichlorine. Algecide and flocculant.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	0714241	1	5,000	0,006
• 10 kg	0714244	1	10,000	0,012
• 15 kg	0714242	1	15,000	0,017
• 20 kg	071424 6	1	25,000	0,022
• 50 kg	0714243	1	50,000	0,057



Water Disinfection and Chlorine Stabilizer

"CALCIUM HYPOCHLORITE" 70%

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 40 kg Granular	071125	1	40,000	0,044
• 40 kg Tablet	071226	1	40,000	0,044



"FASTCHLOR L".

Sodium hypochlorite with 12% active chlorine content.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 10 I / 12 kg	071311	1	10,000	0,012
• 20 I / 25 kg	071313	1	20,000	0,028
• 25 I / 30 kg	071315	1	25,000	0,044
• 30 I / 36 kg	071312	1	30,000	0,044



CHLORSTAB isocyanuric acid - chlorine stabilizer.It can be used with FASTCHLOR L, Calcium Hypochloride and Salt-Water Chlorinators. Reduces chlorine consumption by 10%.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	075391	1	5,000	0,008
• 10 kg	075392	1	10,000	0,017
• 20 kg	075393	1	20,000	0,023
• 50 kg	075395	1	50,000	0,057



CHLORSTAB Isocyanuric acid Chlo	5 kg first dose for 100 m³ pool water e Stabilizer Following doses according to test results max. 100 ppm
---------------------------------	---



Non-Chlorine Shock Treatment



"DECHLORAMIN".

Granulated active oxygen compound for chloramine destruction. After shocking, the pool can be used by bathers within a very short time. Alternative to the required small amount of chlorine in ozone pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	07612	1	5,000	0,006
• 10 kg	07617	1	10,000	0,011
• 25 kg	07613	1	25,000	0,027



"OXYTRONE"

Granulated active oxygen compound for chloramine destruction. After shocking, the pool can be used by bathers within a very short time. Alternative to the required small amount of chlorine in ozone pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	071151	1	5,000	0,006
• 10 kg	071152	1	10,000	0,011
• 25 kg	071153	1	25,000	0,027



"CHLORINE-OUT"

Reset the Total Chlorine of pool water in pools with high Combined Chlorine problems or pools with high chlorine. To reduce the Total Chlorine of 100 m³ pool water by 1 ppm, dissolve 300 gr of Chlorine-Out in water and add to the pool water.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	071144	1	5,000	0,006
• 10 kg	071145	1	10,000	0,011
• 25 kg	071146	1	25,000	0,027


pH Regulators



"pH (-) DOWN".

Granular acid to reduce and stabilize pH level.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 7 kg	072111	1	7,000	0,006
• 15 kg	072112	1	15,000	0,017
• 25 kg	072113	1	25,000	0,023
• 50 kg	072114		50,000	0,043



Granular acid to reduce and stabilize pH level.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 10 l / 12 kg	072121	1	12,000	0,012
• 20 1 / 25 kg	072123	1	25,000	0,028
• 25 I / 30 kg	072124	1	30,000	0,044
• 30 l / 36 kg	072122	1	36,000	0,044



pH Regulators

"pH (-) DOWN HCI" Liquid pH reducer and limescale remover. (30% Hydrochloric acid)

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 10	072126	1	10,000	0,014
• 25	072125	1	25,000	0,028
• 30	072129	1	30,000	0,044
• 35	072128	1	35,000	0,044



"pH (+) UP".

Alkaline in powder form to increase and stabilize pH level.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 4 kg	072211	1	4,000	0,006
• 10 kg	072212	1	10,000	0,012
• 25 kg	072218	1	25,000	0,022
• 25 kg	072218	1	25,000	0,



Algicides

"ALGEX".

Liquid Algicide and bactericide for destruction of algae.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	073111	1	5,000	0,007
• 10	073112	1	10,000	0,014
• 20	073114	1	20,000	0,028
• 30	073113	1	30,000	0,044



"ALGEX PROTECTOR".

Liquid Algicide and bactericide against algae growth.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	073311	1	5,000	0,007
• 10	073312	1	10,000	0,014
• 20	073314	1	20,000	0,028
• 30	073313	1	30,000	0,044





Algicides

A BRAND NEW KIND OF ALGICIDE



"STARVEX" Anti Phosphate.

Starvex is an ECO-firendly chemical which destroys algea chain by binding and destructing the phosphate in the water. It does not cause turbidity in pool water. It can be used with all pool chemicals. **DOSING RATES ARE VERY LOW.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	075381	1	5,000	0,007
• 10	075382	1	10,000	0,014
• 20	075383	1	20,000	0,028
• 30	075384	1	30,000	0,044

For Phosphate Test Kit, Please see Test Kits Section.

STARVEX Liquid Algicide	1 I dose for 50 m³ pool water. 0,5 I dose in following weeks.
-------------------------	--

Flocculant



"PUREFLOCK L". Highly Effective Liquid Flocculant.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	07411	1	5,000	0,007
• 10	07422	1	10,000	0,014
• 20	07424	1	20,000	0,028
• 30	07423	1	30,000	0,044



"PUREFLOCK C".

Cartridges Flocculant for continuous clarifying treatment.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Box containes 8 cartridges	07421	1	1,280	0,003



"MULTIFLOCK C".

Cartridges Flocculant and algicide for continuous clarifying treatment.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Box containes 8 cartridges	07430	1	1,280	0,003



"CLEARFLOCK GEL" Gel Flocculant.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Box containes 4 gel cartridges	07425	1	0,30	
Box containes 1 gel cartridges	07427	1	0,65	

"ACTIVE FLOCK" Liquid.

"ACTIVE FLOCK" Liquid. Floating partides in the pool water are catched by the sand filter. No sediments on the pool bottom.

, 600. 20110			
Code	Pieces/ box	Weight Kg	Volume m ³
074241	1	5,000	0,007
074242	1	10,000	0,014
074243	1	20,000	0,028
074244	1	30,000	0,044
	Code 074241 074242 074243	Code Pieces/box 074241 1 074242 1 074243 1	Code Pieces/box Weight Kg 074241 1 5,000 074242 1 10,000 074243 1 20,000





Flocculant

"MIRACLEAR" Super Shock Clarifier.

It enables the suspended particles in the pool water to be held inside the filter. Miraclear does not make sediment on the floor of the pool. Single dose in every 3 or 4 week is enough. It's a fast and an effective solution to cloudy pools.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	075371	1	5,000	0,007
• 10	075372	1	10,000	0,014
• 20	075373	1	20,000	0,028
• 30	075374	1	30,000	0,044



Filter and Cell Care

"CALCEX FILTER".

Descaling and cleansing agent for periodical maintenance of sand filters and cell.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 kg	07521	1	1,000	0,001
• 4 kg	07522	1	4,000	0,006
• 10 kg	07523	1	10,000	0,012
• 5	075319	1	5,000	
• 10	075320	1	10,000	



Prevention of Lime Sedimentation in Hard Pool Waters

"CALSTAB".

Stabilizes hardness prevents scaling on pool surfaces.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	07551	1	5,000	0,007
• 10	07552	1	10,000	0,014
• 20	07556	1	20,000	0,028
• 30	07553	1	30,000	0,044



Electrode Cleaning for Salt-Chlorine Generators

"SCALEX" Anti-Lime for Salt-Chlorine Generators.

Initial dose: 2,5 I/100 m³ pool water. This figure should be doubled in pools using hard water. Consecutive use dose: 2.5 I/6 months.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	075327	1	5,000	0,007
• 10 kg	075328	1	10,000	0,014
• 20 kg	075329	1	20,000	0,028



Foot and Surface Disinfection

"FUNGEX". Fungicidal disinfectant.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 10	07541	1	10,000	0,014
• 30	07542	1	30,000	0,044





Pool Surface Cleaning



"SCALEX POOL" Limescale Removal - effective when the pool is "FULL"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 kg	075323	1	5,000	0,001
• 10 kg	075324	1	10,000	0,007
• 20 kg	075325	1	20,000	0,028

"CALCEX POOL".

Descaling cleaner to eliminate calcium deposits on the pool basin. When pool is empty.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•11	075311	1	1,000	0,001
• 51	075312	1	5,000	0,007
• 10	075313	1	10,000	0,012
• 20	075315	1	20,000	0,028
• 30	075314	1	30,000	0,044

"SOOT-OFF".

Cleaner for removing grease and dirts at the water rim.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 11	075321	1	1,000	0,001
• 51	075322	1	5,000	0,007
• 10	075333	1	10,000	0,014
• 20	075334	1	20,000	0,028



"CLEAN GROUTING" Grouting cleaner.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•11	075341	1	1,000	0,001
• 51	075342	1	5,000	0,007



"MORTAR-OFF" Mortar cleaner.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
•11	075351	1	1,000	0,001
• 51	075352	1	5,000	0,007

Winter Care



"POOLWIC".

For Winter Care against algae growth and calcium deposits.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 51	07511	1	5,000	0,007
• 10	07512	1	10,000	0,014
• 20	07514	1	20,000	0,028
• 30	07513	1	30,000	0,044



Pool Chemicals

	GEMAS P	OOL CHEMICALS DOS	ING INSTRUCTIONS
PRODUCT	DESCRIPTION	FUNCTION	DOSAGE
FACTCHLOD	Stabilized Granular	Disinfection	0,5 kg/day for 100 m³ pool water (Public pools) 0,5 kg/week for 100 m³ pool water (Residential pools)
FASTCHLOR	Dichlorine	Shocking	0,6-1 kg/15day for 100 m³ pool water (Public pools) 0,6-1 kg/month for 100 m³ pool water (Residential pools)
FASTCHLOR 100	Stabilized Granular Trichlorine	Disinfection	0,35 kg/day for 100 m³ pool water (Public pools) 0,35 kg/week for 100 m³ pool water (Residential pools)
TABCHLOR 200 gr	Stabilized Trichlorine Tablet	Disinfection	1 Tablet for 30 m³ pool water (once 10-12 days)
H.TRICHLOR T 200 gr	Stabilized Trichlorine Tablet	Disinfection	1 Tablet for 30 m³ pool water (once 10-12 days)
CALCIUM HYPOCHLORITE	%70 Granular/Tablet	Disinfection	200 gr/day for 100 m³ pool water
BROMINE	Bromine Tablet	Disinfection	400 gr/day for 30 m³ pool water
FASTCHLOR L	Sodium Hypochlorite %12	Disinfection	2,5-5 liters/day for 100 m³ pool water
CHLORSTAB	Isocyanuric Acid	Chlorine Stabilizer	5 kg first dose for 100 m³ pool water. Following doses according to test results max. 100 ppm
BESUM	Non-chlorine Shock	F 1.77	100 gr/week for 10 m³ pool water (Residential pools)
DECHLORAMIN	Treatment Agent	For clarifying pool water	150 gr/week for 10 m³ pool water (Public pools)
OXYTRONE	Granular	Oxygen based organic cleaner	1000-1300 gr/week dose per 100 m³ pool water (Residential pools) 1500-1800 gr/week dose per 100 m³ pool water (Public pools)
CHLORINE-OUT	Gralunar	Chlorine and chlorine remover	300 gr dose per 100 m³ pool water to reduce total chlorine by 1 ppm
pH (-) DOWN	Granular	pH Down	1 kg for 100 m³ pool water decreases pH by 0,1 unit
pH (-) DOWN L	Liquid	pH Down	1 liter for 100 m³ pool water decreases pH by 1 unit
pH (-) DOWN HCI	Liquid	pH Reduce and Limescale cleaner	1 I dose per 100 m³ pool water reduces pH by 0,1 and alkalinity by 0,23 ppm
pH (+) UP	Granular	pH Up	1 kg for 100 m³ pool water increases pH by 0,1 unit
			First dosage of 1,5 liters. Weekly dosage of 0,5 liter afterwards (outdoor pool)
ALGEX	Liquid	Algicide	First dosage of 1,5 liters. Weekly dosage of 0,3 liter afterwards (indoor pool)
ALGEX PROTECTOR	Liquid	Algicide	First dosage of 1,5 liters. Weekly dosage of 0,5 liter afterwards (outdoor pool)
STARVEX	Liquid	Algicide	1 l dose for 50 m³ pool water. 0,5 l dose in following weeks.
PUREFLOCK L	Liquid	Flocculant	30-200 ml/day for 100 m³ pool water
CLEARFLOCK GEL	Mold Gel	Gel Flocculant	
PUREFLOCK C	Cartridge	Flocculant	1 cartridge/5-7 days for 60 m³ pool water
MULTIFLOCK C	Cartridge	Flocculant + Anti-Algea	1 cartridge/5-7 days for 60 m³ pool water
ACTIVE FLOCK	Liquid	Polisher	100 m³ pool water 30-200 ml/day
MIRACLEAR	Liquid	Super Shock Clerifier	1 l first dose for 100 m³ pool water. Same dose in following 3-4 week.
CALCEX FILTER	Granular	Anti Calcification	1 kg/15-30 days for each m³ of filter volume
CALSTAB	Liquid	Hardness Stabilization	100-400 ml for 10 m³ pool water.
CALCEX POOL	Liquid	Descaling Cleaner on Surface	Can be diluted at ratio of 1/5 or 1/10. Should be waited maximum 15 minutes.
SCALEX POOL	Liquid	For Cleaning Lime on Pool Surface	2,5-5 l per 100 m³ pool water
SCALEX	Liquid	Anti-Lime for Salt-Chlorine Generators	2,5 I first dose to 100 m³ pool water 375 ml/month or 2,5 l/6 month
SOOT-OFF	Liquid	Grease and dirt remover	Can be diluted at ratio of 1/5 or 1/10.
CLEAN GROUTING	Liquid	Grout cleaning	Can be diluted 1/5 or 1/10. Wait for 2-3 minutes and brush.
MORTAR-OFF	Liquid	Mortar cleaning	Apply on mortar. Brush with heavy duty bristles.
POOLWIC	Liquid	Winter Care Product	3 - 5 liter (According to hardness) to 100 m³ pool Re-dose in 2 months.



Pool Problems and Solutions



PROBLEM	CAUSE	EFFECT	SOLUTION
Dull looking cloudy water	Low chlorine stabilizer (cyanuric acid) high (>100 ppm)	The first stage of algae growth	Adjust pH with FASTCHLOR L and shock chlorination
On walls, pipes, filters, etc. stone formation	pH high, CaCO3 Solubility exceeded, alkalinity high	Pipes blocked increase in filter pressure	pH should be adjusted continuously
Eye and skin irritation	Unsuitable pH, ineffective chlorine due to chlorination with high amount	Increase in the amount of pollution	Adjust pH with FASTCHLOR and shocking chlorination
Constantly in an eye-catching level chlorine smell	Free chlorine low, due to false shock chlorination stabilizer and bound chlorine, high (>0.2 ppm)	Insufficient disinfection	Free chlorine should be 0.8-2.0 ppm and correct shock chlorination must be done
Foaming in pool water	High-dose algaecide use and organic pollution	Cost increase	Shock chlorination and use fresh water
Non shiny water	Filtration low pH high	Insoluble suspended matter increase by amount	Check the filter, decrease pH
Colorful but clear water	Metal ions are present in the water	Metal oxidation	Adjust pH with FASTCHLOR shocking chlorinate and use CALSTAB ion holder
Bleaching in hair, clothing, vinyl coatings	Chlorine level is too high, free chlorine incorrectly measured	Cost increase due to excessive chlorine consumption	Lower the chlorine level
Colored particles present in the water	Low pH and corrosion	Metal oxidation	Raise pH
Green blurry water, slippery surfaces and algae	Low chlorine level too much stabilizer	Algae growth	Adjust pH, perform shock chlorination
Green or brown algae	Lower free chlorine in water	Inadequate disinfection and algae re-production	Adjust pH with FASTCHLOR shocking chlorine,use antialgae. Brush the surfaces and clean

Water Parameters of Pool Water

- (1) It is checked in the pools where chlorine compounds with stabilizers are used for disinfection of water.
- (2) Hydrogen peroxide should be within the range of 40-80 when "hydrogen peroxide + biguanide" is used for disinfection of water. In this case it is acceptible that pH 8.2, ammonium 1.5 and total level of alkalinity suitable up to level 220. No free chlorine measurement is done in these pools but hydrogen peroxide and biguanide are measured.
- (3) It is checked in the pools where Chlorine and chlorinated compounds are used for water disinfection.(4) It is the exact required level where
- Ozone, UV, chlorine dioxide and other disinfection systems are used in the pools for water disinfection.

 NOTE: Hydrogen peroxide, biguanide and free chlorine measurements are made on pool site.

 Our company reserves the right to make changes in all listed products without notifying the customer.

Annex-1 Chemical Properties

Parameter	Analysis Range	Unit	Limit \ Minimum	/alues Maximum
Cyanuric acid (1)			-	100
Biguanid ⁽²⁾			2	30
Hydrogen peroxide (2)			40	80
pH ⁽²⁾			6,5	7,8
Ammonium (2)				0,5
Nitrite				0,5
Nitrate	Once a month	mg/l		50
Copper				1
Aluminum				0,2
Total alkalinity (2) (CaCO ₃)			30	180
Bound chlorine (3)				0,2
Indoor swimming pool water free chlorine (3)			1	1,5
Open swimming pool water free chlorine (3)			1	3
Free chlorine ⁽⁴⁾			0,3	0,6



Test Kits with Liquid Reagents

TEST KIT FOR CHLORINE AND pH WITH LIQUID REAGENTS.

Complete with 25 cc OTO and PHENOL RED Liquid reagents.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	08211	1	0,170	



LIQUID REAGENTS

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• CHLORINE OTO - 25 cc	082111	1	0,028	
• PHENOL RED - 25 cc	082112	1	0,028	



TOTAL HARDNESS TEST KIT. By titration method.

De	escription	Code	Pieces/ box	Weight Kg	Volume m ³
		08221	7	1,120	0,006



Test Kits with Tablet Reagents

TEST KIT WITH TABLETS.

For Free Chlorine and pH. Includes 10 pieces of test agents.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	08111	10	0,160	0,0004



TEST KIT FOR CHLORINE/BROMINE, pH & ALKALINITY

Description	Code	Pieces/ box	Weight Kg	Volume m ³
PT 500	08131	1	0,160	0,0004





Stick Test Kits



AQUACHECK "YELLOW" STICK TEST KITS.

Indicates pH, Free Chlorine, Total Alkalinity and Cyanuric Acid Level. Colormetric based measure system. Includes 50 pieces of test sticks.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
AQUACHECK YELLOW - For 50 Tests	0831	1	0,050	0,0008



POOL ID STRIP SALINITY TEST KIT.

It measures salinity between 0 - 8000 ppm. There are 20 pieces of test strips in the box.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
SALINITY TEST KIT	0835	1		

Electronic Photometer - Test Strips & Readers





AQUACHECK "TRUTEST" DIGITAL TEST STRIPS & READER.

pH, free chlorine and total alkalinity. After the AQUCHECK TRUTEST test strips are immersed in the pool water, the measurement is made by placing it on the Trutest device. It eliminates the risk of making wrong measurements due to users distinguishing colours incorrectly. It reports on the left of the screen that the measured values are low, ideal or high. Keeps the last 9 measurements in its memory. For bromine measurement, multiply the Chlorine measurement obtained by 2.2. Works with 2 alkaline batteries.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
AQUACHECK TRUTEST	0841	1	0,236	0,0018
• AQUACHECK TRUTEST	08411	1	0,042	0,0008
• Replacement Test Strips - 50 pcs				

Photometer Test Kits

"POOLLAB"

Photometric test kit. Total / Bound Chlorine, Ph, Alkalinity, Cyanuric Acid, Total Hardness, Active Oxygen, Bromine, Chlordioxide, Ozone, Hydrogen peroxide can be measured. There are reagents for the first four parameters in the kit. Other reagents should be purchased extra on request. It can be connected to a **smartphone** via Bluetooth. When the test results are synchronized, the software and the preloaded chemicals in the application will suggest the required dose. The user can print these results. The poollab, which is an IP68 rated device, can be safely submersed into the body of water to be sampled.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
POOLLAB 5 in 1 kit	0844	1		



Photometer Test Kits

"POOLLAB 2.0"

Poollab 2.0 Photometric Tester. It can measure 24 different parameters. It can measure 3 parameters at the same time with 3 chambers side by side. With IP68 protection, it allows easy sampling by immersing it in the pool water. It automatically synchronizes with Labcom software over the Cloud with Bluetooth and Wi-fi features. Test results are recorded under the account names determined by the user. With the LabCom software, the results can be printed out, the active chlorine in the water or the required chemical doses can be calculated. Complete with tablets for pH, Total Chlorine, Free Cloe, Alkalinity and Cyanuric Acid Tests.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
POOLLAB 2.0	0845	1		



"PRIMELAB" Multitest.

Photometric test kit. Options with 5 in 1 kit which measures Total/Combined Chlorine, pH, Alkalinity, Total Hardness and Cyanuric Acid. Pro kit includes parameters Total / Combined Chlorine, Bromine, pH, Alkalinity, Cyanuric Acid, Ammonify, Nitrite, Nitrat, Copper, Aluminium, Hidrogen Peroxide, Biguanide, Color and Turbidity).

Complete with all necessary agents calibration and measurement equipment and carrier case. For spare part agent prices, please see page 201. It can be connected via bluetooth to smartphones, tablets and PCs.

The necessary chemical dosages and comments to the test results are given as suggestions with the help of software or application.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Primelab 5 in 1 Kit	0848	1		
Primelab Pro Kit	0849	1		
 Parameter Addition 	0843			





Test Kits With Disc Comparator

With 5 in 1 kit, Free chlorine, pH, total alkalinity, total hardness and cyanuric acid are measured. The result is given by comparing the sample color with color disc. Complete with all agents, sample tubes and carrier bag.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 5 in 1 Test Kit , with disc comparator	0850	1		
 Phosphate Test Kit, with disc comparator 	0851	1		







0850



Tablet Reagents

"DPD1 FREE CHLORINE REAGENT. (1 Folio includes 10 tablets)



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• DPD1 – Folio	081111	50	0,128	0,001
• Box inc. 500 pcs	0811111	1	0,170	0,0009
• Box inc. 1000 pcs	08111112	1		

PHENOL RED REAGENT. (1 Folio includes 10 tablets)



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Phenol Red – Folio	081112	50	0,128	0,001
• Box inc. 500 pcs	0811121	1		
• Box inc. 1000 pcs	0811122	1		

DPD3 DEPENDENT CHLORINE AGENT. (1 Folio includes 10 tablets)


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• DPD3 – Folio	081113	50	0,128	0,001
• Box inc. 500 pcs	0811131	1	0,170	0,0009
• Box inc. 1000 pcs	0811132	1		

Photometer Tablet Reagents

Below spare agents for 250 pieces packages. PLS. ASK PRICE.

Description	Description
TABLET REAGENTS	Chlor dioxide - Glycine
Alkalinity - M	Total Hardness
Cholorine - DPD1	Iron
Cholorine - DPD3	Phosphate - No:1
Cyanuric Acid	Phosphate - No:2
Calcium Hardness	Sodium Hypochloride 1
pH - Phenol Red	Sodium Hypochloride 2
Aluminium - No:1	Sulphate
Aluminium - No:2	Urea - Amonia No:1
Ammonia - No:1	Urea - Amonia No:2
Ammonia - No:2	Zinc - Copper Zinc
Bromine - DPD1	Zinc - EDTA
Bromine - Glycine	
Copper - No:1	LIQUID REAGENTS
Copper - No:2	Hydrogen Peroxide - No:1
Nitrite	Hydrogen Peroxide - No:2
Ozone - DPD1	Nitrate - No:1
Ozone - DPD2	Nitrate - No:2
Ozone - DPD3	Chlorine - No:1
PHMB	Chlorine - No:2
Chloramine DPD1	Chlorine - No:3
Chloramine DPD2	Iron - No:1
Chloramine DPD3	Iron - No:2
Chloride - No:1	рН
Chloride - No:2	Urea - No:3
Chlor dioxide - DPD1	Urea - No:4

We reserve our right to change all or part of the features of the articles or contents of this document, without prior notice.





"Residential" Robotic Pool Cleaners



PLECOS "S2" ROBOTIC POOL CLEANERS.

The Plecos S2 is designed for residential pools up to 12 m in length. It features a 24 V motor unit and an 18 m cable. The cleaning cycle duration is 2 hours, and it has an automatic program for optimal pool cleaning. The S2 cleans the pool surface, walls, and waterline. It adjusts the vacuum according to slipperiness during climbing on the walls to prevent slipping. With the patented POWERSTREAM technology, it offers effective movement and maneuvering features. The active brush moves twice as fast as the robot, removing algae and bacteria from the walls and bottom. The S2 operates in standard cleaning mode with a new generation energy-saving power unit. It has a 2-layer filtering system with a cartridge filter for finer debris and a net filter for coarse dust. The S2 comes with a warranty period of 3 years.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
"S2" Automatic Pool Cleaner	091187	1	12,000	



PLECOS "M4" ROBOTIC POOL CLEANERS.

The Plecos M4 is suitable for home pools between 10-12 m in length. It features a self-powered 24 V motor with a low micron cartridge or mesh filter. It comes with an 18 m cable and has a flow rate of 16 m³/h. The cleaning period is 2.5 hours, and it is self-programmed and microprocessor-controlled for optimal pool cleaning. The M4 climbs the pool walls up to the waterline and offers weekly programming with the options once a day, every two days, and every three days' via the power supply unit. With smartphone application, it provides manual use and weekly programming via the Internet. It includes triple active brushes and easy interchangeable filter panels. GYROSCOPE technology advanced system ensures accurate scanning for systematic coverage of floor, walls and waterline. Without caddy. The warranty period is 3 years.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• "M4" Automatic Pool Cleaner	091188	1	24,000	
• "M4" Caddy	091188C	1		

"Cordless" Robotic Pool Cleaners



PLECOS "FREE" ROBOTIC POOL CLEANERS.

Elevate Your Cordless Pool Cleaning Experience. With the app, you can see the filter status, choose between customized cleaning programs and activate Eco-Mode to enjoy a clean pool for 1-2 weeks on a single charge. The Click-Up™ allows you to stop the robot mid-cycle and to call it to climb up for easy removal. The Plecos FREE is suitable for pools with PVC, fiberglass, and stone surfaces, mosaic and ceramic tiles. This robot is the perfect choice for a sparkling clean pool with minimal effort and maximum results. The warranty period is 3 years.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
"FREE" Automatic Pool Cleaner - Cordless	091192	1	12,000	



Automatic Pool Cleaners for Commercial Pools

PLECOS "W9i" ROBOTIC POOL CLEANERS.

The Plecos W9i is effective for pools up to 20 m in length. It features a double motion axle for pool scanning and comes with 70-micron permanent or disposable filters. The W9i has a 24 m cable, a 24 V motor, a flow rate of 16 m³/h, and a 3-hour cleaning cycle duration. It includes a patented swivel system to prevent cable damage. Climbing interval is 8 minutes. Comes with a caddy. The warranty period is 2 years.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
"W9i" Automatic Pool Cleaner	091190	1	23,000	



PLECOS "W10" ROBOTIC POOL CLEANERS.

The Plecos W10 is user-friendly and suitable for pools up to 25 m in length. It features a double motion axle for efficient pool scanning in 4 hours and comes with 70-micron permanent or disposable filters. The W10 has a 24 m cable, a 24V motor, a flow rate of 16 m³/h, and a 3-hour cleaning cycle duration. It includes a patented swivel system to prevent cable damage. Climbing interval is 8 minutes. **The warranty period is 3 years**.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
"W10" Automatic Pool Cleaner	091189	1	25,000	
"W10" Caddy	091189C	1		
"W10" Caddy	091189C	1		





Automatic Pool Cleaners for Commercial Pools

The 50-r

PLECOS "W30XL" ROBOTIC POOL CLEANER.

The Plecos W30XL is designed for commercial pools up to 60 m in length. It comes with 50-micron filters in three different types: standard, coarse, and disposable. The W30XL includes a caddy, a user-friendly interactive control panel, and a remote control. It guarantees 100% pool scanning using navigation technology unique to automatic pool cleaners. The cleaner can memorize four different pools, and it comes with a warranty period of 2 years.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
"W30XL" Auto. Pool Cleaner	091191	1	101,000	0,150



W30XL entrance to pool.

Crystal clear pools with the 21st century technology

"Plecos W30XL"







W30XL can be controlled remotely.









Places W30 YI

50 microns filter system

Digital control panel

Remote control device

Active Brush System: Hard brushes of polyethylene plastic brushes and rubs the pool and prevents algea and bacteria. Small brushes on the sides reaches to every edge, corner and water line.

Scanning Method: W30XL has a navigation brain unique in the market which guarantees 100% scanning.

Filtration: Automatic pool cleaners cleans the pool with their integrated filters. This is an advantage compared to manual cleaners which uses the pool filter, as they cause faster blockage of the filter. This results with more back washing, so more loss of water and chemicals. As all other automatic pool cleaners

W30XL is environmentally-friendly and economic in this sense. Moreover, with 40 m³/h vacuum rate and 50 micron filter W30XL offers you much more than manual cleaning.

MMI: All the control of the robot is realized with the interactive digital interface panel which is called MMI. With this state of the art device you may set all the parameters of the robot, give comment for delayed start up in order to wait for the sedimentation of dirt on the floor, or give comment for automatically going in and out of the water. You may also control the robot manually with the remote control. Although W30XL is a heavy duty robot, it is the leading public pool cleaner in the market with the highest performance/cost ratio in the market and with the easiness of its use and maintenance.



Rechargeable Cordless Vacuum Cleaner

RECHARGEABLE CORDLESS VACUUM CLEANER.

It is an ideal pool cleaner for all types and sizes of pools, which can be carried by hand with a long and telescopic pole, without the need for a hose and electrical cable, and operates with a rechargeable battery. The product is equipped with a removable brush head, which can conveniently brush the floor, walls and corners of the pool. This device with a battery capacity of 2500mAh can be used for up to 60 minutes without running out of charge. Replaceable-removable brush head. Besides its own 2 meter telescopic pole, it can also be used with Gemas telescopic poles with clip. 2 years warranty.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Rechargable Cordless Vacuum Cleaner	091230	1	2,000	

PS: Compatible with all GEMAS Telescopic Poles



Longest

pole size






niw S

Automatic Suction Pool Cleaner

GEMAS "S250 AUTOMATIC SUCTION POOL CLEANER".

Operates on hydraulic vacuuming principle. Complete with 11 m special hose.



Removable brush head



HOSE FOR GEMAS "S250 AUTOMATIC SUCTION POOL CLEANER". 1 m

Description	Code	Pieces/ box	Weight Kg	Volume m ³
S250 Hose	09123Y01	1		

Compact Suction Cleaner Unit - Cartridge Filter

Compact Suction Cleaner.

Assembled on a st. steel wheel caddy, complete with cartridge filter, monophase self-priming pump, Poolvac manual cleaner, hose, telescopic pole and checkvalve. Fuse and 18 m cable included. Designed for pools which do not have suction inlet. Can be used as a filtration unit as well.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 11 m³/h - 0,75 HP Pump	093101	1	37,000	
• 16 m³/h - 1 HP Pump	093102	1	40,000	




Compact Suction Cleaner Unit - Sand Filter

Compact Suction Cleaner.

Assembled on a st. steel wheel caddy, complete with sand filter, filtration media, monophase self-priming pump, Poolvac manual cleaner, hose, telescopic pole. Fuse and 18 m cable included. Designed for pools which do not have suction inlet. Can be used as a filtration unit as well. Sand is included in the price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
6 m ³ /h. Sand Filter - 0,5 HP Pump	093103	1		
DC. Diagon ack price for larger connection				







Manual Pool Cleaners



GEMAS "POOLVAC" Pool Cleaner.

For concrete pools. Anodized aluminum body.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• With butterfly nut, 11/2"-L=346 mm	092111	1	2,382	0,012
• With butterfly nut, 11/2"-L=456 mm	092112	1	3,094	0,015
• With clip, 11/2"-L=346 mm	092121	1	2,388	0,012
• With clip, 11/2" -L=456 mm	092122	1	3,220	0,015
• With butterfly nut, 2"-L=456 mm	0921121	1	3,060	0,015
• With clip, 2"-L=456 mm	0921122	1	3,128	0,015



GEMAS "FOLD-VAC" Pool Cleaner.

For concrete pools. Aluminum body can be folded. Efficient cleaning is provided at pool corners and edges. Each model is 1,5" and 2" hose connection with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 35,5 cm	092211	1	3,000	0,017
• Width: 45,5 cm	092212	1	3,500	0,018



GEMAS "POOLKING" Pool Cleaner.

For concrete pools with wide dimensions. Aluminum body. Wheel group and hose connection made of chromated bronze and stainless steel. 2" Hose connection. Cleaner scanning width, $L\!=\!80~\text{cm}$

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pull Type	09213	1	10,008	0,020
With fork for using with Handle	09214	1	11,516	0,032



GEMAS "LEAF" Pool Cleaner.

Plastic body with brush. No wheels, for liner and concrete pools. Operates with water jet. 1,5" hose connection with clip. Ø38 cm body dia.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09222	1	0,860	
Spare bag	092221	1		



Manual Pool Cleaners - Liner

GEMAS "LUXVAC" POOL CLEANER.

Plastic Body. Brushes on body for concrete and liner pools. 1,5" hose connection. Pole connection is with clip. Control on top for vacuum strength.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Luxvac Pool Cleaner	09215	1		



GEMAS "TRIANGLE" POOL CLEANER.

Plastic glare body. Brushes on body for concrete and liner pools. 1,5" hose connection. Pole connection is with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Triangle Pool Cleaner	09217	1	1,380	0,013



GEMAS "BUTTERFLY" POOL CLEANER.

Plastic Body. Brushes on body for concrete and liner pools. 1,5" hose connection. Pole connection is with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Butterfly Pool Cleaner	09218	1	0,868	0,007
Butterfly Pool Cleaner - Side Brush	09219	1	1,048	0,008



GEMAS "HEAVY-DUTY FLEX" POOL CLEANER.

Plastic Body. 2500 gr weight for heavy duty usage. Wheels with Adjustable height. Suitable for both concrete and liner pools d38 mm hose connection. Pole connection with clip. 1,5" hose connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Heavy-Duty Flex	09224	1		
• Ditto, with brush on bottom	09225	1		
Metallic Handle	0922401	1		



GEMAS "FLEX" POOL CLEANER.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Flex Pool Cleaner	09220	1		
Ditto, with side brushes	09223	1		



"AQUAQUIK" POOL AND SPA CLEANER.

Manual cleaner with hand pump for easy cleaning in pools and spas. Works without hose. Package is complete with flat scoop, brush, wide and narrow suction heads and wall assembly part. Length:140 cm. Dia: 7,5 cm

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Pool & SPA VAC	09216	1	1,418	0,060







Vacuum Hoses



GEMAS VACUUM HOSE.

Economic blue and white colored, 30 m roll. Without adapter.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• D.38 mm, 1,5"- Price per meter.	09511	30	4,992	0,152
• D.50 mm, 2"- Price per meter.	09512	30	7,696	0,298



GEMAS VACUUM HOSE.

Blue or white colored. Different lengths of D.38 mm, special hose adapter included. Sold in hox

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" - 8 m	095111	1	2,784	0,073
• 1,5" - 10 m	095112	1	3,112	0,073
• 1,5" - 12 m	095113	1	3,340	0,073
• 1,5" - 15 m	095114	1	3,932	0,073



GEMAS VACUUM HOSE.

Blue or white colored. Different lengths of D.50 mm, special hose adapter included.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" - 12 m	095121	1	4,646	0,127
• 2" - 15 m	095122	1	5,372	0,127
• 2" - 18 m	095123	1	6,098	0,127



GEMAS "EVAPOOL VACUUM HOSE".

Economic blue striped, white colored. 30 m rolls.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• D.38 mm, 1,5"- Price per meter.	09511E	30 m		
• D.50 mm, 2" - Price per meter.	09512E	30 m		



GEMAS "EVAPOOL VACUUM HOSE".

Blue striped, white colored. Different lengths of D.38 mm. With special adapter. Sold in box.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" - 8 m	09511E1			
• 1,5" - 10 m	09511E2			
• 1,5" - 12 m	09511E3			
• 1,5" - 15 m	09511E4			



GEMAS "EVAPOOL VACUUM HOSE".

Blue striped, white colored. Different lengths of D.50 mm. With special adapter. Sold in box.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2" - 12 m	09512E1			
• 2" - 15 m	09512E2			
• 2" - 18 m	09512E4			

Hose Adapters and Clips

GEMAS LINK CONNECTOR.

For connection of Ø38 mm hose to "04134" suction inlet, in white ABS plastic. 1,5" threaded.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09821	20	0,812	0,006



BULLDOG CLIP. For hose fixing, in stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For Ø38 mm. (1,5") hose	09831	100	3,000	0,001
• For Ø50 mm. (2") hose	09832	50	1,800	0,002



GEMAS HOSE CUFFS. In flexible PVC plastic, threaded inside.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For Ø38 mm. (1,5") hose	09811	120	6,000	0,028
• For Ø50 mm. (2") hose	09812	120	7,200	0,028
• For both Ø38 mm and Ø50 mm Gemas Eva hose.	09813	120	10,800	0,064
• For both Ø38 mm and Ø50 mm Gemas hose.	09814	120	10,800	0,064



GEMAS THREADED HOSE CUFFS. In PVC plastic, 1,5" male threaded.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
For Ø38 mm.	09841		0,040	



GEMAS HOSE COLLECTION WHEEL.

Made of ABS plastic. 15 m of D.38 Hose collection capacity.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Hose wheel	09513	1	2,678	0,044



GEMAS LEAF TRAP.

Transparent body. Designed to assemble on vacuum hose. Can be cleaned easily. Complete with hose connections, Ø38 mm. (please ask adaptors for Ø50 mm).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Leaf Trap	09851	1		





Leaf Scoops



GEMAS LEAF SCOOP IN PLASTIC. Fixing with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09710	12	3,350	0,053



GEMAS LEAF SKIMMER IN PLASTIC. Fixing with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09720	12	3,780	0,053



GEMAS "LUX" LEAF SCOOP IN PLASTIC. Fixing with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09730	12	7,950	0,085



GEMAS "ECONOMIC" LEAF SCOOP IN PLASTIC. Fixing with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09740	12		





Pool Brushes

GEMAS VACUUM BRUSH IN PLASTIC.

Pool wall brush, standard. With hose connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09624	1		



GEMAS WALL BRUSH IN PLASTIC. Pool wall brush, 60 cm, standard.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09622	1		



GEMAS WALL BRUSH IN PLASTIC. Pool wall brush, 90 cm, standard.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09623	1		



GEMAS CURVED BRUSH IN PLASTIC. Pool wall brush, 46 cm, standard.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09620	1	0,348	0,002



GEMAS FLOOR BRUSH IN PLASTIC.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Flat 12,5 cm	09611			
• Flat 26 cm	09626	2	0,244	0,002



GEMAS ALGAE BRUSH WITH STAINLES STEEL BRISTLES.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• W=12,50 cm	09612	1	0,160	0,001
• W=25,00 cm	09613	1	0,304	0,002



GEMAS CORNER BRUSH. Corner Brush. Circular. Plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09640	1	0,114	0,001





Auxiliary Cleaning Equipment



GEMAS SCRUBBING PAD. With plastic handle.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09633			



GEMAS SCRUBBING PAD. Plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09632		0,050	0,050



GEMAS "LUX" LEAF SCOOP IN PLASTIC. Fixing with clip.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09630		0,296	0,001



GEMAS PUMICE. Plastic clip body. Used for algae cleaning between ceramics.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09631		0,096	



GEMAS LIFEGUARD HOOK. Aluminum.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09800		0.408	0.044



GEMAS LIFEGUARD RING. Plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Big Life Buoy 440x700	09809	1		
Small Life Buoy	09810	1		



GEMAS LIFEGUARD RING - WALL HANG PART. Stainless Steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	09815	1		



Telescopic Handles

TELESCOPIC HANDLES.

In anodized aluminium (natural or gold color). Connection via clip or butterfly nut.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 x 1,5 m	09410	1	0,430	0,159
• 1 x 3 m	09420	1	0,890	0,312
• 2 x 2 m	09430	1	1,100	0,220
• 2 x 2,4 m	09490	1	1,600	0,261
• 2 x 3 m	09440	1	1,500	0,323
• 3 x 1,5 m	09450	1	1,300	0,169
• 3 x 2 m	09460	1	1,540	0,220
• 3 x 3 m	09470	1	2,200	0,328
• 3 x 6 m	09480	1	4,200	0,630



TELESCOPIC HANDLE.

Aluminum, blue anodized. Stripy lower body.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2 x 1,8 m	09489	1	0,800	0,262
• 2 x 2,4 m	09491	1	1,000	0,262
• 2 x 3,0 m Blue	09492	1		





WALL HANG SET FOR TELESCOPIC HANDLE.

Made of Plastic. Complete with screws.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Wall Hang Set	09400	1	0,160	0,001





Pool Thermometers



Pool Thermometers, floating.

Code	Pieces/ box	Weight Kg	Volume m ³
0414	24		
0412	24		
0415	24		
C	0414 0412	0414 24 0412 24	0414 24 0412 24



Pool Thermometer, to be connected to the ladder.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Thermometer - Floating Type	10411	1	0,090	
• To be connected to the ladder	10421	1	0,068	



Pool Thermometer, floating and circular scaled, Ø190 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	10431	1	0,298	0,010



Digital Pool Thermometer with Solar Battery, Ø80 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	10432	1	0,140	0,001

Pool Ice Barrier



Pool Ice Barrier. Made of Plastic. 49 x 24 cm size floating barrier is arrayed all around the pool perimeter. Protects the pool coating by absorbing the expansion of freezing at very low atmospheric temperature.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ice Barrier	1297105	Piece		



Heating Equipments and Dehumidifiers

Pool Heat Pumps

GEMAS Heat Pump.

Uses the extant heat in the air for 80% of the total energy required to heat up the pool. Consumes electrical energy only for the 20% of the required heat.

- Operational costs are 80% lower compared to natural gas. System can be used for heating or cooling. It is the only solution for shock pools.
- The heat exchanger that transfers energy from air to water is made of titanium. It can be installed in the pools with sea water.
- An electronic-digital control board on the device that also shows the temperature of the water.
- Heating or cooling modes are also selected with the help of this board.
- The heat pump can easily be installed on the extant pool installations without any infrastructural problems.
- The heat pump is designed to change the water temperature by $\pm 12^{\circ}\text{C}$ in 5 days when the outside temperature 20°C.
- Using a solar pool cover that provides isolation will shorten the time and reduce energy consumption.
- The heat pump does not work efficiently when the ambient temperature is below 10°C.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 030MS3 - Heating/Cooling, 12,6 kW	101313	1		
• 040MS3 - Heating/Cooling, 18,9 kW	101314	1		
• 060MS3 - Heating/Cooling, 25,2 kW	101315	1		
• 080MS3 - Heating/Cooling, 33,8 kW	101317	1		
• 100MS3 - Heating/Cooling, 42 kW	101318	1		
• 120MS3 - Heating/Cooling, 50,4 kW	101320	1		



Below pool volumes are valid during the heating period (1 may - 15 september) for the conditions when the system is on for 15 hours a day and the pool is covered with an isolated cover during the night. If these conditions cannot be fulfilled, a larger model is recommended.

Model	FPHC	030T	045T	060T3	080T3	100T3	120T3
Cooling gas		R410A	R410A	R410A	R410A	R410A	R410A
Heating Capacity*	kW	12,6	18,9	25,2	33,0	42,0	50,4
COP* A:24/W:28	W/W	5,5	5,5	5,5	5,5	5,5	5,5
Input Power*	kW	2,29	3,44	4,58	6,11	7,64	9,16
Input Current*	Α	10,4	15,6	8,7	11,6	14,5	17,4
Heating Capacity**	kW	10,5	15,8	21,0	28,0	35,0	42,0
COP** A:15/W:28	W/W	4,6	4,6	4,6	4,6	4,6	4,6
Input Power**	kW	2,28	3,43	4,57	6,09	7,61	9 <u>,</u> 13
Input Current **	Α	10,4	15,6	8,7	11,6	14,5	17,3
Havuz Hacmi ****	m^3	30	50	65	80	130	180
Cooling Capacity (A35W28) -	kW	7,5	11,3	15,0	20,0	25,0	30,0
Cooling Capacity (ASSW20)	BTU/h	25590	38385	51180	68240	85300	102360
COP A:35/W:28	W/W	2,8	2,8	2,8	2,8	2,8	2,8
Input Power	kW	2,68	4,02	5,36	7,14	8,93	10,71
Input Current	Α	13,4	20,1	10,7	14,3	17,9	21,4
Power Supply	V/PH/Hz	220/1/50	220/1/50	380/3/50	380/3/50	380/3/50	380/3/50
Compressor		Rotary	Rotary	Scroll	Scroll	Scroll	Scroll
Compressor Qty		1	1	1	2	2	2
Fan Qty		1	1	1	2	2	2
Noise	dB(A)	52	54	55	58	60	62
Water Out let/Water In let	inch	1-1/2"	1-1/2"	1-1/2"	2"	2"	2"
Water Flow Volume	m³/h	3,61	5,42	7,22	9,63	12,04	14,45
Water Pressure Drop	kpa	15	16	16	18	18	18
Fan Direction		Vertical	Vertical	Vertical	Vertical	Vertical	Vertical
Unit Net Dimensions (L/M/H)	mm	640/590/790	710/660/940	810/660/940	810/660/990	1450/730/1135	1450/730/1335
Unit Shipping Dimensions (L/M/H)) mm	680/630/910	750/700/1060	850/700/1060	850/700/1110	1520/750/1290	1520/750/1490
Net Weight	kg	80	98	113	240	260	280
Shipping Weight	kg	88	120	125	270	290	310



101313



101315



101317



101320

Heating Equipments and Dehumidifiers.



Pool Heat Pumps



Models with Inverter:

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• FIP7S - Heating: 7.80 kW / Cooling, 4.30 kW	101325	1		
• FIP10S - Heating: 10.60 kW / Cooling, 5.90 kW	101326	1		
• FIP13S - Heating: 13.70 kW / Cooling, 7.30 kW	101327	1		
• FIP17S - Heating: 17.20 kW / Cooling, 9.50 kW	101329	1		
• FIP21S - Heating: 21.40 kW / Cooling, 11.60 kW	101334	1		
• FIP30S - Heating: 30.00 kW / Cooling, 15.90 kW	101335	1		

Heat Exchangers, Shell & Tube Type



GEMAS Heat Exchangers, Shell and Tube Type.

Made of AISI 316 quality Stainless Steel. Max. pressure 10 bars. Operated by 90-70 °C hot water from the boiler. Connection cuffs are not included.

Description	Code	Pieces/ box	Weight \	/olume m³
• 22.000 kcal/h Conn.: Pool side 1,5"- boiler side 0,75	101210	1		
• 35.000 kcal/h Conn.: Pool side 1,5"- boiler side 0,75	101211	1		
• 40.000 kcal/h Conn.: Pool side 1,5"- boiler side 0,75	101217	1		
• 65,000 kcal/h Conn.: Pool side 1,5"- boiler side 1"	101212	1		
• 80.000 kcal/h Conn.: Pool side 2"- boiler side 1"	101218	1		
• 90.000 kcal/h Conn.: Pool side 2"- boiler side 2x1"	101213	1		
• 110.000 kcal/h Conn.: Pool side 2"- boiler side 1"	101219	1		
• 180.000 kcal/h Conn.: Pool side 2"- boiler side 2x1,5"	101214	1		
• 220.000 kcal/h Conn.: Pool side 2"- boiler side 2x2"	101220	1		
• 250.000 kcal/h Conn.: Pool side 2"- boiler side 2x2"	101215	1		
• 330.000 kcal/h Conn.: Pool side 2"- boiler side 2x2"	101221	1		
• 400.000 kcal/h Conn.: Pool side 2"- boiler side 2x2"	101216	1		
St. Steel Wall Clampset	10121101	1		



Heat Exchangers, Shell and Tube Type. With plastic body, AISI 316/Titanium-Corrugated Metal Coil. The plastic body is resistant to high pressure and corrosion. It is attractive in terms of cost advantage and quality. It works with hot water (90/70°C) from the boiler. Max. pressure: Primary (boiler side) circuit 6 bar, secondary (poolside) 2 bar. Connection fittings are ABS, 0-rings are silicone.

Description	Code	Pieces/ Weight Volume box Kg m ³
• D-KWT 25, 25 kW - 21,500 kcal/h, AISI 316	101201	1
• D-KWT 45, 45 kW - 39,560 kcal/h, AISI 316	101202	1
• D-KWT 85, 85 kW - 78,260 kcal/h, AISI 316	101203	1
• D-KWT 105, 105 kW - 108,360 kcal/h, AISI 316	101204	1
D-KWT 25, Titanium	101201T	1
D-KWT 45, Titanium	101202T	1
• D-KWT 85, Titanium	101203T	1
D-KWT 105, Titanium	101204T	1







Heating Equipments and Dehumidifiers


Heat Exchangers, Shell & Tube Type

Model		D-KWT 25	D-KWT 45	D-KWT 85	D-KWT 105
Heating Capacity	kw	25	45	91	126
Heating Capacity	kcal/h	21.500	39.560	78.260	108.360
Temperature difference	°C	70 = 0.36 kW/°C	70 = 0.66 kW/°C	70 = 1.3 kW/°C	70 = 1.8 kW/°C
Area	m ²	0.09	0.15	0.33	0.54
Flow Primary*	m³/h	2	2	2	2
Flow Secondary*	m³/h	8	10	12	15
Pressure Loss Primary*	bar	0.10	0.15	0.28	0.36
Pressure Loss Secondary*	bar	0.11	0.15	0.22	0.30
Max. Pressure Primary*	bar	6	6	6	6
Max. Pressure Secondary*	bar	2	2	2	2
Outer Body		PP 30% Fiberglass	PP 30% Fiberglass	PP 30% Fiberglass	PP 30% Fiberglass
Connection Socket		ABS	ABS	ABS	ABS
0-ring		Silicon	Silicon	Silicon	Silicon
Spiral Hose		AISI 316 / Titanium	AISI 316 / Titanium	AISI 316 / Titanium	AISI 316 / Titanium
Weight	kg	1.8	2.2	3.6	5.3
Packaging Volume	m³	0.079	0.095	0.162	0.233


^{*}Primary: Heating fluid, Secondary: Heating fluid (Pool water)

^{**}The technical value table above also applies to Gemas Shell and Tube Type Heat Exchangers.

	Dimensions					
Heat Exchanger Type	A (mm)	B (mm)	C (mm)	D	E (mm)	F
101210 - 22.000 kcal/h	350	110	135	D.63-PN10	50	3/4"
101217 - 40.000 kcal/h	420	110	205	D.63-PN10	50	3/4"
101212 - 65.000 kcal/h	665	110	450	D.63-PN10	50	1″
101218 - 80.000 kcal/h	710	110	495	D.63-PN10	50	1″
101219 - 110.000 kcal/h	1020	110	805	D.63-PN10	50	1″



Dimensions							
A (mm)	B (mm)	C (mm)	D	E (mm)	F		
345	110	135	D.63-PN10	50	3/4"		
415	110	205	D.63-PN10	50	3/4"		
705	110	495	D.63-PN10	50	1″		
1015	110	805	D.63-PN10	50	1″		
	345 415 705	345 110 415 110 705 110	A (mm) B (mm) C (mm) 345 110 135 415 110 205 705 110 495	A (mm) B (mm) C (mm) D 345 110 135 D.63-PN10 415 110 205 D.63-PN10 705 110 495 D.63-PN10	A (mm) B (mm) C (mm) D E (mm) 345 110 135 D.63-PN10 50 415 110 205 D.63-PN10 50 705 110 495 D.63-PN10 50		



Shell & Tube Type Heat Exchanger Selection Chart

Model	D-KWT 25			D-KWT 45			D-KWT 85			D-KWT 105		
Pool Water	20 °C	24 °C	28 °C	20 °C	24 °C	28 °C	20 °C	24 °C	28 °C	20 °C	24 °C	28 °C
Heating Capacity	25 kW	23,5 kW	22,1 kW	46 kW	43,4 kW	40,7 kW	91 kW	85,8 kW	80,6 kW	126 kW	118.8 kW	111,6 kW
Primary Input/Output	90/79°C	90/79,6°C	90/80,2°C	90/69,6°C	90/70,8°C	90/72°C	90/49,6°C	90/52°C	90/54,2°C	90/34°C	90/37,3°C	90/40,5°C
Secondary Input/Output	20/22,7°C	24/26,5°C	28/30,4°C	20/24°C	24/27,8°C	28/31,5°C	20/26,5°C	24/30,2°C	28/33,8°C	20/27,2°C	24/30,8°C	28/34,4°C
Heating Capacity	21,5 kW	20 kW	18,6 kW	39 kW	36,4 kW	33,7 kW	78 kW	72,8 kW	67,6 kW	108 kW	100,8 kW	93,6 kW
Primary Input/Output	80/70,5°C	80/71,2°C	80/71,8°C	80/62,8°C	80/64°C	80/65,1°C	80/45,5°C	80/47,8°C	80/50,1°C	80/32,3°C	80/35,5°C	80/38,7°C
Secondary Input/Output	20/22,3°C	24/26,2°C	28/30°C	20/23,4°C	24/27,1°C	28/30,9°C	20/25,6°C	24/29,2°C	28/32,9°C	20/26,2°C	24/29,8°C	28/33,4°C
Heating Capacity	18 kW	16,5 kW	15,1 kW	32 kW	29,4 kW	26,7 kW	65 kW	59,8 kW	54,6 kW	90 kW	82,8 kW	75,6 kW
Primary Input/Output	70/62°C	70/62,8°C	70/63,4°C	70/55,9°C	70/57°C	70/58,3°C	70/41,4°C	70/43,7°C	70/46°C	70/30,4°C	70/33,6°C	70/36,7°C
Secondary Input/Output	20/21,9°C	24/25,8°C	28/29,6°C	20/22,8°C	24/26,5°C	28/30,3°C	20/24,7°C	24/28,3°C	28/31,9°C	20/25,2°C	24/28,8°C	28/32,4°C
Heating Capacity	14,5 kW	13 kW	11,6 kW	25 kW	22,4 kW	19,7 kW	52 kW	46,8 kW	41,6 kW	72 kW	64,8 kW	57,6 kW
Primary Input/Output	60/53,6°C	60/54,3°C	60/54,9°C	60/49°C	60/50,2°C	60/51,4°C	60/37,2°C	60/39,5°C	60/41,8°C	60/28,4°C	60/31,6°C	60/34,8°C
Secondary Input/Output	20/21,6°C	24/25,4°C	28/29,2°C	20/22,1°C	24/25,9°C	28/29,7	20/23,7°C	24/27,4°C	28/31°C	20/24,1°C	24/27,7°C	28/31,3°C
Heating Capacity	11 kW	9,5 kW	8,1 kW	18 kW	15,4 kW	12,7 kW	39 kW	33,8 kW	28,6 kW	54 kW	46,8 kW	39,6 kW
Primary Input/Output	50/45,2°C	50/45,9°C	50/46,5°C	50/42,1°C	50/43,3°C	50/44,5°C	50/33°C	50/35,2°C	50/37,5°C	50/26,4°C	50/29,6°C	50/32,7°C
Secondary Input/Output	20/21,2°C	24/25°C	28/28,9°C	20/21,5°C	24/25,3°C	28/29,1°C	20/22,8°C	24/26,4°C	28/30,1°C	20/23,1°C	24/26,7°C	28/30,3°C



Plate Heat Exchangers - High Pressure Drop



GEMAS Stainless Steel Plate Heat Exchanger. Made of AISI 316 quality stainless steel with nitryl or EPDM seal exchangers. Operated by 90-70°C hot water from boiler. Max. pressure 10 bars - Max. heat 130°C. Pressure loss from boiler and pool is 5 mwh.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 30,000 kcal/h, 504 Body, 5 Pl.	101251	1		
• 40,000 kcal/h, 504 Body, 6 Pl.	101252	1		
• 50,000 kcal/h, 504 Body, 7 Pl.	101253	1		
• 60,000 kcal/h, 504 Body, 8 Pl.	101254	1		
• 70,000 kcal/h, 504 Body, 10 Pl.	101255	1		
• 80,000 kcal/h, 504 Body, 10 Pl.	101256	1		
• 90,000 kcal/h, 504 Body, 12 Pl.	101257	1		
• 100,000 kcal/h, 504 Body, 12 Pl.	101258	1		
• 125,000 kcal/h, 504 Body, 16 Pl.	101259	1		
• 150,000 kcal/h, 504 Body, 20 Pl.	101261	1		
• 175,000 kcal/h, 504 Body, 24 Pl.	101262	1		
• 200,000 kcal/h, 514 Body, 10 Pl.	101263	1		
• 250,000 kcal/h, 514 Body, 12 Pl.	101264	1		
• 300,000 kcal/h, 514 Body, 14 Pl.	101265	1		
• 325,000 kcal/h, 514 Body, 14 Pl.	101266	1		
• 400,000 kcal/h, 514 Body, 18 Pl.	101267	1		
• 500,000 kcal/h, 514 Body, 22 Pl.	101268	1		
• 600,000 kcal/h, 514 Body, 28 Pl.	101269	1		
Thermostat and Solenoid Automation	101260	1		




504 BODY







101260 Optional



Body Model	A (mm)	B (mm)	C (mm)
504 BODY	490	La+Lc+35	200
514 BODY	942	La+Lc+40+20	350



SIDE









Plate Heat Exchangers - Low Pressure Drop


GEMAS Plate Heat Exchangers.


Plates made of AISI 316 quality stainless steel, with nitryl or EPDM gaskets. Body plates are 20 mm and painted over galvanization. Operated by 90-70°C hot water from boiler. Max Pressure 10 bar - Max temperature 130°C. Pressure losses from the sides of the pool and boiler are shown seperately for each capacity.

_	1 3	'	,			
	Description	Code			eight V Kg	olume m³
•	40,000 kcal/h: Pool side 1,02 mwh -	101231	1	1 34	1,500	
	Boiler side 1,00 mwh 2,00 - 2,00 m ³ /h 6 p	ol.				
•	65,000 kcal/h: Pool side 1,16 mwh -	101232	1	1 35	5,900	
	Boiler side 1,20 mwh 3,20 - 3,30 m ³ /h 8 pl	l.				
•	90,000 kcal/h: Pool side 1,28 mwh -	101233	1	l 64	1,000	
	Boiler side 1,29 mwh 4,50 - 4,60 m ³ /h 10	pl.				
•	110,000 kcal/h: Pool side 1,21 mwh -	101234	1	1 65	5,200	
	Boiler side 1,90 mwh 5,50 - 5,60 m^3/h 11	pl.				
•	130,000 kcal/h: Pool side 1,18 mwh -	101235	1	1 85	5,600	
	Boiler side 1,71 mwh 6,50 - 6,60 m^3/h 13	pl.				
•	150,000 kcal/h: Pool side 1,55 mwh -	101236	1	1 87	7,200	
	Boiler side 1,60 mwh 7,50 - 7,70 m^3/h 14	pl.				
•	180,000 kcal/h: Pool side 1,65 mwh -	101237	1	1 87	7,200	
	Boiler side 1,70 mwh 9,00 - 9,20 m^3/h 16	pl.				
•	225,000 kcal/h: Pool side 1,58 mwh -	101238	1	l 88	3,800	
	Boiler side 1,63 mwh 11,00 - 11,00 m^3/h :	20 pl.				
•	300,000 kcal/h: Pool side 1,63 mwh -	101239	1	l		
	Boiler side 1,97 mwh 15,00 - 15,40 m^3/h 2	25 pl.				
•	400,000 kcal/h: Pool side 1,71 mwh -	101240	1	l		
	Boiler side 1,97 mwh 20,00 - 20,50 m^3/h	33 pl.				
•	500,000 kcal/h: Pool side 1,81 mwh -	101241	1	l		
	Boiler side 1,87 mwh 25,00 - 26,00 m^3/h	41 pl.				
•	700.000 kcal/h: Pool side 1,14 mwh -	101242	1	l		
	Boiler side 1,88 mwh 27,00 - 36,00 m^3/h	62 pl.				











101260 Optional



Plate Heat Exchangers-Titanium-Low Pressure Drop

GEMAS Titanium Plate Exchanger.

Titanium plates resistent to sea water. Seals of nitrile or EPDM. Operated by 90-70°C hot water from boiler. Max pressure 10 bars, max temperature 130°C. Pressure losses from the side of the pool and the boiler are shown below separately for each capacity.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 40,000 kcal/h: Pool side 1,02 mwh -	101231T	1	34,500	
Boiler side 1,00 mwh 2,00 - 2,00 m ³ /h 6 pl.				
• 65,000 kcal/h: Pool side 1,16 mwh -	101232T	1	35,900	
Boiler side 1,20 mwh 3,20 - 3,30 m ³ /h 8 pl.				
• 90,000 kcal/h: Pool side 1,28 mwh -	101233T	1	64,000	
Boiler side 1,29 mwh 4,50 - 4,60 m ³ /h 10 pl.				
• 110,000 kcal/h: Pool side 1,21 mwh -	101234T	1	65,200	
Boiler side 1,90 mwh 5,50 - 5,60 m ³ /h 11 pl.				
• 130,000 kcal/h: Pool side 1,18 mwh -	101235T	1	85,600	
Boiler side 1,71 mwh 6,50 - 6,60 m ³ /h 13 pl.				
• 150,000 kcal/h: Pool side 1,55 mwh -	101236T	1	87,200	
Boiler side 1,60 mwh 7,50 - 7,70 m ³ /h 14 pl.				
• 180,000 kcal/h: Pool side 1,65 mwh -	101237T	1	87,200	
Boiler side 1,70 mwh 9,00 - 9,20 m ³ /h 16 pl.				
• 225,000 kcal/h: Pool side 1,58 mwh -	101238T	1	88,800	
Boiler side 1,63 mwh 11,00 - 11,00 m ³ /h 20 pl.				
• 300,000 kcal/h: Pool side 1,63 mwh -	101239T	1		
Boiler side 1,97 mwh 15,00 - 15,40 m ³ /h 25 pl.				
 400,000 kcal/h: Pool side 1,71 mwh - 	101240T	1		
Boiler side 1,97 mwh 20,00 - 20,50 m ³ /h 33 pl.				
• 500,000 kcal/h: Pool side 1,81 mwh -	101241T	1		
Boiler side 1,87 mwh 25,00 - 26,00 m ³ /h 41 pl.				
• 700.000 kcal/h: Pool side 1,14 mwh -	101242T	1		
Boiler side 1,88 mwh 27,00 - 36,00 m ³ /h 62 pl.				



Option (101260): Complete with solenoid valve, thermostat and thermostat cap for automation-€650.





Electrical Heaters

GEMAS Heatrone PRO

Electrical Heater with plastic body made of fiberglass reinforced PP. Triphase. Complete with magnetic contactors, thermal switch and flow switch. Control board has seven segment digital thermostat and led indicator for operation, as well as power control. Heating elements made of AISI 316 Stainless Steel. Timer is optional. Please add "O" at the end of existing code when ordering.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 9 kW Electrical Heater	10121	1		
• 12 kW Electrical Heater	10122	1		
• 15 kW Electrical Heater	10123	1		
• 18 kW Electrical Heater	10124	1		



GEMAS Heatrone PRO-Ti

Ditto, but heating elements made of Titanium.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
9 kW Electrical Heater	10121T	1		
• 12 kW Electrical Heater	10122T	1		
• 15 kW Electrical Heater	10123T	1		
• 18 kW Electrical Heater	10124T	1		



GEMAS Heatrone PRO-MINI

Electrical Heater with plastic body made of fiberglass reinforced PP. Complete with magnetic contactors, thermal switch and flow switch. Control board has seven segment digital thermostat and led indicator for operation, as well as power control. Heating elements made of AISI 316 Stainless Steel. Timer is optional. Please add "O" at the end of existing code when ordering.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 kW Electrical Heater (Monofaze)	10020	1		
• 2 kW Electrical Heater (Monofaze)	10021	1		
• 3 kW Electrical Heater (Trifaze)	10022	1		
6 kW Electrical Heater (Trifaze)	10024	1		





10022 10024

GEMAS Heatrone PRO-MINI - Ti

Ditto, but heating elements made of Titanium.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1 kW Electrical Heater (Monofaze)	10020T	1		
• 2 kW Electrical Heater (Monofaze)	10021T	1		
• 3 kW Electrical Heater (Trifaze)	10022T	1		
6 kW Electrical Heater (Trifaze)	10024T	1		





Pool Thermometers

Pool Thermometers, floating.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Thermometer - Floating Type (Duck)	10414	24		
• Thermometer - Floating Type (Fish)	10412	24		
• Thermometer - Floating Type (Turtle)	10415	24		



Pool Thermometer, to be connected to the ladder.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Thermometer - Floating Type	10411	1	0,090	
To be connected to the ladder	10421	1	0,068	



Pool Thermometer, floating and circular scaled, Ø190 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	10431	1	0,298	0,010



Digital Pool Thermometer with Solar Battery, Ø80 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	10432	1	0,140	0,001





Dehumidifiers


GEMAS Dehumidifier. Provides energy-saving humid control for indoor swimming pool. Allows adjusting desired humidity rate with digital hygrometer.





10231

- Quite operation,
 HD Puster Technical
- HP Buster Technology,
- R410A Eco-Friendly Gas,
- · Installation on basement or wall,
- Plastic Case,
- Optional Electrical Heater.




Description	Code	Pieces/ box	Weight Kg	Volume m ³
Model MDH75A / 75 I/day	10231	1	57,000	0,244
Model MDH90A / 90 I/day	10236	1	64,000	0,336
 Model MDH125A / 125 I/day 	10234	1	66,000	0,336
 Model MDH170A / 170 I/day 	10235	1	79,000	0,427

Note: Test Conditions - 30°C ambient temperature, 80% relative humidity.



10234

Determination Chart for Daily Evaporation in Indoor Pool Areas



Model	MDH75A	MDH90A	MDH125A	MDH170A
Capacity (kg/24sa) 30°C/70% humidity*	75	90	125	170
Heat Retention (kW) 30°C/70% humidity	* 3.2	4	5	8.2
Noise Level (dB(A))	48	50	50	52
Air Flow (m ³ /h)	600	1200	1200	1800
Input Energy	220V/1ph/50Hz	220V/1ph/50Hz	220V/1ph/50Hz	220V/1ph/50Hz
Operation Power (kW)	1.30	1.60	2.00	2.92
Current (A)	5.9	7.3	9.1	13.3
Start Current (A)	25	34	42	63
Water Inlet (inch)	3/4	3/4	3/4	3/4
Water Outlet (inch)	3/4	3/4	3/4	3/4
Drainage (mm D>ş Çap)	16	16	16	16
Operation Temperature (°C)	5~35	5~35	5~35	5~35
Compressor Protection	3 minutes delay	3 minutes delay	3 minutes delay	3 minutes delay
Defrost Mode	Automatic	Automatic	Automatic	Automatic
Cooler	R410A	R410A	R410A	R410A
Compressor	Rotary	Rotary	Rotary	Rotary
Net / Gross Weight (kg)	52/57	57/64	59/66	70/79
Net Dimensions (mm)	905x243x673	1288x243x673	1288x243x673	1672x243x673
Package Dimensions (mm)	1015x315x765	1395x315x765	1395x315x765	1775x315x765



12,50 x 25,00 x 1,80

12,50 x 25,00 x 1,50

8,00 x 16,00 x 1,50

6,00 x 12,00 x 1,50

5,00 x 10,00 x 1,50

,00 x 8,00 x 1,50

48 h

72 h

72 h

72 h

72 h **Pool Dimensions**

Volume (m³)

 $\Delta t = 5^{\circ}C$

 $\Delta t = 10^{\circ}C$

Wind Sheltered Pools

Heat

Requirement

(kcal/h)

,86

Ш

Watt)

ndoor Pools

Open Pools

24 h

72 h

24 h

48 h

24 h

48 h

24 h

72 h

24 h

48 h

24 h

48 h

25°C

 $= 10^{\circ}C$

Heat Requirement Chart For Miscellaneous Pools

16,00 x 35,00 x 1,50

25,00 x 50,00 x 2,00

1525604 1004677

|1327177|1066714| 979892

|1848104|1327177|1153535


1900152 1014576

719384 2733635

25,00 x 50,00 x 1,50


20,00 x 40,00 x 1,50

- Instructions:
- 2- Exchanger capacities on the price list are for 90/70 °C boiler water temperature. Selected exchanger capacities needs to be increased for lower boiler water temperatures 3- Values on the chart are approximate and can vary according to pool's construction and coating 1- Above values are calculated with assumption of 24 hr of boiler operation. These values needs to be increased (x 24/work hours) in cases where boiler works less
- 4- Δt = Preferred temprature increase for pools
- Above time values for preffered temperature increase. Installation capacity needs to be increased for decreasing operation time values
- Using the "solar air-bubble cover" during the heating process, provides energy saving. (>%50
- Same type of cover decreases humidity by %50 at indoor pools






Water Cascade - Acrylic - RGB LED



Made of transparent acrylic. Complete with stainless steel bottom mounting plate, gasket, screws and nuts. Different light animations are created with RGB LED. Transformer remote control unit is not included in the price. Color change can be achieved with on-off.




PS: It must be used with a dedicated 1 HP Streamer pump.
















TECHNICAL CHARACTERISTICS

MODEL	Ø	A (mm)	B (mm)	C (mm)	D (mm)	E (mm)	Power (W)	Voltage (VDC)
WF-300 LED	1.5"	603	423.5	320	236	416	12.0	12
WF-301 LED	2.0"	750	540.6	395	280	500	13.0	12

Water Cascade




Mini Cobra Water Cascade.

Made of AISI 304 grade stainless steel. Connection 1,5" female threaded. Complete with bolts and plugs.

7	Description	Code	Pieces/ box	Weight Kg	Volume m ³
		11190	1		

PS: It must be used with a dedicated 1 HP Streamer pump.




Water Cascade

Midi Cobra Water Cascade.

Made of AISI 304 grade stainless steel. Connection 2" female threaded. Complete with bolts and plugs.

Description	Code	Pieces/ W box	/eight Volume Kg m³
• Midi 1 - h=575 x 500 mm	11191	1	
• Midi 2 - h=900 x 600 mm	11193	1	

PS: It must be used with a dedicated 2 HP Streamer pump.




Niagara Water Cascade.

Made of AISI 304 grade stainless steel. Connection 2" female threaded. Complete with bolts and plugs.

Description	Code	Pieces/ Weight box Kg	Volume m ³
	11192	1	

PS: It must be used with a dedicated 2 HP Streamer pump.






Water Cascade


Arcade - Lux Water Cascade.

Made of AISI 304 grade stainless steel. 2" female thereaded connection. Complete with bolt and plugs.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 500 mm cascade	11150	1		
• 600 mm cascade	11151	1		

PS: It must be used with a dedicated 3 HP Streamer pump.









Arcade - Water Cascade.

Made of AISI 304 grade stainless steel. 2" female thereaded connection. Complete with bolt and plugs.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 400 mm cascade	11160	1	30,300	
• 600 mm cascade	11161	1		

PS: It must be used with a dedicated 3 HP Streamer pump.








Delta - Water Cascade.

Made of AISI 304 grade stainless steel. $2^{\prime\prime}$ female thereaded connection. Complete with bolt and plugs.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
350 mm cascade	11170	1	12,400	

PS: It must be used with a dedicated 3 HP Streamer pump.






Water Cascade


Floor Waterfall.


Made of AISI 304 grade stainless steel. Connection 2" female threaded. Complete with bolts and plugs.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	11200	1		

PS: It must be used with a dedicated 3 HP Streamer pump.










Water Jet.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 body made of AISI 304 grade	11140	1		
stainless steel. Exchangeable jet mout	h.			
• Jet No 1	11141	1		
• Jet No 2	11142	1		
• Jet No 3	11143	1		
• Jet No 4	11144	1		

PS: It must be used with a dedicated 3 HP Streamer pump.











Top view





Water Cascade - Wall Type


Wall Waterfall.


Made of AISI 304 grade stainless steel. Connection 2 x 1,5" female threaded. Complete with bolts and plugs.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• L= 1 m.	11110	1		
• L= 1,5 m.	11111			

PS: It must be used with a dedicated 1 - 1 1/2 HP Streamer pump.






Tortum Water Cascade.


Made of AISI 304 grade stainless steel. Connection 1,5" female threaded. Complete with bolts and plugs.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• L= 0,3 m.	11112	1		
• L= 0,5 m.	11113	1		

PS: It must be used with a dedicated 3/4 - 1 HP Streamer pump.






Wall Shower.


Made of AISI 304 grade stainless steel. Connection 1,5" female threaded. Complete with bolts and plugs. Recommended to be used with 05080 pneumatic button.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
	11121	1		

PS: It must be used with a dedicated 0,75 HP Streamer pump.









Water Cascade - Mushroom Type


Mushroom Cascade.


FRP mushroom with AISI 304 grade stainless steel pivot, flanged at both ends.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Mushroom Cascade L=Ø2000 mm:	11133	1		
Requires 150 m³/h				
• Mushroom Cascade L=Ø1600 mm:	11132	1	53,000	1,190
Requires 80 m³/h				
• Mushroom Cascade L=Ø1000 mm:	11131	1		
Requires 40 m³/h				









Water Cascade - Wall Type - Stainless Steel


"Pool Waterfall".


Made of AISI 304 grade stainless steel. Connection 2 x 1,5" female threaded.


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Model HS01 - L= 0,30 m width	11180	1		
• Model HS02 - L= 0,50 m width	11181	1		
• Model HS03 - L= 1,00 m width	11182	1		
• Model HS04 - L= 1,50 m width	11183	1		



PS: Suggested pumps are Streamer Mini 0,33 HP, 0,5 HP, 0,75 HP ve 1 HP respectively.









Water Cascade - Wall Type - LED



"LED RGB COLORED POOL WATERFALL".

Two models for different water effects. It has a remote control. Revitalizes your pool. It is one of the most beautiful aesthetic properties for pools and SPAs. While creating a water movement in your pool, relaxing water adds elegance and style to your pool and massages your back. It provides vivid colors with its RGB LED unit that can be activated when desired. With a choice between 2 different water cascading models

- Rainfall or Waterfall Arc, offering visual interest, relaxing sound and a unique waterfall view.

Features:

- Two different widths: 25 mm and 150 mm. Suitable for different wall sizes.
- Three different lengths: 600 mm, 900 mm and 1200 mm
- LED strip lighting is powered by external 12V DC, which is safe and reliable.
- LEDs can be operated with a panel or remote control and there are 10 different lighting patterns.

LED Pool Waterfall Control Box

The LED strip is placed in the unit (instead of using fiber optics) the light falls as close as possible to the water. This design provides water illumination falling into a wonderful pool. A selection of 10 pre-programmed LED lighting patterns provide the best lighting options.

There are 2 different models for different water effects:

- PB Series: Standard orbital waterfall effect
- RS Series: Rain effect with transparent orbit

LED Strip Power 12V DC

Remote Control

10 Lighting Patterns

Width **25/150 mm**

Length **600/900/1200 mm**




Water Cascade - Wall Type - LED


PB Series Pool Waterfall.


Provides excellent water light effect by creating standard continuous waterfall flow.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• PB600-150L	11PB600	1		
• PB900-150L	11PB900	1		
• PB1200-150L	11PB1200	1		










TECHNICAL CHARACTERISTICS


MODEL	A (mm)	B (mm)	C (mm)	D (mm)	Voltage (VDC)	Power (W)
PB600-150L	606	263	76	150	12	8.0
PB900-150L	906	263	76	150	12	12.0
PB1200-150L	1206	263	76	150	12	17.0

RS Series Pool Waterfall.

Creates a rain-like waterfall flow, providing a perfect water and light effect in your pool.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• RS600-150L	11RS600	1		
• RS900-150L	11RS900	1		









TECHNICAL CHARACTERISTICS

MODEL	A (mm)	B (mm)	C (mm)	D (mm)	Voltage (VDC)	Power (W)
RS600-150L	606	284	78	171	12	8.0
RS900-150L	906	284	78	171	12	12.0



Inpool Hydro Massage Systems




Air Bed.

Made of AISI 304 grade stainless steel. Complete with adjustable legs and PVC piping. \emptyset 63 mm air connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Double	11330	1		
• Single	11331	1		

PS: This product must be used with 2,2 - 1,1 kw blower.




Rectangular Floor Air Jet.

Made of AISI 304 grade stainless steel. Connection 2" female threaded. Complete with bolt and plugs.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
660 x 260 mm	11340	1		

PS: This product must be used with 2,2 kw blower.






Circular Floor Air Jet.


Made of AISI 304 grade stainless steel. Connection 2" female threaded. Complete with bolt and plugs.



Description	Code	Pieces/ Weight box Kg	Volume m ³
Ø310 mm dia	11350	1	

PS: This product must be used with 1,1 kw blower.







Counter Current and Massage Systems

STP-SP Counter Current System. Complete with jet pump, pneumatic switch, LED light, valves and fittings. Two seperate air buttons for pump and LED. Completely made of ABS plastic. The suction line is 75 mm and the discharge line is 63 mm. Thanks to the suction check valve, the air suction line can be installed below the water level. Hand massage is possible with optional massage hose. Complete with a stainless steel handle. For Concrete and Liner Pools.




For Concrete and Liner Pools:

Description	Code	Pieces/ box	Weight Kg
• STP-SPM Monophase-with 3,0 HP BTP 0,396	112270M	1	
• STP-SPT Triphase-with 3,0 HP BTP	112271T	1	
• STP-SPT Triphase-with 4,5 HP BTP	112272T	1	
• STP-SPT Triphase-with 5,5 HP BTP	112273T	1	
• STP-SP Counter Current System, Niche, front frame set	1122213	1	
Massage Hose Set	1122211	1	




PERFORMANCE CURVES





PUMP TYPE	DIMENSIONS						Weight			
1000	Α	В	С	D	Е	F	G	Н	H1	(Kg)
STP-2200	370	156	440	Ø75	395	77	1110	340	635	22
STP-3000	410	156	470	Ø75	395	77	1110	340	635	24
STP-4000	440	156	500	075	395	77	1110	340	635	26










MOUNTING TYPE:





Counter Current and Massage Systems - S. Steel



STP-SS Counter Current System.

Complete with jet pump, pneumatic switch, LED light, valves and fittings. Two seperate air buttons for pump and LED.


Completely made of stainless steel 304 grade. The suction line is 75 mm and the discharge line is 63 mm. Thanks to the suction check valve, the air suction line can be installed below the water level. Hand massage is possible with optional massage hose. For Concrete and Liner Pools.

For Concrete and Liner Pools:




Description	Code	Pieces/ box	Weight Kg
STP-SSM Monophase-with 3,0 HP BTP	112270MSS	1	
• STP-SST Triphase-with 3,0 HP BTP	112271TSS	1	
STP-SST Triphase-with 4,5 HP BTP	112272TSS	1	
• STP-SST Triphase-with 5,5 HP BTP	112273TSS	1	
• STP-SS Counter Current System, Niche, front frame set		1	
Massage Hose Set	1122211	1	






	PUMP TYPE	DIMENSIONS							Weight		
1		Α	В	С	D	Е	F	G	Н	H1	(Kg)
	STP-2200	370	156	440	Ø75	395	77	1110	340	635	22
	STP-3000	410	156	470	Ø75	395	77	1110	340	635	24
	STP-4000	440	156	500	Ø75	395	77	1110	340	635	26








MOUNTING TYPE:



Prefabricated Swimming Pool

Pool Wall





Counter Current and Massage Systems

GEMAS "ELIPTICAL MODEL" Counter Current System.

Complete with jet pump, pneumatic switch, valves and connection parts. Easy to direct nozzle inside pool. Completely made of ABS plastic. Suction line Ø75 mm, return line Ø63 mm. Air suction line can be established below water level by the help of suction check valve. Possible hand massage with optional massage hose. Optional stainless steel handle. Can be used both for liner and concrete pools.

For Concrete Pools:

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3,0 HP Monophase-with Pumpex pump	112221	1		
• 3,5 HP Monophase-with Fooderjet pump	112222	1		
• 3,0 HP Triphase-with Pumpex pump	112223	1		
• 3,5 HP Triphase-with Fooderjet pump	112224	1		
• 4,5 HP Triphase-with Fooderjet pump	112225	1		
• 5,5 HP Triphase-with Fooderjet pump	112226	1		



For Liner Pools:

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3,0 HP Monophase-with Pumpex pump	112251	1		
• 3,5 HP Monophase-with Fooderjet pump	112252	1		
• 3,0 HP Triphase-with Pumpex pump	112253	1		
• 3,5 HP Triphase-with Fooderjet pump	112254	1		
• 4,5 HP Triphase-with Fooderjet pump	112255	1		
• 5,5 HP Triphase-with Fooderjet pump	112256	1		



GEMAS "ELIPTICAL MODEL" Counter Current System.

Niche made of ABS and front frame set.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For Concrete Pools	11223	1		
• For Liner Pools	11224	1		



GEMAS "ELIPTICAL MODEL" Counter Current System, Massage Hose Set.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1122211	1		



AISI 304 Grade Stainless Steel Handles for GEMAS Counter Current System. Complete with screws and pegs, with flange. Pipe is Ø42 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Price for 2	1122212	1		





Counter Current and Massage Systems



GEMAS "SQUARE MODEL" Counter Current System.

Complete with jet pump, pneumatic switch, valves and connection parts. Easy to direct nozzle inside pool. Completely made of ABS plastic. Suction line Ø75 mm, return line Ø63 mm. Air suction line can be established below water level by the help of suction check valve. Possible hand massage with optional massage hose. Optional stainless steel handle. Can be used both for liner and concrete pools.

For Concrete Pools:

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3,0 HP Monophase-with Pumpex pump	112221K	1		
• 3,5 HP Monophase-with Fooderjet pump	112222K	1		
• 3,0 HP Triphase-with Pumpex pump	112223K	1		
• 3,5 HP Triphase-with Fooderjet pump	112224K	1		
• 4,5 HP Triphase-with Fooderjet pump	112225K	1		
• 5,5 HP Triphase-with Fooderjet pump	112226K	1		



For Liner Pools:

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3,0 HP Monophase-with Pumpex pump	112251K	1		
• 3,5 HP Monophase-with Fooderjet pump	112252K	1		
• 3,0 HP Triphase-with Pumpex pump	112253K	1		
• 3,5 HP Triphase-with Fooderjet pump	112254K	1		
• 4,5 HP Triphase-with Fooderjet pump	112255K	1		
• 5,5 HP Triphase-with Fooderjet pump	112256K	1		



GEMAS "SQUARE MODEL" Counter Current System.

Niche made of ABS and front frame set.

Description	Code	Pieces/ Weight box Kg	Volume m ³
For Concrete Pools	11223K	1	
For Liner Pools	11224K	1	



GEMAS "SQUARE MODEL" Counter Current System, Massage Hose Set.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1122211	1		



Inpool Hydro Massage Systems

In-Pool Hydro Massage Bed.

Made of Acrylic + Polyester. Water and air connections are ready to install.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Type 1	11310	1	15,000	
• Type 2	11311	1		



In-Pool Hydro Massage Chair.

Made of Acrylic + Polyester. Water and air connections are ready to install.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	11320	1		







Decorative Wall Nozzles



Small Lionhead, Antique Copper



Large Lionhead, Antique Copper



Plain Bowl Waterfall



Plain Bowl Waterfall, Antique Copper



Slotted Bowl Waterfall, Antique Copper



Snail Antique Copper



Antique Badge

GEMAS Wall Nozzles. Made of polyester and the surface finish is made with various aging paints. Standart trims are antique copper, antique brass, antique silver and oxide. Special implementations can be made according to special demands.

Description	Code	ces/ ox	Weight Kg	Volume m ³
Small Lionhead, Antique Copper	1122411	1		
Large Lionhead, Antique Copper	1122421	1		
Plain Bowl Waterfall, Antique Copper	1122431	1		
Slotted Bowl Waterfall, Antique Copper	1122241	1		
Snail, Antique Copper	1122251	1		
Antique Badge, Antique Copper	1122261	1		









Fiberoptic Star Effect

GEMAS Fiberoptic Star Effect.

Before coating the pool, fiberoptic fibers are inserted on pool floor, extended into engine room and all fibers connected to RGB light source. In this way, RGB or single colored star effect is created on the pool floor.

Des	cription	Code	Pieces/ box	Weight Kg	Volume m ³
		1122711			











Poyrazlux - Winter Cover



Pool Cover. Made of PVC. Peripheral reinforcement of 5 cm. Laterals at each 1 m of the periphery are used to stretch the cover over pool surface by means of stainless steel springs attached to special bronze retractable anchors. Drain holes are available at the center to discharge the rain water. Complete with springs and retractable anchors.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Rectangular shape, price per square meter	12110			
• Irregular shape, price per square meter	12111			
• Free form cover, price per square meter	12112			
Special cut for pool ladder or other	12117			
special forms, price per cut				

PS. Pool dimensions should be increased by 1,20 m for overflow pools; whereas by 0,6 m for skimmer pools.


Solar Cover - Heat Saving

Solar Pool Cover. Provides a limited amount of solar heating and saves energy by minimizing the surface heat loss. Decreases the humidity 50% at indoor pools. Recommended to be used with cover reel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Solar Cover, in roll per m ²	1211101			
Width: 2 m. (Welded price is double).				

PS. Please ask for prices of Solar Covers in special shape.





Cover Accessories



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Retractable anchor	121101	1	0,062	
Dynamometric Spring.	121102	1	0,144	
AISI 304 grade stainless steel				
Manuel Vacuum Pump. Used for	12114	1		
discharge of rain water on the cover.				



Motorized Pool Cover

COVERTEC Pool Cover.

Blue PVC 650 gr/m². Reinforced with aluminium bars placed with 1,2 m - 1,4 m intervals. With the help of portable rechargeable-reductor 24 V motor, the pool cover is opened or collected easily and quickly. Safe for children and pets. For windy environments, fixation is provided by side reinforcements. For irregular-shaped swimming pools, the cover needs to be rectangular form. There should be 25 cm margin for short edges and 50 cm margin for long edge.



Description	Code	Pieces/ Weight box Kg	Volume m ³
• 3 x 6 m Pool	12210	1	
• 4 x 8 m Pool	12211	1	
• 5 x 10 m Pool	12212	1	
• 6 x 12 m Pool	12213	1	

All Pool Covers Have Below Specifications

- Strong resistance to UV lights from the Sun. Preserves its aero-elastic structure under bad weather conditions.
- Can be easily clean due to dirt-proof LAQUER coating.
- Anti Fungal
- Anti Bacterial
- Not affected negatively by pool chemicals













Motorized Pool Cover



Automatic PVC Slatted Pool Cover. Made of PVC profiles, 24 V Above-groun motor. It weights a person walking above and does not sink. With the help of safety straps, the cover can be fixed manually to pool deck. It's suitable for new and existing pools. For remote control option please ask for price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3 x 6 m Pool - White	12220			
• 4 x 8 m Pool - White	12221			
• 5 x 10 m Pool - White	12222			
• 6 x 12 m Pool - White	12223			
• 3 x 6 m Pool - Solar Blue	12224			
• 4 x 8 m Pool - Solar Blue	12225			
• 5 x 10 m Pool - Solar Blue	12226			
• 6 x 12 m Pool - Solar Blue	12227			

PS. This is a no-stock item. Produced according to order.











Cover Reels

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Cover Reel. Made of	12113	1	6,100	0,047
ABS plastic with cover tie	set. w/o Bar			
Ditto, made of	12115	1		
stainless steel with cover tie set (excluding bar)				
• 3 x 2 m Aluminium	121131	1	6,394	0,039
Telescopic Cover Bar.				

PS. Please ask quotation for "telescopic cover bar"





Pool Ice Barrier

Pool Ice Barrier. Made of Plastic. 49 x 24 cm size floating barrier is arrayed all around the pool perimeter. Protects the pool coating by absorbing the expansion of freezing at very low atmospheric temperature.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ice Barrier	1297105	1		









Ball Valves



Ball Valves in UPVC.

Slip connection and adjustable ball pressure. HDPE seats and EPDM 0-rings. PN 16.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.20 mm - Slip connection	131111	88	23,050	0,094
• d.25 mm - Slip connection (NEW)	131112	78	27,160	0,094
• d.32 mm - Slip connection (NEW)	131113	20	7,900	0,017
• d.40 mm - Slip connection (NEW)	131114	12	7,800	0,017
• 0,5 - Threaded	131111T	88	23,050	0,094
• 0,75 - Threaded	131112T	78	27,160	0,094
• 1" - Threaded	131113T	20	7,900	0,017
• 1,25" - Threaded	131114T	12	7,800	0,017



Ball Valves in UPVC.

Slip connection; adjustable ball pressure as well as patented union-screwing by means of handle. HDPE seats and EPDM O-rings. PN 16.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.50 mm - Slip connection	131115L	6	4,620	0,013
• d.63 mm - Slip connection	131116L	6	7,542	0,021
• d.75 mm - Slip connection	131117L	2	3,680	0,016
• d.90 mm - Slip connection	131118L	2	3,660	0,016
• d.110 mm - Slip connection	131119L	1	6,240	0,018
• 1,5" - Threaded	131115LT	6	4,620	0,013
• 2" - Threaded	131116LT	6	7,542	0,021
• 2,5" - Threadedi	131117LT	2	3,680	0,016
• 3" - Threaded	131118LT	2	3,660	0,016
• 4" - Threaded	131119LT	1	6,240	0,018



Single Union UPVC Ball Valve.

Made of UPVC. One side is female slip connection from the inside and the other side is with a union. O-rings EPDM, packing PP. PN 16.

Patented design: Valve handle can be used to tighten the union. Please ask price for threaded versions.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.50 mm	131415	6	3,900	0,013
• d.63 mm	131416	6	6,200	0,021
• d.75 mm	131417	2	3,000	0,016
• d.90 mm	131418	2	3,030	0,016



Industrial Ball Valves

UPVC Industrial Ball Valve.

Slip connection and adjustable ball pressure. For chemical resistance, O-rings from viton, seal from teflon.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.32 mm	131123	20	7,900	0,017
• d.40 mm	131124	12	7,800	0,017
• d.50 mm	131125L	6	4,620	0,013
• d.63 mm	131126L	6	7,542	0,021
• d.75 mm	131127L	2	3,000	0,016
• d.90 mm	131128L	2	3,060	0,016
• d.110 mm	131129L	1	5,975	0,018



Industrial Ball Valves

UPVC Industrial Ball Valve.

Adjustable ball pressure and threaded connection. For chemical resistance, O-rings from viton, seal from teflon. PN 16.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1"	131123T	20	7,900	0,017
• 1,25"	131124T	12	7,800	0,017
• 1,5"	131125LT	6	4,620	0,013
• 2"	131126LT	6	7,542	0,021
• 2,5"	131127LT	2	3,680	0,016
• 3"	131128LT	2	3,660	0,016
• 4"	131129LT	1	6,240	0,018



UPVC Automatic Ball w/Actuator Valves

UPVC Automatic Ball w/Actuator Valves

Ø50 - Ø63 mm with optional wifi control

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø50 mm Motorized Valve	131115LGA	1	1,602	0,008
Ø63 mm Motorized Valve	131116LGA	1	1,876	0,008



131116LGA

Motorized UPVC Ball Valves

Motorized UPVC Ball Valves.

ON/OFF Electric Actuator operates with 24V AC/DC. All valves could be controlled manually by switch.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø50 mm Motorized Valve	131115LEA	1	1,602	0,008
Ø63 mm Motorized Valve	131116LEA	1	1,876	0,008





3-Way Valves



Three Way Disc Valve. Made of ABS. Slip Connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Three Way Disc Valve - Ø50 mm	13171	1	1,602	0,008
• Three Way Disc Valve - Ø63 mm (NEW)	13172	1	1,876	0,008

Mini Valves



PP Mini Irrigation Valve. Handle from ABS PN16.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1" x 0,75 Male-Female Valve	131210	100	19,600	0,055
• 0,75 Male-Female Valve	131211	100	18,700	0,055
• 1" Male-Female Valve	131212	100	20,800	0,055
• 1" x 0,75 Female-Female Valve	131210D	100	19,200	0,055
• 0,75 Female-Female Valve	131211D	100	18,400	0,055
• 1" Female-Female Valve	131212D	100	21,050	0,055

Butterfly Valves



GEMAS UPVC BUTTERFLY VALVES.

Handle made of ABS, Lining From EPDM. Stem from Zinc Plated Carbon Steel. AISI 316 Stem is optional. Valve can be adjusted by 3,75 degree sensitivity. Hole for Security Padlock. Complete with flanges bolts and nuts. NEW Design Butterfly Valve is limited to sizes d110, d125, d140 and d160. Please ask availability for other sizes.

	Description	Code	Pieces/ box	Weight Kg	Volume m ³
	• Ø63 mm	131600	1	2,470	0,094
	• Ø75 mm (NEW)	131601	1	3,250	0,094
	• Ø90 mm (NEW)	131602	1	5,270	0,124
	• Ø110 mm	131603	1	6,530	0,124
	• Ø125 mm	131604	1	8,770	0,124
	• Ø140 mm	131605	1	9,100	0,124
/	• Ø160 mm	131606	1	12,100	0,124
,	• Ø200 mm (NEW)	131607	1	17,300	0,124
	• Ø225 mm (NEW)	131608	1	17,800	0,124
	• Ø250 mm	131609	1	36,200	0,124
	• Ø280 mm	131610	1	40,100	0,124
	• Ø315 mm	131611	1	46,100	0,124





Butterfly Valves

MOTORIZED BUTTERFLY VALVE, ON-OFF:

Valve actuator, works with 24 V AC/DC. Complete with flanges, flange adaptors, bolts & nuts. All valves can be controlled manually with switch or flywheel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø90 mm	131602M11	1		
• Ø110 mm	131603M11	1		
• Ø125 mm	131604M11	1		
• Ø140 mm	131605M11	1		
• Ø160 mm	131606M11	1		
• Ø200 mm	131607M11	1		
• Ø225 mm	131608M11	1		
• Ø250 mm	131609M11	1		
• Ø280 mm	131611M11	1		
• Ø315 mm	131610M11	1		



PLEASE ASK PRICE FOR PROPOTIONAL MODELS.

Check Valves - Wafer Check Valves

UPVC Swing Check Valves. Two piece body. Complete with bolts.

Descript	ion	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	Slip connection	131499Y	30	24,200	0,124
• Ø63 mm	Slip connection	131500Y	24	20,000	0,124
• Ø75 mm	Slip connection	131501Y	12	17,000	0,124
• Ø90 mm	Slip connection	131502Y	10	17,850	0,124
• Ø110 m	m Slip connection	131503Y	6	19,000	0,124



UPVC Wafer Check Valves. Complete with flange adaptors, flanges, bolts and nuts.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø90 mm	131502	1	3,620	0,124
• Ø110 mm	131503	1	4,250	0,124
• Ø125 mm	131504	1	5,080	0,124
• Ø140 mm	131505	1	5,360	0,124
• Ø160 mm	131506	1	7,400	0,124
• Ø200 mm	131507	1	10,050	0,124
• Ø225 mm	131508	1	10,150	0,124
• Ø250 mm	131509	1	20,600	0,124
• Ø280 mm	131510	1	21,500	0,124
• Ø315 mm	131511	1	25,650	0,124





UPVC Swing Check Valve W/Transparent Cover and Spring.

Easy cleaning access via the threaded cover. Thanks to its transparent cover and large chamber, any type of congestion problem can be easily observed. DN50.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø63 mm Slip connection	131500G	1		





Check Valves - Spring Weighed Check Valves



Spring Weighed Check Valves. In UPVC or ABS. EPDM 0-rings. AISI 316 grade spring. PN16.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	131315	6	4,330	0,013
• Ø63 mm	131316	6	5,810	0,022
• Ø75 mm	131317	2	3,920	0,016
• Ø90 mm	131318	2	3,780	0,016
• Ø50 mm - Transparent	131315PC	6	4,330	0,013
• Ø63 mm - Transparent	131316PC	6	5,800	0,022
• Ø75 mm - Transparent	131317PC	2	3,920	0,016
• Ø90 mm - Transparent	131318PC	2	3,780	0,016

Valve Boxes



Valve Box.

Designed to supply access to valves which are underground Manufactured from PP.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø250 mm, circular (10")	135601	1		
• 250 x 375 mm, prismatic (12")	135602	1		





Sight Glass



"Union Sight Glass" In UPVC.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.50 mm	134204			
• d.63 mm	134205			
• d.75 mm	134206			
• d.90 mm	134207			
• d.110 mm	134208			



Sight Glass

"Flanged Sight Glass"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.90 mm	134220			
• d.110 mm	134221			
• d.125 mm	134222			
• d.140 mm	134223			
• d.160 mm	134224			
• d.200 mm	134225			
• d.225 mm	134226			




UPVC By-Pass Kit

UPVC By-Pass Kit

Easy mount valve and fittings kit for installation of BY-Pass lines to auxilary equipment such as heat pumps, salt chlorinators, UV strelizers etc. Complete with 125 ml UPVC glue and 100 ml cleaner.

Codo	Pieces	/ Weight	Volume
Code	box	Kg	m^3
13543BP			
nd			
13547BP			
nd			
	nd	Code box 13543BP 13547BP	13543BP 13547BP







UPVC Fittings - Elbow

"Elbow, 90°" PN16 up to size 160 mm. Bigger size PN10.





Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	133101	250	4,000	0,021
• Ø25 mm	133102	500	5,500	0,021
• Ø32 mm	133103	250	17,500	0,094
• Ø40 mm	133104	144	3,400	0,021
• Ø50 mm (NEW)	133105	180	25,380	0,034
• Ø63 mm (NEW)	133106	100	20,700	0,034
• Ø75 mm	133107	80	24,400	0,124
• Ø90 mm	133108	50	25,800	0,124
• Ø110 mm	133109	30	23,800	0,124
• Ø125 mm	133110	16	15,600	0,124
• Ø140 mm	133111	12	15,400	0,124
• Ø160 mm	133112	8	18,300	0,124
• Ø200 mm	133113	4	14,660	0,124
• Ø225 mm	133114	3	13,300	0,124
• Ø250 mm (NEW)	133115	1	7,710	0,094
• Ø280 mm	133116	1	9,800	0,124
• Ø315 mm	133117	1	14,440	0,124

"Elbow, 45°" PN16 up to size 160 mm. Bigger size PN10.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	133201	600	3.400	0,021
• Ø25 mm	133202	500	3,400	0,021
• Ø32 mm	133203	320	4,200	0,021
• Ø40 mm	133204	150	4,200	0,021
• Ø50 mm	133205	225	24,070	0,940
• Ø63 mm	133206	120	19,800	0,940
• Ø75 mm	133207	100	24,180	0,124
• Ø90 mm	133208	50	18,080	0,124
• Ø110 mm	133209	30	17,120	0,124
• Ø125 mm	133210	18	14,340	0,124
• Ø140 mm	133211	15	16,380	0,124
• Ø160 mm	133212	9	16,400	0,124
• Ø200 mm	133213	4	14,300	0,124
• Ø225 mm	133214	4	15,260	0,124
• Ø250 mm	133215	1	6,100	0,124
• Ø280 mm	133216	1	8,980	0,124
• Ø315 mm	133217	1	10,880	0,124



UPVC Fittings - Tee

"Tee"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	133301	150	3,240	0,021
• Ø25 mm	133302	150	4,420	0,021
• Ø32 mm	133303	100	5,380	0,021
• Ø40 mm	133304	50	4,180	0,021
• Ø50 mm (NEW)	133305	115	20,580	0,940
• Ø63 mm (NEW)	133306	75	20,010	0,940
• Ø75 mm	133307	50	20,800	0,124
• Ø90 mm	133308	30	21,780	0,124
• Ø110 mm	133309	20	20,820	0,124
• Ø125 mm	133310	11	14,700	0,124
• Ø140 mm	133311	8	15,140	0,124
• Ø160 mm	133312	5	15,060	0,124
• Ø200 mm	133313	3	14,160	0,124
• Ø225 mm	133314	2	13,800	0,124
• Ø250 mm	133315	1	10,500	0,094
• Ø280 mm	133316	1	12,200	0,124
• Ø315 mm	133317	1	18,760	0,124



UPVC Fittings - Reducing Tee

"Reducing Tee"

Description	Code	Pieces/ Weight box Kg	Volume m ³
• Ø63 - Ø50 mm	13330061	75	0,940
• Ø75 - Ø50 mm	13330071	50	0,124
• Ø75 - Ø63 mm	13330072	50	0,124
• Ø90 - Ø63 mm	13330081	50	0,124
• Ø90 - Ø75 mm	13330082	30	0,124
• Ø110 - Ø63 mm	13330091	20	0,124
• Ø110 - Ø75 mm	13330092	20	0,124
• Ø110 - Ø90 mm	13330093	20	0,124
• Ø125 - Ø75 mm	13330101	11	0,124
• Ø125 - Ø90 mm	13330102	11	0,124
• Ø125 - Ø110 mm	13330103	11	0,124
• Ø140 - Ø90 mm	13330111	8	0,124
• Ø140 - Ø110 mm	13330112	8	0,124
• Ø140 - Ø125 mm	13330113	8	0,124
• Ø160 - Ø63 mm	13330121	5	0,124
• Ø160 - Ø75 mm	13330122	5	0,124
• Ø160 - Ø90 mm	13330123	5	0,124
• Ø160 - Ø110 mm	13330124	5	0,124
• Ø160 - Ø125 mm	13330125	5	0,124
• Ø160 - Ø140 mm	13330126	5	0,124
• Ø200 - Ø75 mm	13330131	3	0,124





UPVC Fittings - Reducing Tee

"Reducing Tee"



Description	Code	Pieces/ \ box	Weight Volume Kg m ³
• Ø200 - Ø90 mm	13330132	3	0,124
• Ø200 - Ø110 mm	13330133	3	0,124
• Ø200 - Ø125 mm	13330134	3	0,124
• Ø200 - Ø140 mm	13330135	3	0,124
• Ø200 - Ø160 mm	13330136	3	0,124
• Ø225 - Ø110 mm	13330141	2	0,124
• Ø225 - Ø125 mm	13330142	2	0,124
• Ø225 - Ø140 mm	13330143	2	0,124
• Ø225 - Ø160 mm	13330144	2	0,124
• Ø225 - Ø200 mm	13330145	2	0,124

UPVC Cross "Cross"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.32 mm	133321			
• d.40 mm	133322			
• d.50 mm	133323			
• d.63 mm	133324			
• d.75 mm	133325			
• d.90 mm	133326			
• d.110 mm (NEW)	133327			
• d.125 mm	133328			
• d.140 mm	133329			
• d.160 mm	133330			
• d.200 mm	133331			
• d.225 mm	133332			
• d.250 mm	133333			
• d.280 mm	133334			
• d.315 mm	133335			

UPVC Fittings - Nipple

"Nipple"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 0,5	1111080			
• 0,75	1111081			
• 1"	1111082			
• 1,25"	1111083			
• 1,5"	1111084			
• 2"	1111085			
• 2,5"	1111086			
• 3"	1111087			
• 4"	1111088			
• 4,5"	1111089			
• 5"	1111090			
• 6"	1111091			
• 7"	1111092			



UPVC Fittings - Adaptors

"Female Threaded Adaptor"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	133405	120	13,600	0,049
• Ø63 mm	133406	87	15,010	0,049
• Ø75 mm	133407	120	25,760	0,094
• Ø90 mm	133408	60	19,600	0,094
• Ø110 mm	133409	44	13,460	0,094



"Male Threaded Adaptor"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	133505	156	17,720	0,049
• Ø63 mm	133506	116	18,040	0,049
• Ø75 mm	133507	120	26,700	0,094
• Ø90 mm	133508	75	25,860	0,094
• Ø110 mm	133509	36	17,000	0,094



UPVC Sockets

"Socket"


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	133821	500	7,000	0,021
• Ø25 mm	133822	500	10,500	0,021
• Ø32 mm	133823	300	10,650	0,021
• Ø40 mm	133824	250	15,500	0,021
• Ø50 mm	133805	150	13,100	0,049
• Ø63 mm	133806	87	13,400	0,049
• Ø75 mm	133807	96	22,300	0,094
• Ø90 mm	133808	60	22,540	0,094
• Ø110 mm	133809	36	21,480	0,094
• Ø125 mm	133804	24	14,340	0,094
• Ø140 mm	133803	15	14,380	0,094
• Ø160 mm	133802	12	16,660	0,094
• Ø200 mm	133810	5	11,320	0,094
• Ø225 mm	133811	3	10,220	0,094
• Ø250 mm	133812	2	8,910	0,124
• Ø280 mm	133813	1	6,120	0,124
• Ø315 mm	133814	1	7,100	0,124





UPVC Fittings - Reducing Sockets

"Reducing Socket"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø25 - Ø20 mm	133602	250		
• Ø32 - Ø25 mm	133604	1000		
• Ø40 - Ø32 mm	133603	600		
• Ø50 - Ø32 mm	133601	200		
• Ø50 - Ø40 mm	1336095	200	16,800	0,094
• Ø63 - Ø50 mm	133605	252	16,100	0,049
• Ø75 - Ø63 mm	133606	150	12,400	0,049
• Ø90 - Ø75 mm	133607	88	12,496	0,049
• Ø110 - Ø90 mm	133608	48	12,912	0,049
• Ø75 - Ø50 mm	1336061	150	15,100	0,049
• Ø90 - Ø63 mm	1336071	88	15,900	0,049
• Ø110 - Ø75 mm	1336081	48	13,800	0,049
• Ø110 - Ø63 mm	1336082	48	13,700	0,049
• Ø125 - Ø90 mm	1336091	36	15,190	0,049
• Ø125 - Ø110 mm	133609	36	10,440	0,049
• Ø140 - Ø90 mm	133612	23	18,800	0,049
• Ø140 - Ø110 mm	1336121	23	6,400	0,049
• Ø140 - Ø125 mm	1336122	23	8,700	0,049
• Ø160 - Ø90 mm	133610	15	11,320	0,049
• Ø160 - Ø110 mm	133611	15	10,180	0,049
• Ø160 - Ø140 mm	13366111	15	8,940	0,049
• Ø200 - Ø160 mm	133672	14	17,500	0,094
• Ø200 - Ø140 mm	133671	14		0,094
• Ø225 - Ø200 mm	133681	12	16,300	0,094
• Ø225 - Ø160 mm	133682	12	15,400	0,094
• Ø250 - Ø225 mm	133683	8	13,900	0,094
• Ø280 - Ø250 mm	133686			
• Ø315 - Ø250 mm	133693			

"Conical Socket"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø75 - Ø50 mm	1339071			
• Ø75 - Ø63 mm	1339072			
• Ø90 - Ø63 mm	1339082			
• Ø110 - Ø63 mm	1339091			
• Ø160 - Ø110 mm	13390121			
• Ø200 - Ø110 mm	13390131			

UPVC Fittings - Caps

"Caps"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	133701	200		
• Ø25 mm	133702	1000		
• Ø32 mm	133703	600		
• Ø40 mm	133704	360		
• Ø50 mm	133705	262	14,480	0,049
• Ø63 mm	133706	130	13,120	0,049
• Ø75 mm	133707	80	15,200	0,049
• Ø90 mm	133708	46	11,440	0,049
• Ø110 mm	133709	33	14,340	0,049
• Ø125 mm	133711	20	9,620	0,049
• Ø140 mm	133712	11	8,280	0,049
• Ø160 mm	133713	8	8,840	0,049
• Ø200 mm	133714	8	13,100	0,094
• Ø225 mm	133715	6	12,800	0,094
• Ø250 mm	133716	4	13,200	0,124
• Ø280 mm	133717	3	15,800	0,124
• Ø315 mm	133718	2		0,124



"Female Threaded Cap"

Description	Code		eight Volume Kg m³
• Ø50 mm	133705T	210	0,049
• Ø63 mm	133706T	130	0,049
• Ø75 mm	133707T	80	0,049
• Ø90 mm	133708T	46	0,049
• Ø110 mm	133709T	33	0,049
• Ø125 mm	133711T	46	
• Ø140 mm	133712T	33	
• Ø160 mm	133713T		
• Ø200 mm	133714T		
• Ø225 mm	133715T		



"Male Threaded Cap"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2,5"	133722			
• 3"	133723			
• 4"	133724			



"Caps Male Threaded"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" Male Threaded w/oring	133728T			
• 2" Male Threaded w/oring	133729T			

Unions

"Both Side Female Union"

O-ring in EPDM. Compatible with Fitvalf d.50 mm ball valve handle.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.20 mm	132111	250	11,400	0,021
• d.25 mm	132112	200	12,800	0,021
• d.32 mm	132113	150	13,400	0,021
• d.40 mm	132114	80	11,280	0,021
• d.50 mm	132115	100	19,600	0,094
• d.63 mm	132116	50	18,400	0,094
• d.75 mm	132117	30	22,300	0,094
• d.90 mm	132118	30	19,600	0,094
• d.110 mm	132119	20	30,000	0,094

UPVC One Sided Threaded Union. O-Ring in EPDM.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.20 mm	132111T1	250	11,400	0,021
• d.25 mm	132112T1	200	12,800	0,021
• d.32 mm	132113T1	150	13,400	0,021
• d.40 mm	132114T1	80	11,280	0,021
• d.50 mm	132115T1	100	19,600	0,094
• d.63 mm	132116T1	50	18,400	0,094
• d.75 mm	132117T1	40	22,300	0,094
• d.90 mm	132118T1	30	19,600	0,094
• d.110 mm	132119T1	20	30,000	0,094

UPVC Both Sided Threaded Union. EPDM O-Ring.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 0,5	132111T	250	11,400	0,021
• 0,75	132112T	200	12,800	0,021
• 1"	132113T	150	13,400	0,021
• 1,25"	132114T	80	11,280	0,021
• 1,5"	132115T	100	19,600	0,094
• 2"	132116T	50	18,400	0,094
• 2,5"	132117T	40	22,300	0,094
• 3"	132118T	30	19,600	0,094
• 4"	132119T	20	30,000	0,094



Unions

UPVC Unions. Female socket / Male threaded.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5" - d.50 mm	132121	100	24,200	0,094
• 2" - d.63 mm	132122	50	21,800	0,094
• 1,5" - d.63 mm Male Adapter.	132123	50	21,400	0,094
• 1,5" - d.50 mm*	1321211	100	24,200	0,094

^{* 1321211} code must be ordered to be used with GEMAS multiport valves 02400T, 02404T, and 02403T



"Brass Union Female Threaded"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• d.20 mm	133450			
• d.25 mm	133451			
• d.32 mm	133452			
• d.40 mm	133453			
• d.50 mm	133454			
• d.63 mm	133455			



UPVC Fittings - Flange Adaptors

"UPVC Flange Adaptor"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	133927	200	13,600	0,049
• Ø63 mm	133928	100	11,200	0,049
• Ø75 mm	133929	70	12,400	0,049
• Ø90 mm	133908	42	10,850	0,049
• Ø110 mm	133909	25	10,380	0,049
• Ø125 mm	133910	15	9,400	0,049
• Ø140 mm	133911	14	8,940	0,049
• Ø160 mm	133912	16	18,320	0,094
• Ø200 mm	133913	8	12,640	0,094
• Ø225 mm	133914	8	14,740	0,094
• Ø250 mm (NEW)	133915	5	14,800	0,124
• Ø280 mm	133916	4	11,700	0,124
• Ø315 mm	133917	2	8,500	0,124







Unions

"Female Threaded Flange Adaptor"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1,5"	133927T			
• 2"	133928T			
• 2,5"	133929T			
• 3"	133908T			
• 4"	133909T			
• 4,5"	133910T			
• 5"	133911T			
• 6"	133912T			
• 7"	133913T			
• 8"	133914T			

Flange Adaptors and Flanges



"UPVC Flange"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	1331005	70	17,800	0,049
• Ø63 mm	1331006	60	19,100	0,049
• Ø75 mm	1331007	50	21,200	0,049
• Ø90 mm	1331008	40	15,940	0,049
• Ø110 mm	1331009	34	15,200	0,049
• Ø125 mm	1331010	23	15,060	0,049
• Ø140 mm	1331011	23	13,680	0,049
• Ø160 mm	1331012	25	20,840	0,094
• Ø200 mm	1331013	16	26,440	0,094
• Ø225 mm	1331014	16	24,080	0,094
• Ø250 mm (NEW)	1331015	5	14,800	0,124
• Ø280 mm	1331016	4	9,600	0,124
• Ø315 mm	1331017	2	5,600	0,124



"Blind Flange"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø110 mm	1331109	34		
• Ø125 mm	1331110	23		
• Ø140 mm	1331111	23		
• Ø160 mm	1331112	25		
• Ø200 mm	1331113			
• Ø225 mm	1331114			



Flange Adaptors and Flanges

"Vibration Flange"

Description	Code	Pieces/ Weight box Kg	Volume m ³
• d.50 mm	0141113		
• d.65 mm	0141114		
• d.80 mm	0141115		
• d.100 mm	0141116		
• d.125 mm	0141117		
• d.150 mm	0141118		
• d.200 mm	0141119		
• d.250 mm	0141120		
• d.300 mm	0141121		
• d.350 mm	0141122		
• d.400 mm	0141123		
• d.450 mm	0141124		
• d.500 mm	0141125		
• d.600 mm	0141126		



Hose Connection and Wall Conduit Flanges

UPVC Hose Connection. O-rings in EPDM.

One side is external threaded, the other side is internal slip.

Code	Pieces/ box	Weight Kg	Volume m ³
136115	100	24,200	0,094
136125	50	21,800	0,094
	50	21,400	0,094
	136115	Code box 136115 100 136125 50	Code box Kg 136115 100 24,200 136125 50 21,800





UPVC Wall Conduit Flange.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø63 mm	041602			
• Ø75 mm	041603			
• Ø90 mm	041604			
• Ø110 mm	041605			





UPVC Pipes - 6 bars

UPVC Solvent Cement Socket Pressure Pipes for Clean Water:

UPVC Clean Water Pipes have a smooth and a regular surface. Resistant to pressure and atmosphere conditions. With its high durability to chemicals, it is suitable for all kinds of liquid flow. Manufactured according to the norms of TS274, EN 1452 and DIN 8062,19532. They are the most common products that are used for the transfer of clean water with their simple installation and transfer, durability and healthy structure.

As Grade is the major principle for our Grade. Tests and analysis are done regulary at the laboratory.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø50 mm	1390601			
• Ø63 mm	1390602			
• Ø75 mm	1390603			
• Ø90 mm	1390604			
• Ø110 mm	1390605			
• Ø125 mm	1390606			
• Ø140 mm	1390607			
• Ø160 mm	1390608			
• Ø200 mm	1390609			
• Ø225 mm	1390610			
• Ø250 mm	1390611			
• Ø280 mm	1390612			
• Ø315 mm	1390613			
• Ø355 mm	1390614			
• Ø400 mm	1390615			

UPVC Pipes - 10 bars - 16 bars

UPVC Solvent Cement Socket Pressure Pipes for Clean Water. 10 BARS



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	1391000			
• Ø25 mm	1391001			
• Ø32 mm	1391002			
• Ø40 mm	1391003			
• Ø50 mm	1391004			
• Ø63 mm	1391005			
• Ø75 mm	1391006			
• Ø90 mm	1391007			
• Ø110 mm	1391008			
• Ø125 mm	1391009			
• Ø140 mm	1391010			
• Ø160 mm	1391011			
• Ø200 mm	1391012			
• Ø225 mm	1391013			



UPVC Pipes - 10 bars - 16 bars

UPVC Solvent Cement Socket Pressure Pipes for Clean Water. 10 BARS

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø250 mm	1391014			
• Ø280 mm	1391015			
• Ø315 mm	1391016			
• Ø355 mm	1391017			
• Ø400 mm	1391018			



UPVC Solvent Cement Socket Pressure Pipes for Clean Water. 16 BARS

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø20 mm	1391601			
• Ø25 mm	1391602			
• Ø32 mm	1391603			
• Ø40 mm	1391604			
• Ø50 mm	1391605			
• Ø63 mm	1391606			
• Ø75 mm	1391607			
• Ø90 mm	1391608			
• Ø110 mm	1391609			
• Ø125 mm	1391610			
• Ø140 mm	1391611			
• Ø160 mm	1391612			
• Ø200 mm	1391613			
• Ø225 mm	1391614			
• Ø250 mm	1391615			
• Ø280 mm	1391616			
• Ø315 mm	1391617			
• Ø355 mm	1391618			
• Ø400 mm	1391619			



UPVC Solvent Cements



"FITVALF UPVC Solvent Cement". Plastic bottle with brush. ASTM Heavy Duty formula. Low Viscosity, Fast Curing Time.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Fitvalf 1000 ml	13525	12		
• Fitvalf 500 ml	13527	12	6,900	0,011
Fitvalf 250 ml	13529	24	7,600	0,011
• Fitvalf 125 ml	13537	16		
CHRISTY'S Solvent Cement 1 KG	13570			
• Fitvalf UPVC Solvent Cement 125 ml Tube	13580			

"FITVALF Pool UPVC Solvent Cement". Plastic bottle with brush. Medium Duty formula. Medium Viscosity, Normal Curing Time.

Description		Code	Pieces/ box	Weight Kg	Volume m ³
• Fitvalf Pool 1	000 ml	13531	6		
• Fitvalf Pool 5	00 ml	13550	12	7,200	0,012
• Fitvalf Pool 2	50 ml	13554	24	6,900	0,011
• Fitvalf Pool 1	25 ml	13556	16	7,600	0,011
Hydrodif Glue	e for UPVC Flex Tubes-50	0 gr 13530			

Shirt-His

13530

UPVC Solvent Cements



"Fast UPVC Cements" Made in USA.

Can be pressurized to system 15 minutes after application.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
1 kg	13540			

UPVC Pipe Clamps

UPVC Pipe Clamps.



Code	Pieces/ box	Weight Kg	Volume m ³
133350			
133351			
133352			
133353			
133354			
133355			
133356			
133357			
133358			
133359			
133360			
133361			
	133350 133351 133352 133353 133354 133355 133356 133357 133358 133359 133360	Code box 133350 133351 133352 133353 133354 133355 133356 133357 133358 133359 133360	133350 133351 133352 133353 133354 133355 133356 133357 133358 133359 133360




Starting Platforms

Track-Start Platforms. Made of FRP, AISI 304 stainless steel handles. Foot rest pad can be adjusted to front or back. Platform in non-slip and large surface.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Height: 400 mm	14141	1		
Relay Sensor, Mechatronic	14141DS	1		
Height: 700 mm (NEW)	14142	1		












14141DS





Fixed Starting Platforms. Made of FRP, AISI 304 grade stainless steel top and front handles. Height can be adjusted up to 700 mm through the elevation platform. FRP turning panels can be adapted to front side of the platform.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Height: 400mm	14151	1		
Height: 700mm	14152	1		
FRP Turning Panel (Optional)	14153	1		





14151

View with elevation platform




Starting Platforms



Starting Platform with Elevation and Turning Podiums. Made of FRP over steel frame, h=300 mm, height adjustable legs. Used with 400 mm height starting platforms. Each for every swim lane.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 2000 x 1000 mm	141411	1		
• 2500 x 1000 mm	141412	1		

PS: For platform connection, the dimensions of "A, B, C, D and E" must be given.




Starting Platforms; **Adjustable**. Base in AISI 304 grade stainless steel, platform in fiberglass reinforced polyester with non-slip finish. 500 x 500 mm. Special anchor to be installed in concrete slab is upon request.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Height : 700 mm	14111	1	23,112	0,340
Height: 400 mm	14112	1	17,200	0,375






Special Anchor (Optional)





Adjustable Starting Platform. AISI 304 grade stainless steel cylindrical body. The platform can by adjusted 3 cm forwards or backwards. The handle is also independently adjustable by 3 cm. Non-slippery surface, polyester and fiberglass 500 x 500 mm platform.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Height: 400 mm	14113	1		
Height: 700 mm	14114	1		
30 ±2	39.a2 II	30.52		







Starting Platforms

Starting Platforms; Fixed. Base made of AISI 304 grade stainless steel Ø42 mm. pipe, platform in fiberglass reinforced polyester with non-slip finish. 500 x 500 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Height: 700 mm	14121	1		
Height : 400 mm	14122	1		










Starting Platforms; Fixed. Base made of AISI 304 grade stainless steel, platform in fiberglass reinforced polyester with non-slip finish. 500 x 500 mm.

600 ±10

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Height: 700 mm	14131	1		
 Height: 400 mm 	14132	1		









Special Anchor (Optional)



Anchors



Level Anchors for Zurich and Wiesbaden Type Swimming Pools.

In AISI 304 grade stainless steel, for Ø42 mm pipe.

[Description Co	ode	Pieces/ box	Weight Kg	Volume m ³
	14	410	2	1,672	0,008



Inclined Anchors for Finnish Type Swimming Pools.

In AISI 304 grade stainless steel, for Ø42 mm pipe.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14420	2	1,020	0,008



Level Anchors with Bolts for "14121" and "14122" Starting Platforms.


In AISI 304 grade stainless steel for Ø42 mm pipe.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14430	2	1,240	0,008

Turning Panels

Turning Panels for Overflow Competition Pools.


Frame in AISI 304 grade stainless steel frame screened with plastic grating. Height 300 mm.




Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Lane width : 2,0 m	14210	1	12,000	
• Lane width : 2,5 m	14220	1	14,000	
Support for turning panels in	14201	2	7,000	
AISI 304 grade stainless steel.				


PS: Designed to be fixed with "14410" or "14420" anchors which are not included.

"L" and "H" should be dimensioned when ordering.





Pipe center size should be given






Post Set

Set of Backstroke Turn Indicators. Composed of 2 posts Ø42 mm. in AISI 304 grade stainless steel. Height: 1,80 m. One of them is with a pulley and the other with a fixing element for cord. Complete with nylon cord and flags.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For pools of 12,5 m width	14311	1	16,000	0,060
• For pools of 25 m width	14312	1	14,000	0,050

PS: Designed to be fixed with "14410" or "14420" anchors which are not included.






Set of False Start Posts. Composed of 2 posts Ø42 mm. in AISI 304 grade stainless steel. Height: 1,80 m. One of them is with a pulley and the other with a fixing element for cord. Complete with plastic floats and nylon cord.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For pools of 12,5 m width.	14321	1	12,000	0,057
• For pools of 25 m width.	14322	1	14,000	0,030

PS: Designed to be fixed with "14410" or "14420" anchors which are not included. Two sets are necessary for a competition pool.







Floating Lanes

Rome Model. Complete with plastic floats, nylon line and 1 hook.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14511	1	8,700	0,135
• Length: 50 m	14512	1	17,400	0,265









Floating Lanes

Seul Model. Complete with plastic floats, nylon line and 1 hook




Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14521	1	23,700	0,340
• Length: 50 m	14522	1	47,400	0,620



Moscow Model. Complete with plastic floats, nylon line and 1 hook




Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14531	1	22,150	0,340
• Length: 50 m	14532	1	44,300	0,620



Sydney Model. Complete with plastic floats, nylon line and 1 hook



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14541	1		
• Length: 50 m	14542	1		






Post Set

Set of Backstroke Turn Indicators. Composed of 2 posts Ø42 mm. in AISI 304 grade stainless steel. Height: 1,80 m. One of them is with a pulley and the other with a fixing element for cord. Complete with nylon cord and flags.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For pools of 12,5 m width	14311	1	16,000	0,060
• For pools of 25 m width	14312	1	14,000	0,050

PS: Designed to be fixed with "14410" or "14420" anchors which are not included.







Set of False Start Posts. Composed of 2 posts Ø42 mm. in AISI 304 grade stainless steel. Height: 1,80 m. One of them is with a pulley and the other with a fixing element for cord. Complete with plastic floats and nylon cord.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• For pools of 12,5 m width.	14321	1	12,000	0,057
• For pools of 25 m width.	14322	1	14,000	0,030

PS: Designed to be fixed with "14410" or "14420" anchors which are not included. Two sets are necessary for a competition pool.







Floating Lanes

Rome Model. Complete with plastic floats, nylon line and 1 hook "14650"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14511	1	8,700	0,135
• Length: 50 m	14512	1	17,400	0,265









Floating Lanes

Seul Model. Complete with plastic floats, nylon line and 1 hook "14650"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14521	1	23,700	0,340
• Length: 50 m	14522	1	47,400	0,620




PS: For FINA standarts, all floating lanes must be ordered with Stainless Steel line (14632).

Moscow Model. Complete with plastic floats, nylon line and 1 hook "14650"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14531	1	22,150	0,340
• Length: 50 m	14532	1	44,300	0,620




PS: For FINA standarts, all floating lanes must be ordered with Stainless Steel line (14632).

Sydney Model. Complete with plastic floats, nylon line and 1 hook "14650"



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Length: 25 m	14541	1		
• Length: 50 m	14542	1		




PS: For FINA standarts, all floating lanes must be ordered with Stainless Steel line (14632).



Floaters

"Rome Model". Floater.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
White	145101	500	7,000	0,110
• Orange	145102	500	7,000	0,110
• Blue	145103	500	7,000	0,110
• Red	145104	500	7,000	0,110



"Seul Model". Floater.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
White	145201	150	7,000	0,080
• Orange	145202	150	7,000	0,080
• Blue	145203	150	7,000	0,080
• Red	145204	150	7,000	0,080



Floating Lane Accessories

Seperator Collector Trolley. It has 4 wheels which 2 of them with brakes. Covered with PVC canvas for avoiding dripping out of excess water. Design to carry 1 piece 50m seperator. It's for the installation of the seperator with stainless steel anchors in the overflow pools. AISI 304 grade stainless steel. Dimenson is 200 x 100 x 84. Has a 0,75 release valve in the bottom, to drain collected water.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14680	1		

Float Lane Roller. Made of AISI 304 grade stainless steel, Ø42 pipe. Width: 1,20 m.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Width: 1,20 m	14660	1	25,000	2,200
• Width: 1,80 m	14661	1		

Roller Capacity: Width 1,20 m				
FLOAT LINE	25 m	33 m	50 m	
Seul Model	4	2	2	
Rome Model	8	6	4	
Moscow Model	4	2	2	

Roller Capacity: Width 1,80 m				
FLOAT LINE	25 m	33 m	50 m	
Seul Model	6	3	3	
Rome Model	12	9	6	
Moscow Model	6	3	3	



Float Line. Rope.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Nylon.	14631	160 m	8,420	0,025
Ø7 mm. Price per meter.				
 Plastified Stainless Steel. 	14632			
Ø5 mm. Price per meter.				





Floating Lane Accessories



Ergonomic Seperator Tensioner. Body made of GF-PP and accessories from AISI 316. complete with 7 mm thick hook, SS rope fixing accessories. Threaded tension rod and easy grip plastic body allows easy tightening up to 130 mm. Can only used with SS lane ropes

De	scription	Code	Pieces/ box	Weight Kg	Volume m ³
		14643			



Separator Vibration Damping Spring. In AISI 316 grade stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14644	1	0,686	0,001



Floating Line Tensor with Spring. In chrome plated bronze.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14641	1	0,686	0,001



Floating Line Tensor with Screw. In AISI 304 grade stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14642	6	0,182	



Rope Anchor. Made of bronze. 0,75.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14651		0,186	



Line Hook. To be attached at one end of float lane. In AISI 304 grade stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14650		0.186	



Lane Anchor Cup. AISI 304 grade, to be embedded to pool wall.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Model 1	14611	1	22,150	0,340
• Model 2	14627	1	44,300	0,620



Float Support. To be used with anchors "14410" and 14420". In AISI 304 grade stainless steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	14620	2	0,520	



Floating Lane Accessories

Refree Seat. Made of AISI 304 grade stainless steel and Ø42 mm pipe.

Refree Seat. Made of Alor 304 grade Stalliess steel and 042 min pipe.				10	
Description	Code	Pieces/ box	Weight Kg	Volume m ³	
Model 1	14670	1	0,566	0,001	7
• Model 2	14671	1			\Box .
Model 1 500	325 ± 5 325 ± 5 325 ± 5 325 ± 5 325 ± 5 435 ± 5	1800±30	1250 ±5	500 ±10 250 ±5 250 ±5 250 ±5 250 ±5	Model 1

Automatic Timing Systems for Competition Pools ALGE TIMEMANAGER TM-SWIM



PLEASE ASK PRICE ON PROJECT BASIS

ALGE TIMEMANAGER TM-SWIM SPECIFICATIONS


- PC based timing system
- Easy connection to new generation lap-top and PC with USB interface
- User friendly
- Swimlane control with 16 touchpads
- Audio and optic control for each swimlane
- Each swimlane can be connected to 5 independent timing channels (1 touchpad, 3 button, 1 Relay Time)
- Integrated battery system 4 hours working time
- Integrated speaker system
- False start warning on the screen
- Detection and warning system for difference of timing channels
- Reliable Touchpads
- · Saving the statistics values
- Compatible with FINA, SSCH, AAU, NCAA and LEN regulations.



AUTOMATIC TIMING SYSTEMS FOR COMPETITION POOLS ALGE TIMEMANAGER TM-SWIM

PC Software

Alge Swimtime Software provides the information of time-manager processor, with user friendly and visual interface. Available for all Windows Systems.





- · User Friendly software
- Visual illustration
- · Same layout with pool
- Free update for 10 years
- Back-up Battery
- · Manage 16 swimlane
- Competitors Information





COMPETITION POOL SCORE SYSTEM PRODUCTS



TimeManager TM-SWIM: It's the processor that all timing activities are processed and recorded. Easy connection to new generation lap-top and PC with USB interface. Automatic timing, recording and instant printout. In this way, printouts of all timings are obtained in case of a system issue. Complete with speaker, 4 hour battery for power cut, printer, score board, starting system, auditory and visual warning inputs. Measuring range is 23 hours, 59 minutes, 59,9999 seconds.



TouchPads TP2400/TP1800: The most important instrument of the system. Quality of this product determines quality of the system. The backside is made of stainless steel. To be found in two different swimlane measures.



SWIM Terminal SWT3: Needs to be installed to each swimlane. The TimeManager automaticly finds and enumerates SWT3 which is founded in each swimlane. 5 different time channels can be connected to every SWT3 terminals; 1 x touchpad, 3 x Manuel Time Buttons, 1 x starting time



Manuel Time Buttons: Waterproof design, 2 m cable.



Start Unit: Complete with integrated microphone and start buton.



Track Start Blocks. Made of FRP. Foot rest pad can be adjusted for ergonomic start.



Active (SPA) and Passive (SPP) Speakers. Each active speakers includes a amplifier and controls a passive speaker.



Platform with Time Sensor: Can be adapted to available platforms. Starting time detection platform adaptor.




LED SCORE BOARDS: Options for 1, 8, 10 lines, wall matrix video options and options for colored displays.




Backstroke Starting Kit. Prevents the start through the glide from touching panel. Compatible with GEMAS Starting Platform













10 LINES MATRIX LED SCOREBOARD

Below seen videowall is optional







Massage Jets



"Freedom" model massage jet. Water connection d.50 mm, air connection Ø 32 mm, complete with internal set. Recommended flow; 1,5 m 3 /h - 7 mSS

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-FS715	1	0,380	



"Freedom" model massage jet internal set. Adjustable type

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-FS00TA	1	0,090	



"Hydrojet" model massage jet. Complete with nozzle. Water and Air connection Ø 50 mm, PVC, including nozzle. Recommended flow; 1,5 m³/h - 7 mSS

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-4100	1	0,440	



"Magna" Model Massage Jet Body. Water connection d.50, air connection d.32, excluding nozzle. Recommended flow; 2,7 m³/h - 7 mwh

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-4833	1	0,440	



To be used for "Magna" Model Massage Jet.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Magna'SSage: Single mouth 0,008	1516-4821	1	0,062	
heading jet nozzle.				
Magna'SSage: Double mouth	1516-4820	1	0,078	
swivel heading jet nozzle.				



"SP-1434A" Model Massage Jet. Water and air connections Ø 50 mm; PVC, 2" inlet included. Recommended flow; 1,5 m 3 /h - 7 mwh

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-1434A	1		



"SP-1434ASS" Model Massage Jet. Water and air connection Ø 50, PVC, 2" inlet included. Frame is stainless steel. Recommended flow; 1,5 m³/h - 7 mwh

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-1434ASS			



Massage Jets


Massage Unit.


Bare unit. Can be installed as single or multiple wall-floor massage stations. Comes with air suction hose and wall-floor air regulator.

Description	Code	Pieces/ box	Weigh Kg	Volume m ³
• Model 1 - Ø40 mm	1510-1435	1		
• Model 2 - Ø28 mm	1510-1436			



1510-1436







1510-1435


Massage Unit.

Used for massage from the floor.

Comes with air suction hose and wall-floor air regulator.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Model 3 - 5 x Ø19 mm	1510-1437	1		





"EM" Model Massage Jets. Water connection D.50, air connection D.32. Complete with adjustable type internal set.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1596601207	1	0,420	



"EM" Model Massage Jet Internal Set.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Adjustable type, Recommended Flow 1,5m³/h	1588090812	1	0,090	
 Rotary type, Recommended Flow 1,5m³/h 	1588090912	1	0,090	





1588090812

1588090912



Massage Jets



"Swimjet" Model Massage Jet. Water connection Ø 63 mm, air connection Ø 32 mm, length 145 mm. Recommended flow; 16 m 3 /h - 7 mwh

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1516-5759	1	0,420	



"Hydrojet" Model Massage Jet Extension. L=105 mm, ABS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-4400	1	0,214	



"Venturi TEE" Model Massage Jet Body. Water connection Ø 48,6 mm, length excluding nozzle: 260 mm. Suggested discharge: $5m^3/h$ - 7mwh (Used for building massage station inside the pool).

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1510-4320	1	0,253	



"Venturi TEE" Model Massage Jet Inlet.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
F.I.S. F <tt<ngs.< td=""><th>1510-3420</th><td>1</td><td>0,090</td><td></td></tt<ngs.<>	1510-3420	1	0,090	

Air Jets



Air jet. White, ABS.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 9 Holes - Top, Removable Cover	1511-9201	1		
• 9 Holes - Top	1511-9202	1		

Suction Drain



"Big Type" Suction Drain.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
White ABS, 3" external thread 0,008	1510-6201	1	1,222	
Ø 152 mm external diameter				
Ø 90 mm Slip Connection				
Recommended Flow Rate 20 m³/h				




Air Blowers


BLOWERS FOR DISCONTINUED USE.

Genesis Blower 1,2 kW, 230 V/50 Hz. Maximum pressure: 3,0 mwh, Maximum recommended flow rate: $160 \text{ m}^3/\text{h}$.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Genesis Blower 1,2 kW	15GB120-2NN-3	1	2,792	0,011











"Air Blower for Continuous Use"


Description	Code	Pieces/ box	Weight Kg	Volume m ³
Blower 1.3 kW, Single Stage, 220/380V	15410H26	1	17,000	
Blower 2.2 kW, Single Stage, 220/380V	15610H16	1	28,000	
Blower 2.2 kW, Double Stage, 220/380V	15420H46	1	27,000	
Blower 3 kW, Single Stage, 220/380V	15630H26	1	35,000	
Blower 3 kW, Double Stage, 220/380V	15720H26	1	48,000	
• Blower 4.3 kW, Double Stage, 380/660V	15730H47	1	45,000	
Blower 4.3 kW, Double Stage, 380/660V	15720H37	1	54,000	
Blower 5.5 kW, Double Stage, 380/660V	15720H47	1	70,000	
Blower 7.5 kW. Double Stage, 380/660V	15720H57	1	74.000	




TECHNICAL CHARACTERISTICS

MODEL	15410H26	15610H16	15420H46	15630H26	15720H26	15730H47	15720H37	15720H47	15720H57
Frequency (Hz)	50	50	50	50	50	50	50	50	50
Power (kW)	1.3	2.2	2.2	3	3	4.3	4.3	5.5	7.5
Voltage (V)	220-380	220-380	220-380	220-380	220-380	380∆-660Y	380∆-660Y	380∆-660Y	380∆-660Y
Current (A)	5.7	9.7	9.7	12.5	12.5	9.5	10	13.3	16.7
Max. Flow (m ³ /h)	145	265	150	345	320	420	320	320	320
Vacuum (mbar)	-170	-235	-330	-240	-280	-265	-360	-440	-440
Pressure (mbar)	200	220	420	220	260	290	380	500	570
Noise (dB)	63	69	66	70	73	70	73	73	73
Weight (Kg)	17,000	28,000	27,000	35,000	48,000	45,000	54,000	70,000	74,000









Air Buttons

1522-1043 1522-1044

"Standard" Pneumatic Air Button

Description	Code	Pieces, box	/ Weight Kg	Volume m ³
Body external diameter 31,5 mm,	1522-1043	1	0,020	
3 mm tube connection.				
Body external diameter 1",	1522-1044			
3 mm tube connection.				



Gemas Pneumatic Air Button

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Gemas Large model air button with	156437	1	0,035	
Ø 63 mm 2" connection				
Gemas Small model air button with	156438	1	0,022	
Ø 50 mm 1.5" connection				

PS: h = 67mm. 4 mm air connection. Effective from 25 meters.

Pneumatic Switch Boards



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• PNEUMATIC SWITCH BOARD,	05080	1	0,748	
Complete with contactor and circuit bre	eaker for up to 4 kw to	riphase pumps.		
Assembled in a humid resistant plastic	box.			
• PNEUMATIC SWITCH.	156871	1	0,020	
Permanent type. Up to 1 HP				
• PNEUMATIC SWITCH HOSE.	15310			
D 2.0 - 4.0 mm. Price per meter.				

Electronic 3-Function Button



GEMAS "Electronic Button" 64mm.

Works with the driver. It can be installed / used outdoors. UV protected touch pad.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3-Function Button	15231	1		
• Driver	15230	1		

Air Regulators





1510-2100S

De





1510-2200 1510-2300

"Standart" Type Air Regulator

J				
Description	Code	Pieces/ box	Weight Kg	Volume m ³
Big model 1 1/4" male threaded	1510-2100	1	0,084	
• Big model 1 1/4" male threaded. St.Steel	1510-2100S	1		
• Small model 3/4" male threaded	1510-2200	1	0,036	
• Small model 1" male threaded. Chrome-plated.	1510-2300	1		



Caps

Hydro-Air "Caps"

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø 50 mm	1520-1015	1	0,036	



PVC Flexible Tubes

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Ø 32 mm PVC Flexible Tube	15410			
• Ø 50 mm PVC Flexible Tube	15420			
• Ø 63 mm PVC Flexible Tube	15430			



Flexible Tube Cement

Description	Code	Pieces/ box	Weight Kg	Volume m ³
500 ml	13530	1	0,500	



SPA Underwater Lights

"Mini 2001" Underwater Lights. Heat resistant plastic body, bottom outlet. Complete with 2 m. cable. 50 W/12 V bulb or 4,2 W power LED. Led bulbs is 100% sealed from water with transparent epoxy.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Slip type body with plastic frame	05112S	4	2,000	0,007
• 05112S,6 W/12 V SMD 36 LED	05112SLS	4		
• 2" Threaded body with plastic frame	05112T	4	2,100	0,007
• 05112T, 6 W/12 V SMD 36 LED	05112TLS	4		



05112SLS



05112T

Nut for Mini Underwater Light, for FR-Polyester Pools. Made of white ABS Plastic with 2" internal thread. Complete with gasket.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Ø 50 mm	04237	35	1,474	0,006





Steam Generators with Electric Heater



FL Series Steam Generator.

Device protection when it is without water. High pressure protection, automatic water fill up and drainage. All models should be used with an external control panel. One remote control panel can operate 2, 3 or 4 pieces combined with steam generator. Generator feeding water should not be over 0-5 Fh (French Hardness) hardness level. Otherwise it will be out of warranty. Complete with safety valve.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• FL-45, 4,5 kW	182101			
• FL-60, 6 kW	182102			
• FL-90, 9 kW	182104			
• FL-120, 12 kW	182105			
• FL-150, 15 kW	182106			
• FL-180, 18 kW	182107			



Control panels for steam generators with electric heater. The "Operating" light, steam room temperature display, working hour countdown, automatic disinfection function (ozone) can be obsevered outside the panel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• FAN-T, For 60/90 models	182201			
• FAN-M, For 120/180 models	182202			



STEAMER STEAM GENERATORS WITH ELECTRODE.

The product is not negatively effected from hard water. Automatic water filling and drainage. Device can be adjusted gradually and operated to the max. 10 kW level. Electrode and tanks are washed automatically. Can be operated automatic and manual. Phase protection exists on the device. Body electrostatic painted and Stainless Steel 304 Quality. 40x200 mm LCD Board is on the device enabling to observe all the control values. 3 functional key gives opportunity for manual operation, automatic operation and stopping the system and draining. All devices are used with external control panels. 3 steam generators can be combined and controlled by 1 piece remote control. 1 It Lime Protector included in price.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• EL1000-3, up to 18 kW	182111			
Lime Protector 1 liter	075311			



Steam Generators with Electric Heater

Control Panel for STEAMER Steam Generators with Electrode.

Device is controlled with touch pad. The cabinet Lightning, ventilation and heating-steam function can be controlled separately with time clock trough the device. It can be programmed each week day separately. Same Control panel can control 3 pieces generators. Enables possibility to operate Monophase or Triphase. It is not mandatory to be used with steam generator.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
ELKT1000	182211			

Steam Room Accessory Equipments

Steam Nozzle.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Stainless Steel AISI 304	182301	1		
Steam Nozzle Plastic	182302			



182301



182302

Steam Bath Door.

8 mm thick tempered glass. Aluminium hinge, plastic handle. 71,5x200x5,5 cm

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	182401	1		



Steam Bath Door Handle. Made of plastic.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	1824011	1		





Prefabricated Construction Materials for SPA




Relaxation Beds

Made of Extruded polystyrene, XPS, hard foam and all surfaces are reinforced with fiber glass and covered with industrial plaster. There will no need of construction process, glass mosaics can be covered directly right after delivery.

Descripti	ion	Code	Pieces/ box	Weight Kg	Volume m ³
		184101			
	2000				








Steam Room Seats

Made of Extruded polystyrene, XPS, hard foam and all surfaces are reinforced with fiber glass and covered with industrial plaster. There will no need of construction process, glass mosaics can be covered directly right after delivery.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	185101			






Rounded Shower Cabin

Made of Extruded polystyrene, XPS, hard foam and all surfaces are reinforced with fiber glass and covered with industrial plaster. There will no need of constructive process, glass mosaics can be covered directly right after delivery. 50x1020x2000 mm.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	186101			



Spiral Shower Cabin

Made of Extruded polystyrene, XPS, hard foam and all surfaces are reinforced with fiber glass and covered with industrial plaster. There will no need of constructive process, glass mosaics can be covered directly right after delivery. 50x1575x1950x2000 mm

Description	Code	Pieces/ box	Weight Kg	Volume m ³
	186102			



SPA BS-691

5 Kişilik Akrilik Lüks Masaj Küveti-SPA

5 Persons Luxury Hot Tub Spa

Klasik Seri SPA:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi, şelale opsiyonu ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

Classic Series SPA

Classic Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose. If you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt
151140	SPA BS-691-Bulut Siyahı/Cloud Black	2350x2350x900mm	Kızıl Kahve/Red Brown
151141	SPA BS-691-Okyanus Mavisi/Ocean Blue	2350x2350x900mm	Kızıl Kahve/Red Brown
151142	SPA BS-691-Bulut Beyazı/Cloud White	2350x2350x900mm	Gri/Grey





151142





151140





151141

Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: 2350 x 2350 x 900 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 2 x 2.2kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5"dönen jet/Rotating jet: 2 pcs

5" jet: 3 pcs

4,5"dönen jet/Rotating jet: 6 pcs

3,5"dönen jet: 9 pcs

3,5" jet: 7 pcs

2,5"dönen jet/Rotating jet: 18 pcs

2,5" jet: 18 pcs

Hava Ayarlayıcı/Air Regulator: 3 pcs

Standart Kabuk/Shell: Akrilik/Acrylic Etek/Skirt: PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW Filtre/Filter: 1 pc

• UV Light

Isitici/Heater: 1 x 3kW
Ozon/Ozone System: 1pc

LED: 5" LED 1 pc Small LED 14 pcs

Su Tahliye/Drain: 1 pc Su Emiş/Suctions: 4 pcs Su Yönlendirici/Diverter: 1 pc Parmak Fıskiye/Comet: 2 pcs Hacim/Volume (m³): 1.4m³

Koltuk/Seat: 5 pcs Yastık/Pillow: 2 pcs Hoparlör/Speaker: 2 pcs Merdiven/Stairs: 1 pc

Toplam Güç/Total power: 8.35kW Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/ Plywood case







SPA BS-194

6 Kişilik Akrilik Lüks Masaj Küveti-SPA

6 Persons Luxury Hot Tub Spa

Klasik Seri SPA:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

Classic Series SPA:

Classic Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose of you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt	
151143	SPA BS-194-Bulut Beyazı/Cloud White	2220x2220x890mm	Gri/Grey	14





Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: 2200 x 2200 x 890 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 2 x 1.5kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5" LED'li dönen jet/Rotating jet: 3 pcs

5" power jet: 1 pc 3,5"dönen jet: 3 pcs 3/4" jet: 52 pcs Baloncuklu ışık jet/ light with bubble Jet: 4 pcs Air bubble Jet: 12pcs

Hava Ayarlayıcı/Air Regulator: 2 pcs

Standart Kabuk/Shell: Akrilik/Acrylic Etek/Skirt: PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW

Filtre/Filter: 1 pc
• UV Light

Isitici/Heater: 1 x 3kW
Ozon/Ozone System: 1pc
LED: 5" LED 1 pc
Su Tahliye/Drain: 1 pc
Su Emiş/Suctions: 4 pcs

Su Yönlendirici/Diverter: 2 pcs

Hacim/Volume (m³): 1.1m³
Koltuk/Seat: 6 pcs
Yastık/Pillow: 4 pcs
Hoparlör/Speaker: 2 pcs
Merdiven/Stairs: 1 pc
Toplam Güç/Total power: 6.95kW
Elektrik/Electric: 220 V / 50Hz

Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/ Plywood case







SPA BS-391

5 Kişilik Akrilik Üstten Taşmalı Lüks Masaj Küveti-SPA

5 Persons Luxury Overflow Hot Tub Spa

Klasik Seri SPA:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi, şelale, taşma tankı ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

Classic Series SPA:

Classic Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose. If you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt	
151144	SPA BS-391-Bulut Beyazı/Cloud White	Ø2300x900mm	Gri/Grey	



Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: Ø2300 x 900 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 2 x 1.5kW Hava Körüğü/Blower: 1 x 0.7kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5" LED'li dönen jet/Rotating jet: 2 pcs 3,5" LED'li dönen jet/Rotating jet: 3 pcs 2,5"dönen jet/Rotating jet: 20 pcs

3/5" jet: 31 pcs

Hava Ayarlayıcı/Air Regulator: 2 pcs

Standart Kabuk/Shell: Akrilik/Acrylic Etek/Skirt: PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW Filtre/Filter: 1 pc • UV Light

Isitici/Heater: 1 x 3kW Ozon/Ozone System: 1pc LED: 5" LED 1 pc Small LED 10 pcs

Su Tahliye/Drain: 1 pc Su Emiş/Suctions: 4 pcs Su Yönlendirici/Diverter: 2 pcs Şelale/Waterfall: 1 pc Hacim/Volume (m³): 1.7m³ Koltuk/Seat: 5 pcs Yastık/Pillow: 2 pcs Hoparlör/Speaker: 2 pcs Merdiven/Stairs: 1 pc

Toplam Güç/Total power: 6.95kW Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/







SPA BS-192H 6 Kişilik Akrilik Lüks Masaj Küveti-SPA

6 Persons Luxury Hot Tub Spa

H Serisi:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi, ozon, UV dezenfeksiyon, şelale ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

H Series

H Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose. If you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt
151145	SPA BS-192H-Bulut Mavisi/Cloud Blue	2080x2080x890mm	Gri/Grey
151146	SPA BS-192H-İnci Beyazı/Pearl White	2080x2080x890mm	Kahve Rengi/Coffee Color









151145

Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: 2080 x 2080 x 890 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 2 x 1.5kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5" LED jet: 3 pcs

3" LED jet: 6 pcs 2" jet: 8 pcs 1" jet: 34 pcs Air bubble Jet: 10pcs

Hava Ayarlayıcı/Air Regulator: 2 pcs

Standart Kabuk/Shell: Akrilik/Acrylic **Etek/Skirt:** PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW

Filtre/Filter: 1 pc
• UV Light

Isitici/Heater: 1 x 3kW
Ozon/Ozone System: 1pc
LED: 5" LED 1 pc

Su Tahliye/Drain: 1 pc **Su Emiş/Suctions:** 4 pcs **Su Yönlendirici/Diverter:** 2 pcs

Şelale/Waterfall: 1 pc

Şelale Anahtarı/Waterfall Switch: 1 pc

Hacim/Volume (m³): 1.1m³

Koltuk/Seat: 6 pcs Yastık/Pillow: 4 pcs Hoparlör/Speaker: 2 pcs Merdiven/Stairs: 1 pc

Toplam Güç/Total power: 6.95kW Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/







SPA BS-694H

7 Kişilik Akrilik Lüks Masaj Küveti-SPA

7 Persons Luxury Hot Tub Spa

H Serisi:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

H Series

H Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose. If you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

		1/1		17 A 14 A 15 A
Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt	
151147	SPA BS-694H-Bulut Beyazı/Cloud White	2200x2200x900mm	Gri/Grey	
151148	SPA BS-694H-Okyanus Mavisi/Ocean Blue	2200x2200x900mm	Gri/Grey	







151148

Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: 2200 x 2200 x 900 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 1 x 1.5kW

1 x 2.2kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5" Power LED jet: 1 pc 5" LED jet: 13 pcs

4" LED jet: 1 pc 3" LED jet: 15 pcs 1" jet: 8 pcs

Air bubble Jet: 12 pcs

Hava Ayarlayıcı/Air Regulator: 2 pcs

Standart Kabuk/Shell: Akrilik/Acrylic **Etek/Skirt:** PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW Filtre/Filter: 1 pc

• UV Light

Isitici/Heater: 1 x 3kW
Ozon/Ozone System: 1pc
LED: 5" LED 1 pc
Su Tahliye/Drain: 1 pc
Su Emiş/Suctions: 4 pcs
Su Yönlendirici/Diverter: 2 pcs

Parmak Fiskiye/Comet: 2 pcs
Fiskiye Anahtari/Fountain switch: 1 pc

Hacim/Volume (m³): 1.2m³ Koltuk/Seat: 7 pcs Yastık/Pillow: 3 pcs Merdiven/Stairs: 1 pc

Toplam Güç/Total power: 7.65kW Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/







SPA BS-593H

6 Kişilik Akrilik Lüks Masaj Küveti-SPA

6 Persons Luxury Hot Tub Spa

H Serisi:

Taşıyıcı iskelet üzerinde kompozit kaplamalı eteği ile standart özelliklerdedir. Renk seçenekleri mevcuttur. Yüksek standartlara sahip bir masaj havuzu isteyenler için iyi bir seçenektir.

Bu seri SPA'lar, akıllı ve kullanımı kolay bir kontrol sistemi ile donatılmıştır. Kulanıcıların kendileri için en iyi masaj modunu seçmeleri son derece kolaydır. Yüksek verimli/kaliteli masaj ve filtrasyon pompaları ile birlikte hava masajı fonksiyonu, bluetoothlu ses sistemi, ısıtma sistemi, LED'li ışık sistemi ve benzeri özellikler sunulmaktadır.

Tüm masaj küvetleri aşağıda listelenen teknik özelliklere ilaveten; plastik **iki basamaklı merdiveni, ısı izolasyonlu kış örtüsü** ile kompledir. Akrilik gövde dış tarafından Poli Üretan izolasyonla ısı kaybına karşı izole edilmiştir.

H Series

H Series SPA uses Classic Skirt, standard configurations, and there are lots of models and colors for you to choose. If you need a higher standard configurations massage pool, this is a good choice, each model has its own characteristics.

This series SPA has an intelligent, easy to operate control system, it's convenient for customer to use and choose the best massage mode. High efficiency/quality water pumps. Air bubble function, bluetooth system, heating system, cascade system, light system and so on.

Kod/Code	Ürün/Description	Boyut/Dimensions	Etek/Skirt
151149	SPA BS-593H-İnci Beyazı/Pearl White	2360x2260x900mm	Gri/Grey
151150	SPA BS-593H-Bulut Mavisi/Cloud Blue	2360x2260x900mm	Gri/Grey







151149

151150

Teknik Özellikler/Technical Specs:

Boyutlar/Dimensions: 2360 x 2260 x 900 mm **Kontrol Sistemi/Control System:** 1 set

Pompalar/Pumps

Masaj Jet Pompaları/Jet Pumps: 2 x 1.5kW

Hava Körüğü/Blower: 1 x 0.7kW Hava Nozulu/Air Nozzle: 24 pcs

Jet/Jets: 5" LED jet: 3 pcs

4" LED jet: 5 pcs 3" jet: 14 pcs 2" jet: 2 pcs 1" jet: 41 pcs Air bubble Jet: 10 pcs

·

Hava Ayarlayıcı/Air Regulator: 4 pcs

Standart Kabuk/Shell: Akrilik/Acrylic **Etek/Skirt:** PS Kompozit

Filtre Pompası/Filtration Pump: 1 x 0.25kW

Filtre/Filter: 1 pc
• UV Light

Isitici/Heater: 1 x 3kW
Ozon/Ozone System: 1pc
LED: 5" LED 1 pc
Su Tahliye/Drain: 1 pc
Su Emiş/Suctions: 4 pcs
Su Yönlendirici/Diverter: 2 pcs
Parmak Fiskiye/Comet: 3 pcs
Fiskiye Anahtari/Comet Switch: 1 pc


Hacim/Volume (m³): 1.4m³

Koltuk/Seat: 6 pcs Yastık/Pillow: 3 pcs Merdiven/Stairs: 1 pc

Toplam Güç/Total power: 6.95kW Elektrik/Electric: 220 V / 50Hz Ambalaj/Package: Kontrplak kasa/ Plywood case









Cascade Nozzles - Stainless Steel



Water level dependant foam-effect nozzles, should be operated under water level. Completely made of AISI 304 quality stainless steel.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Cascade (50T) 1" Male threaded:	161161	1		
Articulated. Ø50 mm water column				
• Cascade (70T) 1,5" Male threaded:	161121	1		
Articulated. Ø75 mm water column				
• Cascade (90T) 2" Male threaded:	161131	1		
Articulated. Ø97 mm water column				
• Cascade (110T) 2,5" Female threaded:	161141	1		
Articulated. Ø117 mm water column				
• Cascade (130T) 3" Female threaded:	161151	1		
Articulated. Ø135 mm water column				











Cascade Nozzles - Bronze

Water level dependant foam-effect nozzles, should be operated under water level. Completely made of bronze.




16115

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Cascade (50T) 1" Female threaded:	16111	1	0,722	0,0006
Articulated. Ø50 mm water column				
• Cascade (70T) 1,5" Female threaded:	16112	1	1,828	0,0015
Articulated. Ø75 mm water column				
• Cascade (90T) 2" Female threaded:	16113	1	2,346	0,0023
Articulated. Ø97 mm water column				
• Cascade (110T) 2,5" Female threaded:	16114	1	2,732	0,0045
Articulated. Ø117 mm water column				
• Cascade (130T) 3" Female threaded:	16115	1	14,194	0,0130
Articulated. Ø135 mm water column				



Cascade Nozzles




Flow and Pressure Indicators According to Nozzles Squirt Height


Squirt	CASC	ADE 50 1	-	CAS	CADE 70	Т	CAS	CADE 90	Т	CAS	CADE 110	Т	CASC	ADE 130)T
Height	Flow m³/h	Pressure re mSS	equirement atm	Flow m³/h	Pressure re	equirement atm	Flow m³/h	Pressure re mSS	equirement atm	Flow m³/h	Pressure re mSS	equirement atm	Flow m³/h	Pressure r	equirement atm
0,25 m	1,37	1,1	0,11	2,62	0,8	0,08									
0,50 m	1,93	2,1	0,21	3,70	1,5	0,15	7,39	1,9	0,19						
0,75 m	2,36	3,2	0,32	4,54	2,3	0,23	8,59	2,6	0,26						
1,00 m	2,73	4,2	0,42	5,24	3,1	0,31	9,65	3,3	0,33	14,44	3,0	0,30	20,72	3,0	0,30
1,50 m	3,35	6,4	0,63	6,42	4,6	0,46	11,46	4,7	0,47	17,41	4,4	0,44	25,01	4,4	0,44
2,00 m	3,86	8,5	0,85	7,42	6,2	0,62	13,04	6,0	0,60	19,95	5,8	0,58	28,67	5,8	0,58
2,50 m	4,32	10,6	1,06	8,29	7,7	0,77	14,43	7,4	0,74	22,20	7,2	0,72	31,91	7,1	0,71
3,00 m	4,73	12,7	1,27	9,08	9,2	0,92	15,70	8,7	0,87	24,24	8,5	0,85	34,86	8,5	0,85
4,00 m	5,46	16,9	1,69	10,49	12,3	1,23	18,00	11,5	1,15	27,87	11,3	1,13	40,10	11,3	1,13
5,00 m				11,73	15,4	1,54	20,00	14,2	1,42	31,09	14,0	1,40	44,73	14,0	1,40
6,00 m				12,85	18,5	1,85	21,85	16,9	1,69	34,00	16,8	1,68	48,93	16,8	1,68
8,00 m							25,12	22,4	2,24	39,18	22,3	2,23	56,39	22,3	2,23
10,00 m							28,00	27,8	2,78	43,75	27,8	2,78	62,97	27,8	2,78
12,00 m										47,88	33,3	3,33	68,93	33,3	3,33
14,00 m										51,69	38,8	3,88	74,42	38,8	3,88
16,00 m													79,52	44,3	4,43
18,00 m													84,32	49,8	4,98
20,00 m													88,86	55,3	5,53



Cascade Nozzles




TECHNICAL CHARACTERISTICS



MODEL	50 T / 161111	70 T / 161121	90 T / 161131	110 T / 161141	130 T / 161151
S Ø (mm)	50	70	96	117	147
R Ø (mm)	32 (1")	40 (1 1/2")	50 (2")	65 (2 1/2)	80 (3")
D Ø (mm)	74	90	117	130	150
e Ø (mm)	63	82	110	120	150
H (mm)	190	240	283	240	330
h (mm)	170	215	253		
W (mm)	20	25	30		
WEIGHT (Kg)					




Cascade Nozzles





Cascade Nozzles





Finger Nozzles - Bronze/Chrome plated

Made of bronze. Can be articulated up to 15°.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	161211	1	0,054	
Water spray dia. Ø6,0 mm				
• Finger (5-8T) 0,5 Male Threaded.	161221	1	0,086	
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	161222	1	0,080	
Water spray dia. Ø10 mm				
• Finger (10-12T) 1" Male Threaded.	161231	1	0,246	
Water spray dia. Ø12 mm				



Finger Nozzles - Bronze/Chrome plated - Adjustable

Chrome plated bronze. Can be articulated up to 15°. Flow adjusting valve over fountain.

Description	Code	Pieces/	Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	1612111	1	9	
Water spray dia. Ø6,0 mm	.0.2	·		
• Finger (5-8T) 0,5 Male Threaded.	1612211	1		
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	1612221	1		
Water spray dia. Ø10,0 mm				
• Finger (10-12T) 1" Male Threaded.	1612311	1		
Water spray dia. Ø12,0 mm				



Finger Nozzles - Plastic/Chrome Plated - Adjustable

Chrome plated plastic. Can be articulated up to 15°. Flow adjusting valve over fountain.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	161211PCR	1		
Water spray dia. Ø6,0 mm				
• Finger (5-8T) 0,5 Male Threaded.	161221PCR	1		
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	161222PCR	1		
Water spray dia. Ø10 mm				
• Finger (10-12T) 1" Male Threaded.	161231PCR	1		
Water spray dia. Ø12 mm				





Finger Nozzles - Plastic/Golden Plated - Adjustable

Made of plastic. Can be articulated up to 15°. (Please add unit prices for footed models)



Description	Code	Piece: box	s/ Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	161211PG	1		
Water spray dia. Ø6,0 mm				
• Finger (5-8T) 0,5 Male Threaded.	161221PG	1		
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	161222PG	1		
Water spray dia. Ø10 mm				
• Finger (10-12T) 1" Male Threaded.	161231PG	1		
Water spray dia. Ø12 mm				

Finger Nozzles - Plastic/Chrome Plated - Adjustable

Made of plastic. Can be articulated up to 15°.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	161211PC	1		
Water spray dia. Ø6,0 mm				
• Finger (5-8T) 0,5 Male Threaded.	161221PC	1		
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	161222PC	1		
Water spray dia. Ø10 mm				
• Finger (10-12T) 1" Male Threaded.	161231PC	1		
Water spray dia. Ø12 mm				

Finger Nozzles - Plastic/Black


Made of plastic. Can be articulated up to 15°.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Finger (3-6T) 3/8" Male Threaded.	161211P	1		
Water spray dia. Ø6,0 mm				
• Finger (5-8T) 0,5 Male Threaded.	161221P	1		
Water spray dia. Ø8 mm				
• Finger (5-10T) 0,5 Male Threaded.	161222P	1		
Water spray dia. Ø10 mm				
• Finger (10-12T) 1" Male Threaded.	161231P	1		
Water spray dia. Ø12 mm				



Finger Nozzles




Flow and Pressure Indicators According to Nozzles Squirt Height

Squirt	FINGER 3-6 T			FIN	FINGER 5-8 T		FINGER 5-10 T			FINGER 10-12 T		
Height	Flow m³/h	Pressure rem	quirement atm	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure re m / h	quirement atm
0,25 m	0,23	0,30	0,03	0,41	0,30	0,03	0,65	0,30	0,03			
0,50 m	0,33	0,60	0,06	0,59	0,60	0,06	0,92	0,60	0,06	1,32	0,60	0,06
0,75 m	0,40	0,90	0,09	0,72	0,90	0,09	1,13	0,90	0,09	1,63	0,90	0,09
1,00 m	0,47	1,20	0,12	0,84	1,20	0,12	1,31	1,20	0,12	1,89	1,20	0,12
1,25 m	0,53	1,51	0,15	0,94	1,51	0,15	1,47	1,51	0,15	2,12	1,51	0,15
1,50 m	0,58	1,81	0,18	1,04	1,81	0,18	1,62	1,81	0,18	2,33	1,81	0,18
2,00 m	0,68	2,42	0,24	1,21	2,42	0,24	1,88	2,42	0,24	2,72	2,42	0,24
2,50 m	0,76	3,03	0,30	1,36	3,03	0,30	2,13	3,03	0,30	3,06	3,03	0,30
3,00 m	0,84	3,64	0,36	1,50	3,64	0,36	2,35	3,64	0,36	3,38	3,64	0,36
4,00 m	0,99	4,88	0,49	1,76	4,88	0,49	2,76	4,88	0,49	3,97	4,88	0,49
5,00 m				2,00	6,12	0,61	3,13	6,12	0,61	4,51	6,12	0,61
6,00 m							3,48	7,37	0,74	5,01	7,37	0,74
8,00 m										5,96	9,91	0,99



Geiser Nozzles - Stainless Steel







Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Geiser (20T) - 1" Male threaded: Water	161311	1		
spray nozzle dia. Ø20 mm				
• Geiser (40T) - 1,5" Female threaded:	161321	1		
Water spray nozzle dia. Ø40 mm				
• Geiser (60T) - 2" Female threaded: Water	161331	1		
spray nozzle dia. Ø60 mm				
• Geiser (80T) - 2,5" Female threaded:	161341	1		
Water spray nozzle dia. Ø80 mm				
• Geiser (100T) - 3" Female threaded:	161351	1		
Water spray nozzle dia. Ø100 mm				











Geiser Nozzles - Bronze


Water-level dependant foam-effect nozzles, should be operated under water level. Completely made in bronze.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Geiser (20T) - 1" Male threaded: Water	16131	1	1,054	
spray nozzle dia. Ø20 mm				
• Geiser (40T) - 1,5" Female threaded:	16132	1	3,882	
Water spray nozzle dia. Ø40 mm				
• Geiser (60T) - 2" Female threaded: Water	r 16133	1	3,210	
spray nozzle dia. Ø60 mm				
• Geiser (80T) - 2,5" Female threaded:	16134	1	10,730	
Water spray nozzle dia. Ø80 mm				
Geiser (100T) - 3" Female threaded:	16135	1	15,200	
Water spray nozzle dia. Ø100 mm				



Geiser Nozzles





Flow and Pressure Indicators According to Nozzles Squirt Height

Squirt	GEIS	ER 20 T		GEIS	ER 40 T		GEIS	SER 60 T		GEIS	SER 80 T		GEIS	ER 100 T	
Height	Flow m³/h	Pressure re m / h	equirement atm	Flow m³/h	Pressure re	equirement atm	Flow m³/h	Pressure re m / h	equirement atm	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure r	equirement atm
0,50 m	1,83	1,9	0,19	4,05	1,8	0,18	7,90	2,2	0,22						
0,75 m	2,07	2,4	0,24	4,60	2,4	0,24	8,88	2,8	0,28						
1,00 m	2,28	3,0	0,30	5,08	2,9	0,29	9,78	3,4	0,34	15,62	3,5	0,35			
1,50 m	2,66	4,0	0,40	5,94	4,0	0,40	11,36	4,6	0,46	18,57	5,0	0,50			
2,00 m	3,00	5,1	0,51	6,68	5,0	0,50	12,74	5,8	0,58	21,10	6,5	0,65	31,14	6,8	0,68
2,50 m	3,29	6,2	0,62	7,35	6,1	0,61	13,98	6,9	0,69	23,37	7,9	0,79	34,00	8,1	0,81
3,00 m	3,57	7,2	0,72	7,97	7,1	0,71	15,12	8,1	0,81	25,44	9,4	0,94	36,62	9,4	0,94
4,00 m	4,06	9,4	0,94	9,08	9,2	0,92	17,19	10,5	1,05	29,13	12,3	1,23	41,39	12,0	1,20
5,00 m	4,50	11,5	1,15	10,06	11,3	1,13	19,03	12,8	1,28	32,41	15,2	1,52	45,66	14,6	1,46
6,00 m	4,90	13,6	1,36	10,96	13,5	1,35	20,70	15,2	1,52	35,38	18,2	1,82	49,56	17,2	1,72
8,00 m				12,56	17,7	1,77	23,70	19,9	1,99	40,68	24,0	2,40	56,52	22,4	2,24
10,00 m				13,98	21,9	2,19	26,37	24,6	2,46	45,37	29,9	2,99	62,79	27,6	2,76
12,50 m							29,36	30,5	3,05	50,62	37,2	3,72	69,80	34,1	3,41
15,00 m							32,07	36,4	3,64	<i>55,37</i>	44,5	4,45	76,16	40,6	4,06
17,50 m										<i>59,75</i>	51,8	5,18	82,04	47,1	4,71
20,00 m										63,83	59,1	5,91	87,51	53,6	5,36
25,00 m													97,55	66,6	6,66
30,00 m													106,65	79,6	7,96



Geiser Nozzles






TECHNICAL CHARACTERISTICS

MODEL	20 T / 161311	40 T / 161321	60 T / 161331	80 T / 161341	100 T / 161351
S Ø (mm)	23	45	60	80	100
R Ø (mm)	32 (1")	40 (1 1/2")	50 (2")	65(2,5")	80 (3")
D Ø (mm)	74	92	117	230	165
e Ø (mm)	61	81	107	120	150
H (mm)	207	277	325	250	330
h (mm)	176	217	246	240	310
W (mm)	31	60	80	10	20
WEIGHT (Kg)					




Geiser Nozzles





Geiser Nozzles





Water Fan Nozzle

"Water Fan Nozzle" Made of Stainless Steel.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Water Fan Nozzle (115 - 15T), 1"	161111	1	1,798	0,002
• Duck Mouth, 1"	161113	1		
• Duck Mouth, 1,5"	161114	1		



Finger Jet Nozzle

"Finger Water Fan Nozzle" Made of Stainless Steel. Distributes the water with 60° angle from $\emptyset4,0$ mm water jet. 1" male threaded connection.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Finger Water Fan (13 - 4T). 13 Mouth	1611121	1	2,814	0,003
• Finger Water Fan (25 - 4T). 25 Mouth	1611122	1	2,868	0,003
Big Type Finger Water Fan (6 - 8T)	1611123			



Volcano Nozzles

Creates a water pattern consisting of a series of jets which rise in one or more steps.

Description	Code	Piec bo	-	Veight Kg	Volume m ³
• Volcano (43 - 3T) 1"	16143P	1		-	-
Male threaded : Made in plastic.					
• Volcano (19 - 3T) 1"	16142	1		1,118	0,0008
Male threaded : Water spray hole dia.					
Ø3 mm x 19 pcs.					
 Volcano (43 - 3T) 1" 	16143	1		1,160	0,0008
Male threaded : Water spray hole dia.					
Ø3 mm x 43 pcs.					
• Volcano (200/19 - 6T) 2"	16144	1		4,154	0,0034
Male threaded : Consists of 1 x Ø10 mm	+				
18 x Ø6 mm finger nozzle					
Ditto, Made of golden plated plastic	16144P	1			
finger jets.					
 Volcano (300/19 - 8T) 2,5" Male 	16145	1		9,250	
threaded : Consists of 1 x Ø12 mm					
+ 18 x Ø8 mm finger nozzle					





Volcano 200/19 - 6 T



Volcano 300/19 - 8 T



Water Bell Nozzles





Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 30T : H= 30 cm 1" Male threaded.	161621	1	1,040	0,001
• 40T : Height = 40 cm 1" Male threaded.	161622	1	1,316	0,001
• 60T : H= 60 cm 1" Male threaded.	161523	1	1,538	0,002
• 30TP: H= 30 cm and can be extended.	16161P	1	0,148	0,001
0,5 Male threaded. Made in plastic.				



Water Sphere Nozzles



127 Arms made in stainless steel are fitted on the central bronze sphere. Stands on a stainless steel pivot.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Water Sphere Nozzle 1500, Ø1500 mm	161101	1		
• Water Sphere Nozzle 2500, Ø2500 mm	161102	1		
• Half a sphere of water 1500, Ø1500 mm	161103	1		
• Half a sphere of water 2500, Ø2500 mm	161104	1		

Valves for Nozzle Adjustment






 $\label{lem:chrome} \mbox{Chrome plated bronze. Female threaded nozzle side and male threaded pipe connection side.}$

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 0,5	16201	1		
• 0,75	16202	1		
• 1"	16203	1		
• 1,5"	16204	1		
• 2"	16205	1		

Nozzle Joint








Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 1" Plastic	16301			
• 1,5" Plastic	16302			
• 1" with Stainless Steel Nut	16303			
• 1,5" with Stainless Steel Nut	16304			



Water Bell Nozzles



Flow and Pressure Indicators According to Nozzles Squirt Height

Bell	WATI	ER BELL 30 T		WATER BELL 45 T			WATER BELL 60 T		
Diameter	Flow m³/h	Pressure re m / h	equirement atm	Flow m³/h			Flow m³/h	Pressure red m / h	quirement atm
0,15 m									
0,20 m									
0,30 m	2,10	1, 1	0,11						
0,40 m	2,58	1,3	0,13	2,58	1,4	0,14			
0,50 m	3,06	1,6	0,16	3,06	1,7	0,17	2,58		
0,60 m	3,54	2,0	0,20	3,54	2,1	0,21	3,06		
0,70 m	4,02	2,5	0,25	4,02	2,6	0,26	3,54		
0,90 m				4,50	3,2	0,32	4,02		
1,10 m							4,50	2,1	0,21
1,30 m							4,98	2,4	0,24
1,50 m								2,8	0,28



Water Star Nozzles



Made in bronze. O.D. Ø750 mm. Water spray nozzle Ø4 mm. Connection: 1,5"


Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 12 / K3 - 4 / 750T with 12 arms	16101	1		
• 18 / K3 - 4 / 750T with 18 arms	16102	1		
• 24 / K3 - 4 / 750T with 24 arms	16103	1		



Plastic Water Star. Made of 36 pieces of 3/8" plastic finger jets. Dia Ø1000 mm, water jet Ø4,0 mm, connection 1,5".

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Plastic Water Star Nozzle 1000	16104	1	4,184	0,106

Water Pirouette Nozzle



Made in bronze. Effect is created by rotation.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• (M7 - 5T) 0,5 Male threaded	16191		1,846	0,046
• (M7 - 10T) 1" Male threaded	16192	1		



Water Bell Nozzles








Flow and Pressure Indicators According to Nozzles Squirt Height

Consist	WATER STA	R 12/K3-4/	750 T	WATER STA	WATER STAR 18/K3-4/750 T			WATER STAR 24/K3-4/750 T		
Squirt Height				Flow m³/h	Pressure requirement m / h atm		Flow Pressure requiren m³/h m / h		quirement atm	
0,50 m	1,79	0,7	0,07	2,69	0,7	0,07	3,60	0,9	0,09	
0,75 m	2,22	1, 1	0,11	3,33	1, 1	0,11	4,47	1,4	0,14	
1,00 m	2,60	1,4	0,14	3,90	1,4	0,14	5,24	1,8	0,18	
1,25 m	2,94	1,8	0,18	4,40	1,8	0,18	5,93	2,3	0,23	
1,50 m	3,25	2,1	0,21	4,88	2,1	0,21	6,59	2,7	0,27	
1,75 m	3,55	2,5	0,25	5,32	2,5	0,25	7,20	3,2	0,32	
2,00 m	3,84	2,9	0,29	5,75	2,9	0,29	7,80	3,6	0,36	
2,50 m	4,11	3,2	0,32	6,17	3,2	0,32	8,36	4,1	0,41	
3,00 m	4,38	3,6	0,36	6,56	3,6	0,36	8,93	4,5	0,45	
3,50 m	4,89	4,3	0,43	7,33	4,3	0,43	10,00	5,4	0,54	
4,00 m	5,39	5,0	0,50	8,07	5,0	0,50	11,04	6,4	0,64	
4,50 m	5,86	5,8	0,58	8,79	5,8	0,58	12,05	7,3	0,73	



Spring Nozzles





Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Spring (35 - 10E) 1" Male threaded:	161521	1	0,684	0,0004
Water spray dia. Ø32 mm. Adjustable.				
• Spring (55 - 10E) 1" Male threaded:	161522	1	1,282	0,0008
Water spray dia. Ø50 mm. Adjustable.				
• Spring (55 - 15E) 1,5" Male threaded:	16153	1	1,306	0,0008
Water spray dia. Ø50 mm. Adjustable.				
• Spring (75 - 20T) 2" Male threaded:	16154	1	2,742	0,0020
Water spray dia, Ø75 mm. Adjustable.				












16154


TECHNICAL CHARACTERISTICS

MODEL	35 - 10E	55 - 10E	55 - 15E	75 - 20T
S Ø (mm)	50	72	72	80
R Ø (mm)	32 (1")	32 (1")	40 (1 1/2")	50 (2")
D Ø (mm)	58	79	79	100
e Ø (mm)	32,50	50	50	66
H (mm)	153	178	180	240
WEIGHT (Kg)				





Spring Nozzles




Flow and Pressure Indicators According to Nozzles Squirt Height

Squirt	SPRING 35-10 E		SPF	RING 55-10 E	Ŧ	SPR	ING 55-15 E		SPR	ING 75-20 T	•	
Height	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure re m / h	quirement atm	Flow m³/h	Pressure re m / h	quirement atm
0,25 m	2,33	0,7	0,07									
0,50 m	3,29	1,5	0,15	4,85	2,0	0,20	4,85	1,3	0,13	13,23	0,9	0,09
0,75 m	4,03	2,2	0,22	5,95	2,9	0,29	5,95	1,9	0,19	16,25	1,3	0,13
1,00 m	4,65	2,9	0,29	6,89	3,9	0,39	6,89	2,5	0,25	18,81	1,8	0,18
1,25 m	5,21	3,6	0,36	7,72	4,9	0,49	7,72	3,1	0,31	21,08	2,2	0,22
1,50 m	5,70	4,4	0,44	8,48	5,9	0,59	8,48	3,8	0,38	23,15	2,6	0,26
2,00 m	6,58	5,8	0,58	9,84	7,8	0,78	9,84	5,0	0,50	26,86	3,5	0,35
2,50 m				11,05	9,8	0,98	11,05	6,3	0,63	30,17	4,4	0,44
3,00 m							12,17	7,5	0,75	33,21	5,3	0,53
4,00 m							14,18	10,1	1,01	38,70	7,1	0,71
5,00 m							16,00	12,6	1,26	43,67	8,9	0,89
6,00 m							17,69	15,2	1,52	48,27	10,7	1,07



Spring Nozzles





Ornamental Pool and Accessories

Decorative Wall Nozzles

GEMAS Wall Nozzles. Made of polyester and the surface finish is made with various aging paints. Standart trims are antique copper, antique brass, antique silver and oxide. Special implementations can be made according to special demands.

Description	Code	F	Pieces/ box	Weight Kg	Volume m ³
Small Lionhead, Antique Copper	1122411		1		
Large Lionhead, Antique Copper	1122421		1		
Plain Bowl Waterfall, Antique Copper	1122431		1		
• Slotted Bowl Waterfall, Antique Copper	1122241		1		
Snail, Antique Copper	1122251		1		
Antique Badge, Antique Copper	1122261		1		

WALLSPRING DECORATIVE WALLACCENTS



Small Lionhead, Antique Copper



Large Lionhead, Antique Copper



Plain Bowl Waterfall





Plain Bowl Waterfall, Antique Copper



Slotted Bowl Waterfall, Antique Copper



Snail Antique Copper



Antique Badge



Submersible Pumps for Fountains.




Submersible Pumps for Fountains



High pressure - High Flow Submersible deepwell pumps: Such pumps with below technical spects are made of stainless steel (AISI 304) including its fan being capable of working long time by minimum maintenance thanks to the stainless steel pre-filter. All pumps are complete with a ball or butterfly valve suitable to their connection diameter. Low profile of pumps provide usage in shallow ornamental pools. Easy to be fixed to side nozzle collectors and nozzles saving significantly from laborious and expensive pipe installation. It's vitally important to take precautions in control panels of pumps against electric leakage. All pump models are manufactured upon customer's order. Delivery time is approximately 15 days. Please ask quotation for AISI 316 quality pumps.

TECHNICAL CHARACTERISTICS

Step	Stainless Steel (AISI 304), Optional (AISI 316)
Fan	Stainless Steel (AISI 304), Optional (AISI 316)
Pump shaft	X22 CrNi 17
Step rubber	Nitrile Rubber
Filter	Stainless Steel (AISI 304), Optional (AISI 316)
Pump suction adapter	Stainless Steel (AISI 304), Optional (AISI 316)
Pump Output Connection	Stainless Steel (AISI 304), Optional (AISI 316)
Throttle	Stainless Steel (AISI 304), Optional (AISI 316)
Max. Sand Amount	50 gr/m³
Max. departure p	20 (kal/s)
Frequency	50 Hz
Max. working noise	70 dB <
Class of motor protection	IP 68
Motor Body	Stainless Steel (AISI 304)
Max Water Temperature	40℃
Motor Rotation Direction	Anti-clockwise direction
Speed	2900 speed/min.



PUMP TYPE				DIN	IENSION	S (mm)				
	Ø D	L1	L2	L3	L4	L5	H1	H2	Н3	H4
GMD-CR14-E2/05	2"	435	500	183	470	1168	200	301	200	100
GMD-CR17-A1,5/02	2"	289	500	183	470	1022	200	301	200	100
GMD-CR30-B03/02	3"	405	500	264	470	1219	200	337	200	100
GMD-CR30-B04/03	3"	565	600	264	570	1379	200	337	200	100
GMD-CR30-B05/04	3"	530	700	264	670	1544	200	337	200	100
GMD-CR46-C04/02	4"	399	600	414	570	1463	200	350	200	100
GMD-CR46-C07/03	4"	540	600	414	570	1604	250	400	300	100
GMD-CR60-D03/01	4"	425	500	414	470	1289	200	350	200	100
GMD-CR77-E07/01	5"	482	600	380	570	1512	250	480	300	100
GMD-CR77-E10/02	5"	560	700	380	670	1690	250	480	300	100
GMD-CR135-G10/01-1	6"	536	700	408	670	1694	250	498	300	100
GMD-CR135-G10/01	6"	516	700	408	670	1674	250	498	300	100
GMD-CR135-G25/02-1	6"	712	900	408	870	2100	250	498	300	100




Submersible Pumps for Fountains


Submersible Pumps for Fountains

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• GMD-CR14-E2/05M - 2 HP Mono.	1631201M	1	20,000	
• GMD-CR14-E2/05 - 2 HP Tri.	1631201	1	18,000	
• GMD-CR17-A1,5/02 - 1,5 HP Tri.	1631211	1	17,100	
• GMD-CR30-B03/02 - 3 HP Tri.	1631224	1	21,600	
• GMD-CR30-B04/03 - 4 HP Tri.	1631225	1	26,400	
• GMD-CR30-B05/04 - 5,5 HP Tri.	1631223	1	30,800	



PERFORMANCE CURVES





	STEP	MO	TOR	ΑN	AMP						HEAD	mwh					
PUMP TYPE	NUMBER			l 11	Ш	4	6	8	10	12	14	16	17	18	20	21	23
		HP	KW	220 V							FLOV	/ m³/h					
GMD-CR14-E2/05	5	2	1,5	11,50	4,00	32,00	31,00	29,00	28,00	25,00	23,00	18,00	16,50	14,00	-	-	-
GMD-CR17-A1,5/02	2	1,5	1,1	-	3,00	-	-	19,80	18,00	16,20	14,40	13,50	12,60	10,80	9,00	7,20	-
GMD-CR30-B03/02	2	3	2,2	-	5,00	-	-	38,50	36,00	31,00	28,80	22,00	21,60	18,00	14,40	10,80	-

	STEP	MO	TOR	AM	IP					HEAD n	nwh				
PUMP TYPE	NUMBER			"	Ш	14	18	21	24	26	28	29	31	32	34
		HP	KW	220 V	380 V					FLOW n	n³/h				
GMD-CR30-B04/03	3	4	3		7,00	36,00	32,40	28,80	25,20	21,60	18,00	14,40	10,80	7,20	-

	STEP	MO.	TOR	AN.	ΛP					HEAD n	nwh				
PUMP TYPE	NUMBER			"	III	20	25	28	32	34	37	39	41	43	45
		HP	KW	220 V	380 V					FLOW n	n³/h				
GMD-CR30-B05/04	4	5,5	4		9,00	36,00	32,40	28,80	25,20	21,60	18,00	14,40	10,80	7,20	-

PUMP TYPE	MOTOR	VOLTAGE		DI	MENS	IONS (mn	1)		W	EIGHT (Kg)
101111111111111111111111111111111111111	TYPE	(V)	А	В	ØС	D	Е	ØF	Pump	Motor	Total Weight
GMD-CR14-E2/05M	G095MC/02-M	220	985	510	95	2" *11 diş	475	96	6,000	14,000	20,000
GMD-CR14-E2/05	G095MC/02-T	380	955	510	95	2" *11 diş	445	96	6,000	12,000	18,000
GMD-CR17-A1,5/02	G095MC/1,5-T	380	839	414	95	3" *11 diş	415	134	6,100	11,000	17,100
GMD-CR30-B03/02	G095MC/03-T	380	955	480	95	3" *11 diş	475	135	6,600	15,000	21,600
GMD-CR30-B04/03	G 095MC/04-T	380	1115	575	95	3" *11 diş	540	135	8,700	18,000	26,400
GMD-CR30-B05/04	G 095MC/05-T	380	1280	670	95	3" *11 diş	610	135	10,800	20,000	30,800


Submersible Pumps for Fountains.




Submersible Pumps for Fountains



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• GMD-CR46-C04/02 - 4 HP Tri.	1631231	1	25,150	
• GMD-CR60-D03/01 - 3 HP Tri.	1631241	1	53,500	
• GMD-CR77-E07/01 - 7,5 HP Tri.	1631251	1	21,200	
• GMD-CR46-C07/03 - 7,5 HP Tri.	1631232	1	61,000	
• GMD-CR77-E10/02 - 10 HP Tri.	1631252	1	70,000	





	STEP	MO ⁻	TOR	AN	ЛP						HEAD	mwh					
PUMP TYPE	NUMBER			,,	III	4	5	9	10	12	15	16	18	19	20	22	25
		HP	KW	220 V							FLOV	/ m³/h					
GMD-CR46-C04/02	2	4	3	-	5,00	-	-	54,00	52,00	48,00	43,20	39,60	36,00	26,00	28,80	18,00	-
GMD-CR60-D03/01	1	3	2,2	-	5,80	64,80	61,20	46,80	43,20	18,00	-	-	-	-	-	-	-
GMD-CR77-E07/01	1	7,5	5,5	-	12,00	-	79,20	68,40	62,00	61,20	54,00	36,00	24,00	18,00	-	-	-

	STEP	MO.	TOR	ΑN	1P				HE	AD mwh				
PUMP TYPE	NUMBER			l 11	III	17	24	27	30	33	36	40	45	48
		HP	KW	220 V	380 V				FLO	OW m³/h				
GMD-CR46-C07/03	3	7,5	5,5		7,00	54,00	50,50	46,80	43,20	39,60	36,00	28,80	18,00	-

	STEP	МОТ	ΓOR	A۸	ЛP					HEAD n	ıwh				
PUMP TYPE	NUMBER			l 11	III	23	27	28	29	30	33	35	42	44	47
		HP	KW	220 V	380 V					FLOW n	n³/h				
GMD-CR77-E10/02	2	10,00	7,5		18,00	79,20	72,00	68,40	64,80	61,20	57,60	54,00	36,00	18,00	-

DUMD TVDE	MOTOR	VOLTAGE		DI	MENS	IONS (mn	1)		W	EIGHT (Kg)
	TYPE	(V)	Α	В	ØС	D	Е	ØF	Pump	Motor	Total Weight
GMD-CR46-C04/02	G 095MC/04	380	1049	509	95	3"-4" *11 diş	540	145	8,650	16,500	25,150
GMD-CR46-C07/03	G 145MC/07	380	1190	620	145	3"-4" *11 diş	570	145	11,500	42,000	53,500
GMD-CR60-D03/01	G0 95MC/03-T	380	875	400	95	2"-4" *11 diş	475	145	6,200	15,000	21,200
GMD-CR77-E07/01	G 145MC/07	380	1132	562	145	5" *11 diş	570	171	19,000	42,000	61,000
GMD-CR77-E10/02	G 145MC/10	380	1310	690	145	5" *11 diş	620	171	23,000	47,000	70,000




Submersible Pumps for Fountains


Submersible Pumps for Fountains

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• GMD-CR135-G10/01-1 -10 HP Tri.	1631261	1	78,000	
• GMD-CR135-G15/01-15 HP Tri.	1631262	1	89,000	
• GMD-CR135-G25/02-1 -25 HP Tri.	1631263	1 1	14,000	



PERFORMANCE CURVES





	STEP MOTOR		AMP		HEAD mwh									
PUMP TYPE	NUMBER			l 11	Ш	7	8	13	16	17	18	19	23	24
		HP	KW	220 V	380 V				FLO	OW m³/h				
GMD-CR135-G10/01-1	1	10	7,5		16,00	151,2	144,0	126,0	108,0	90,0	72,0	54,0	36,0	-

	STEP MOTOR		AMP		HEAD mwh									
PUMP TYPE	NUMBER	UMBER				11	17	20	22	24	27	28	36	39
		HP	KW	220 V	380 V				FLO	OW m³/h				
GMD-CR135-G10/01	1	15	11		23,50	151,2	144,0	126,0	108,0	90,0	72,0	54.0	36,0	-

	STEP	MOTOR		IOTOR AMP		HEAD mwh								
PUMP TYPE	NUMBER					21	26	32	39	43	47	50	58	59
		HP	KW	220 V	380 V				FL(OW m³/h				
GMD-CR135-G25/02-1	2	25	18,5		40	151,2	144,0	126,0	108,0	90,0	72,0	54,0	36,0	-

PUMP TYPE	MOTOR TYPE	VOLTAGE		DI	MENS	SIONS (mm		WEIGHT (Kg)				
		(V)	А	В	ØС	D	Е	ØF	Pump	Motor	Total Weight	
	GMD-CR135-G10/01-1	G 145MC/10	380	1286	666	145	6" *11 diş	620	210	31,000	47,000	78,000
	GMD-CR135-G15/01	G 145MC/15	380	1366	666	145	6" *11 diş	700	210	31,000	58,000	89,000
	GMD-CR135-G25/02-1	G 145MC/25	380	1692	822	145	6" *11 diş	870	210	38,000	76,000	114,000



Plastic Body-Footed or Staked-Underwater/Landscape Lights



"Spot 14" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or stake type. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - Footed - 24 W	1651140	1		
• 72 LED Daylight - Footed - 24 W	1651141	1		
• 72 LED Turquoise - Footed - 20 W	1651142	1		
• 72 LED Blue - Footed - 20 W	1651145	1		
• 72 LED Red - Footed - 20 W	1651144	1		
• 72 LED Green - Footed - 20 W	1651143	1		
• 72 LED White - Staked - 24 W	1651140K	1		
• 72 LED Daylight - Staked - 24 W	1651141K	1		
• 72 LED Turquoise - Staked - 20 W	1651142K	1		
• 72 LED Blue - Staked - 20 W	1651143K	1		
• 72 LED Red - Staked - 20 W	1651144K	1		
• 72 LED Green - Staked - 20 W	1651145K	1		



"Spot 14" Fountain Underwater Light, RGB Color

Designed for fountains and landscape lighting. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On-Off or remote control. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ \ box	Neight Kg	Volume m ³
• 72 LED RGB - Built-in Control - Footed - 20 W	1651150	1		
• 72 LED RGB - Centrally Control - Footed - 20 W	1651151	1		
• 72 LED RGB - Built-in Control - Staked - 20 W	1651150K	1		
• 72 LED RGB - Centrally Control - Staked - 20 W	1651151K	1		



St. Steel Body-Footed or Staked-Underwater/Landscape Lights

"Spot 14" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. 120° - IP68. The product is patented.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - Footed - 24 W	1651140S	1		
• 72 LED Daylight - Footed - 24 W	1651141S	1		
• 72 LED Turquoise - Footed - 20 W	1651142S	1		
• 72 LED Blue - Footed - 20 W	1651143S	1		
• 72 LED Red - Footed - 20 W	1651144S	1		
• 72 LED Green - Footed - 20 W	1651145S	1		
• 72 LED White - Staked - 24 W	1651140KS	1		
• 72 LED Daylight - Staked - 24 W	1651141KS	1		
• 72 LED Turquoise - Staked - 20 W	1651142KS	1		
• 72 LED Blue - Staked - 20 W	1651143KS	1		
• 72 LED Red - Staked - 20 W	1651144KS	1		
• 72 LED Green - Staked - 20 W	1651145KS	1		





Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

"Spot 14" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program with On-Off or remote control. 120° - IP68. **The product is patented**.

Description	Code	Pieces/ W box	/eight Vol Kg r	lume m³
• 72 LED RGB - Built-in - Footed - 20 W	1651150S	1		
• 72 LED RGB - Central Integrated-Footed - 20 W	1651151S	1		
• 72 LED RGB - Built-in - Staked - 20 W	1651150KS	1		
• 72 LED RGB - Central Integrated-Staked - 20 W	1651151KS	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.



Plastic Body-Footed or Staked-Underwater/Landscape Lights





Designed for fountains and landscape lighting. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or stake type. 120° - IP68. **The product is patented**.




Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - Footed - 11 W	1651160	1		
• 72 LED Daylight - Footed - 11 W	1651161	1		
• 72 LED Turquoise - Footed - 8 W	1651162	1		
• 72 LED Blue - Footed - 8 W	1651163	1		
• 72 LED Red - Footed - 8 W	1651164	1		
• 72 LED Green - Footed - 8 W	1651165	1		
• 72 LED White - Staked - 11 W	1651160K	1		
• 72 LED Daylight - Staked - 11 W	1651161K	1		
• 72 LED Turquoise - Staked - 8 W	1651162K	1		
• 72 LED Blue - Staked - 8 W	1651163K	1		
• 72 LED Red - Staked - 8 W	1651164K	1		
• 72 LED Green - Staked - 8 W	1651165K	1		

"Spot 10" Fountain Underwater Light, RGB Color

Designed for fountains and landscape lighting. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On-Off or remote control. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ V box	Veight Kg	Volume m ³
• 72 LED RGB - Built-in Control - Footed - 8 W	1651170	1		
• 72 LED RGB - Centrally Control - Footed - 8 W	1651171	1		
• 72 LED RGB - Built-in Control - Staked - 8 W	1651170K	1		
• 72 LED RGB - Centrally Control - Staked - 8 W	1651171K	1		







St. Steel Body-Footed or Staked-Underwater/Landscape Lights

"Spot 10" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. 120° - IP68. The product is patented.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 72 LED White - Footed - 11 W	1651160S	1		
• 72 LED Daylight - Footed - 11 W	1651161S	1		
• 72 LED Turquoise - Footed - 8 W	1651162S	1		
• 72 LED Blue - Footed - 8 W	1651163S	1		
• 72 LED Red - Footed - 8 W	1651164S	1		
• 72 LED Green - Footed - 8 W	1651165S	1		
• 72 LED White - Staked - 11 W	1651160KS	1		
• 72 LED Daylight - Staked - 11 W	1651161KS	1		
• 72 LED Turquoise - Staked - 8 W	1651162KS	1		
• 72 LED Blue - Staked - 8 W	1651163KS	1		
• 72 LED Red - Staked - 8 W	1651164KS	1		
• 72 LED Green - Staked - 8 W	1651165KS	1		






Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

"Spot 10" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality. 72 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On-Off or remote control. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ \ box	Neight Kg	Volume m ³
• 72 LED RGB - Built-in Control - Footed - 8 W	1651170S	1		
• 72 LED RGB - Centrally Control - Footed - 8 W	1651171S	1		
• 72 LED RGB - Built-in Control - Staked - 8 W	1651170KS	1		
• 72 LED RGB - Centrally Control - Staked - 8 W	1651171KS	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.





Plastic Body-Footed or Staked-Underwater/Landscape Lights

"Spot 11" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. 36 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. 120° - IP68. **The product is patented.**



Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - Footed - 7 W	1651180	1		
• 36 LED Daylight - Footed - 7 W	1651181	1		
• 36 LED Turquoise - Footed - 5 W	1651182	1		
• 36 LED Blue - Footed - 5 W	1651183	1		
• 36 LED Red - Footed - 5 W	1651184	1		
• 36 LED Green - Footed - 5 W	1651185	1		
• 36 LED White - Staked - 7 W	1651180K	1		
• 36 LED Daylight - Staked - 7 W	1651181K	1		
• 36 LED Turquoise - Staked - 5 W	1651182K	1		
• 36 LED Blue - Staked - 5 W	1651183K	1		
• 36 LED Red - Staked - 5 W	1651184K	1		
• 36 LED Green - Staked - 5 W	1651185K	1		





"Spot 11" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. 36 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On- Off or remote control. 120 $^{\circ}$ - IP68. The product is patented.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED RGB - Built-in Control - Footed - 5 W	1651190	1		
• 36 LED RGB - Centrally Control - Footed - 5 W	1651191	1		
• 36 LED RGB - Built-in Control - Staked - 5 W	1651190K	1		
• 36 LED RGB - Centrally Control - Staked - 5 W	1651191K	1		














St. Steel Body-Footed or Staked-Underwater/Landscape Lights

"Spot 11" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality. 36 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED White - Footed - 7 W	1651180S	1		
• 36 LED Daylight - Footed - 7 W	1651181S	1		
• 36 LED Turquoise - Footed - 5 W	1651182S	1		
• 36 LED Blue - Footed - 5 W	1651183S	1		
• 36 LED Red - Footed - 5 W	1651184S	1		
• 36 LED Green - Footed - 5 W	1651185S	1		
• 36 LED White - Staked - 7 W	1651180KS	1		
• 36 LED Daylight - Staked - 7 W	1651181KS	1		
• 36 LED Turquoise - Staked - 5 W	1651182KS	1		
• 36 LED Blue - Staked 5 W	1651183KS	1		
• 36 LED Red - Staked - 5 W	1651184KS	1		
• 36 LED Green - Staked - 5 W	1651185KS	1		








"Spot 11" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. Stainless steel frame. AISI 304 quality.36 SMD LEDs; complete with polycarbonate bulb body, PCB and 1.0 m long 2 x 0.75 cable. Mounting foot or Staked type. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On-Off or remote control. 120° - IP68. **The product is patented.**

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 LED RGB - Built-in Control - Footed - 5 W	1651190S	1		
• 36 LED RGB - Centrally Control - Footed - 5 W	1651191S	1		
• 36 LED RGB - Built-in Control - Staked - 5 W	1651190KS	1		
• 36 LED RGB - Centrally Control - Staked - 5 W	1651191KS	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.





St. Steel Body -St. Steel Footed Underwater Lights



Stainless Steel Foot

"SPOT 12" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. Stainless steel lamp body with 3 Power LEDs; It is complete with 1.0 m long 2 x 0.75 cable. Light beam angle is 30°. The lamp complies with IP68 degree of protection at a nominal depth of 2 m.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 3 Power LED White - AISI 304 - 9 W	16631SF	1		
• 3 Power LED Daylight - AISI 304 - 9 W	16633SF	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: For models with plastic foot, add "PF" next to the existing code i.e. 16631PF Ps: For models with spike, add "K" next to the existing code i.e. 16631K



"SPOT 12" with Plastic Foot

"SPOT 12" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. Stainless steel lamp body with 3 Power LEDs; It is complete with 1.0 m long 2 x 0.75 cable.RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Light beam angle is 30°. The lamp complies with IP68 degree of protection at a nominal depth of 2 m.

Description	Code	Pieces/ box	Weight Kg
• 3 Power LED RGB - Built-in Control - AISI 304 - 6 W	16635SF	1	
• 3 Power LED RGB - Centrally Control - AISI 304 - 6 W	16636SF	1	

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: For models with plastic foot, add "PF" next to the existing code i.e. 16635PF

Ps: For models with spike, add "K" next to the existing code i.e. 16635K



"SPOT 12" with Spike

"SPOT 12" Underwater Ornamental Light Foots

Description	Code	Pieces/ box	Weight Kg	Volume m³
• AISI 304 Quality Lamp Foot + Body Connection Set	1663003	1		
• AISI 316 Quality Lamp Foot + Body Connection Set	1663002	1		



St. Steel Body -St. Steel Footed Underwater Lights

"SPOT 13" Underwater Ornamental Light, Single Color

Designed for fountains and landscape lighting. Stainless steel lamp body with 6 Power LEDs; It is complete with 1.0 m long 2 x 0.75 cable. Light beam angle is 30°. The lamp complies with IP68 degree of protection at a nominal depth of 2 m.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 6 Power LED White - AISI 304 - 15 W	16651SF	1		
• 6 Power LED Daylight - AISI 304 - 15 W	16653SF	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: For models with plastic foot, add "PF" next to the existing code i.e. 16651PF **Ps:** For models with spike, add "K" next to the existing code i.e. 16651K



Stainless Steel Foot

"SPOT 13" Underwater Ornamental Light, RGB Color

Designed for fountains and landscape lighting. Stainless steel lamp body with 6 Power LEDs; It is complete with 1.0 m long 2 x 0.75 cable. RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Light beam angle is 30°. The lamp complies with IP68 degree of protection at a nominal depth of 2 m.

Description	Code	Pieces/ box	Weight Kg
• 6 Power LED RGB - Built-in Control - AISI 304 - 13 W	16655SF	1	
6 Power LED RGB - Centrally Control - AISI 304 - 13 W	16656SF	1	

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: For models with plastic foot, add "PF" next to the existing code i.e. 16655PF

Ps: For models with spike, add "K" next to the existing code i.e. 16655K



"SPOT 13" with Plastic Foot

"SPOT 13" Underwater Ornamental Light Foots

Description	Code	Pieces/ box	Weight Kg	Volume m³
• AISI 304 Quality Lamp Foot + Body Connection Set	1665002	1		
• AISI 316 Quality Lamp Foot + Body Connection Set	1665002SS	1		



"SPOT 13" with Spike



Massive Stainless Steel Body - Underwater Lights

Underwater Light Stainless Steel Body Single Color
Made of AISI 304 quality stainless steel. Pipe type. Complete with special transparent resin filled, epoxy PCB and 1 m long 2 x 1.5 cable. The light is mounted inside a 32 mm, 40mm, 50 mm or 63 mm PN10 pipe with a tight fit. 2 years sealing guarantee. "01" should be added next to AISI 316 Stainless Steel codes. Prices should be considered with a 20% increase.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
Microchrome for Ø32 mm pipe housing				
• 3 LED White - 4 W	16670	1		
• 3 LED Daylight - 4 W	16671	1		
Mini Chrome for Ø40 mm pipe housing				
• 3 LED White - 4 W	16680	1		
• 3 LED Daylight - 4 W	16681	1		
Midi Chrome for Ø50 mm pipe housing				
• 6 LED White - 6 W	16690	1		
• 6 LED Daylight - 6 W	16691	1		
Maxi Chrome for Ø63 mm pipe housing				
• 6 LED White - 6 W	16760	1		
• 6 LED Daylight - 6 W	16761	1		



Underwater Light Stainless Steel Body RGB

Description

RGB 13 different light patterns for built-in models, RGB 16 light patterns for central integrated models. Switch from program to program with On- Off or remote control.

Pieces/

Weight

Volume



Description	Code	box	Κğ	m^3
Microchrome for Ø32 mm pipe housing				
• 3 LED RGB - Centrally Control - 4 W	16677	1		
		1		
Mini Chrome for Ø40 mm pipe housing				
• 3 LED RGB - Built-in Control - 4 W	16686	1		
• 3 LED RGB - Centrally Control - 4 W	16687	1		
Midi Chrome for Ø50 mm pipe housing				
• 6 LED RGB - Built-in Control - 6 W	16696	1		
6 LED RGB - Centrally Control - 6 W	16697	1		
Maxi Chrome for Ø63 mm pipe housing				
• 6 LED RGB - Built-in Control - 6 W	16766	1		
6 LED RGB - Centrally Control - 6 W	16767	1		





Plastic Body - Footed Underwater Lights

"SPOT 02"

50 W/12 V refractory exclusive plastic body, footed fountain light.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Single Cable Union. Outlet at back.	05022	4		
• Ditto, Stainless Steel Frame	05022C	4		



"SPOT 02"

Spot 02 with 36 SMD RGB LED bulb, plastic body, footed fountain light. Central PCB.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 36 SMD LED White - 7 W	160220	4		
• 36 SMD LED Daylight - 7 W	160223	4		
• 36 SMD LED RGB - Centrally Control - 6 W	160221	4		
• 36 SMD LED RGB - Built-in Control - 6 W	160222	4		




Ps: Regarding control panel and other options of RGB LED fountain lights, please see Section 5; "Mini LED Bulbs" **Ps:** If 316 Stainless Steel Frame of the above lamps is requested, the code "C" should be added next to the existing code.



Stainless Steel Body - Footed Underwater Lights



"SPOT 06" Rainbow RGB Power LED bulb, AISI 304 quality stainless steel body, plastic footed fountain light. Single cable union. Outlet at back. Central control. With 1 m Cable.



Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: Please ask code and price for single color white or daylight.



"SPOT 07" Rainbow RGB Power LED bulb, AISI 304 quality stainless steel body, plastic footed fountain light. Single cable union. Outlet at back. With 1 m Cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Rainbow 9, 9 Power LED - Built-in Control	16457	1		
• Rainbow 9, 9 Power LED - Centrally Control	16458	1		
• Rainbow 18, 18 Power LED - Built-in Control	164367	1		
• Rainbow 18, 18 Power LED - Centrally Control	164368			
• Rainbow 27, 27 Power LED - Built-in Control	16467			
• Rainbow 27, 27 Power LED - Centrally Control	16468			
Stainless Steel Foot is Optional				

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: Please ask code and price for single color white or daylight.

Stainless Steel Body -Underwater Lights with Fountain Nozzles



"SPOT 05" Underwater light to be coupled with fountain nozzles. 304 quality stainless steel body and single union. 15° light angle with Power LED. Different Adaptors are used for different size nozzles (for exp. 1", 1,5", 2"). For this reason nozzles diameter should be mentioned during the order. (Nozzles are NOT included to the price). 13 different light models are avaliable. With 1 m Cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 18 Power LED-Built-in Control	165327	1		
• 18 Power LED-Centrally Control	165328	1		

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.

Ps: Please ask code and price for single color white or daylight.



"SPOT 06-K" Underwater light coupled with Finger fountain nozzle. 304 quality stainless steel body and single union. Nozzle (Ø10 mm) bottom connection is with swivel system and regulation valve (1"). 15° light angle with Power LED. 13 different light models are avaliable and are controled by a Central Control Panel. With 1 m Cable.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 6 Power LED, 1"- Built-in Control	16432F17	1		
• 6 Power LED, 1"- Centrally Control	16432F18	1		
• 9 Power LED, 1"- Built-in Control	16432F27	1		
• 9 Power LED, 1"- Centrally Control	16432F28	1		

Ps: 1- Regarding control panel and other options of RGB LED fountain light, please have a look at relevant section to "RGB LED Bulbs Control Panels"

2- All the lights mentioned above can be 1,5 and 2 m cable length. Please ask price.

Ps: Please ask code and price for single color white or daylight.

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.



Stainless Steel Body -**Underwater Lights for Fountains**

"SPOT 09-K"

Underwater light combined with fountain nozzles. 304 quality stainless steel body and single union. Also nozzle (Ø10 mm) bottom connection is with swivel system and regulation valve (0,5 or 1"). 15° light angle with Power LED. 13 different light models are available. With 1 m cable.

Code	Pieces/ box	Weight Kg	Volume m ³
16433F27	1		
16433F28	1		
	16433F27	16433F27 1	Code box Kg 16433F27 1



2- All the lights mentioned above can be 1,5 and 2 m cable length. Please ask price.

Ps: Please ask code and price for single color white or daylight.

Ps: If AISI 316 of the above lamps is requested, the code "01" should be added next to the existing code. Prices should be considered with a 20% increase.



Stainless Steel Pool Light Foots

Adjustable for all type stainless steel body underwater lights.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Single	16431Y015	1		
• Double	16431Y025	1		



Dry Pool Systems

Dry surface fountain desgined on a bunker walking floor grade made out concrete or polyester and dimensions light combinations 304 quality stainless steel. Dismountable cover and frame. Light housings are designed for SPOT 6. Fountain port is for fountains max. 2". Different designs can be done according to demand.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 300 x 300 mm	16433DF1	1		
• 400 x 400 mm	16433DF2	1		
• 500 x 500 mm	16433DF3	1		



- relevant section (5th) to "RGB LED Bulbs Control Panels"
 - 2- All the lights mentioned above can be produced "Double Union" according to demand. And can be connected serial.
 - 3- All the lights mentioned above can be 1,5 and 2 m cable length. Please ask price.







Concrete and Liner Pool Construction Materials



Volume

Skimmer Liner Pool Ladders

Description

• I: 227 cm w: 152 cm h: 151,5 cm

• I: 184 cm w: 106 cm h: 104,5 cm

system can be mounted.

· Ladder with massage chair

For rectengular pools.

For oval pools. Massage or counter current

GEMAS Embedded Liner Pool Ladder. Made of FR polyester and reinforced with wood. Complete with Connection Flange and PVC concealing flange. Anti-slip steps. Pieces/ Weight

Code

17401

17402

17403



17401



17402





17403





- 2 x Massage Station
- 1 x Counter current



box

1

1



- · Ladder with massage chair
- · Composite Deck

PVC Liner Repair Kit

Liner Repair Kit. 30 ml. Can be used for underwater repairs.



Description	Code	Pieces/ box	Weight Kg	Volume m ³
	17211		0,116	



Concrete and Liner Pool Construction Materials

In-Pool Insulation Materials

GEMAS In-Pool Isolation Material. Used for leak proofing in swimming pools and fountains. Fully elastic, UV filtered, cement added, two-compound waterproofing.

Description Cod	le Pieces/	Weight Kg	Volume m ³
• Gemas PL207, 10 kg Liquid + 20 kg Powder - Gray 173	10 1	30,000	
• Gemas PL207, 10 kg Liquid + 20 kg Powder - White 173	11 1	30,000	





GEMAS Joint Tape and Adhesive. Used for closing static capillary cracks and joins between the pool wall and floor. Tape size 0.20 x 100 m. Prices are per roll. Adhesive average consumption 1.65 - 2.75 kg/m²

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Gemas Joint Tape	17312	4		
Gemas PL05N-01 Adhesive, 10 kg	17313	1	10,000	
Gemas PL05N-01 Adhesive, 20 kg	17314	1	20,000	

GEMAS Concrete Waterproofing Primer. Used as primer before painting on reinforced concrete and screed. Average consumption is 8000 - 1000 gr/m².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Gemas PL302, 20 kg Liquid + 6 kg Powder	17315	1	26,000	

GEMAS Shock Water Breaker Concrete Admixture. Used for stopping pressurized water leaking. Consumption changes according to the surface condition, application thickness, loss such as spillage and cavity filling against water leaks. It is recommended to make trial mixes for optimum mixing ratio, workability and setting time. For wet system shotcrete, it is recommended to use between 3% and 6% of the weight of the binder for 20 cm thick layers.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Gemas BK03, 1 kg	17316	1	1,000	
• Gemas BK03, 5 kg	17317	1	5,000	

GEMAS Pool Paint. Used in natural swimming pools, fountains, thermal pools (up to max. 70° temperatures), fish breeding pools, drinking water tanks, ponds, dams, water channels, water tanks. Consumption varies according to surface condition, application thickness, spillage and void conditions. 200 gr/m² on the first floor, 200 gr/m² on the second floor. On reinforced concrete surfaces, waterproofing is applied after the primer coat.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Gemas Pool Paint, 20 kg	17318	1	20,000	

Pool Paints




Concrete and Liner Pool Construction Materials.



Porcelain Pool Handle and Antislip









Description	Code	Pieces/ box	Weight Kg	Volume m ³
• 12,2 x 24,5 x 2 cm Handle	1711AP			
• 12,2 x 24,5 x 0,9 cm Antislip	1712AP			
• 24,5 x 24,5 x 2 cm Square Handle	1714P			
• 12 x 12 cm Handle Internal Corner	1711CI1			
• 24,5 x 24,5 cm Square Handle	17141			
• 24,5 x 24,5 cm Handle Internal Corner	1714CI1			
• 12 x 12 x 0,9 cm Antislip Internal Corner	1711C01			
• 12 x 12 cm Handle External Corner	1714			
• 24,5 x 24,5 cm Handle External Corner	1714C01			
• 12 x 12 x 0,9 cm Antislip External Corner	1712C01			













Porcelain Pool Handle and Antislip - Striped Design



Description	Code	Pieces/ Weight Volume box Kg m³
• 12,2 x 24,5 x 2 cm Handle	1711A	11,050 0,008
• 12,2 x 24,5 x 1,5 cm Antislip	1712	12,840 0,008
• 12,2 x 24,5 x 0,8 cm Stair-Step Antislip	1713	12,696 0,007
• 12,2 x 24,5 x 0,8 cm Antislip	1712A	9,346 0,007
• 24,5 x 24,5 x 2 cm Square Handle	1714	
• 24,5 x 24,5 x 0,8 cm Square Antislip	1715	
Handle Internal Corner (for 1711)	1711CI	11,376 0,008
Handle External Corner (for 1711)	1711CO	11,376 0,008
Antislip Internal Corner (for 1712)	1712CI	10,100 0,008
Antislip External Corner (for 1712)	1712CO	10,100 0,008
Handle Internal Corner (for 1714)	1714CI	
Handle External Corner (for 1714)	1714CO	
Antislip Corner (for 1715)	1715C	



1713 - 1712A



1714 - 1715



1711CO - 1712CO



Concrete and Liner Pool Construction Materials

Glass Mosaics

GEMAS GLASS MOSAICS.

Description	Code	Pieces/ Weight Volume box Kg m ³
• KSMS-01 Sprayed Turquoise 38 x 38 cm	17062	
• KSMS-01 Sprayed Blue 38 x 38 cm	17061	
• KSMS-01 Sprayed Turquoise 25 x 25 cm	17041	
KSMS-02 Sprayed Blue 25 x 25 cm	17031	
• MIX-13 Mix Blue 25 x 25 cm	17011	
• MIX-15 Mix Blue + White 25 x 25 cm	17051	





38 x 38 KSMS-01

38 x 38 KSMS-02









Leakproofing Meterials

"Fix a leak" leakproofing chemical. Prevents leakage on the body or mechanical installation of filled pools. No matter what construction material of pool or massage pool is, it can be used successfully with installation materials such as PVC, ABS, poly plastics, copper, steel etc. A single bottle of "fix a leak" is efficient per 100 m³ pool. Minimum volume of water that a full bottle can be implemented is 2 m³. If a more concentrated implementation is required, pool should be drained after the implementation process. Please request usage instructions for further details.







Concrete and Liner Pool Construction Materials.




PVC Membrane Pool Coating

Imported Coating Membrane: 1,5 mm and 2 mm wall thickness. Manufactured of laminated double layer PVC film and fortified with polyester mesh. Can be implemented in every type of pools by using equipments of a liner pool. Sold per 25 m roll. Price per m².

Description	Code	Pieces/ box	Weight Kg	Volume m ³
Blue - Width: 1.8x25m Thickness: 1.5mm	17201			
Blue Non-Slip - Width: 1.8x25m Thickness: 1.5mm	17202			
Roma Mosaic - Width: 1.8x25m Thickness: 1.5mm	17203			
• Roma Mosaic Non-Slip - Width: 1.8x25m Thickness: 1.5mm	17204			
Sapphire - Width: 1.8x25m Thickness: 1.5mm	17205			
Sapphire Non-Slip - Width: 1.8x25m Thickness: 1.5mm	17206			
Blue 3D Mosaic Width: 1.8x25m Thickness: 2mm	17207			

PS: Colour of below pictures may differ from the original products.





Concrete and Liner Pool Construction Materials

PVC Membrane Pool Coating


PVC laminated Stainless sheet. PVC laminated Stainless sheet with dimensions of 2 x 1 m. Used as a detection strip in PVC membrane covered pools.

Description	Code	Pieces/ Weigh box Kg	nt Volume m ³
Blue - price per piece	17214	1	
 PVC special conduit side profile (m) 	03752		











Overflow Detailed

Liquid PVC - 1 I.

Description	Code	Pieces/ box	Weight Kg	Volume m ³
• Light blue 8272	17212	1		
• Blue 8273	17213	1		











Quality Policy

GEMAS Genel Muhendislik Mekanik Sanayi ve Ticaret A.S. targets to be a universally well known

company in its sector. In order to achieve that

Gemas embraces:

- Constant increase in customer satisfaction.
- Continuous development in production technology and efficiency.
- Continuous progress in all activities as the main principles of the company.

Genel Manager İbrahim ÜSTÜNES

Date of Issue: 30.03.2005



Safe Swimming Pleasure!

All over your pool; from construction materials to installation, from lighting to filtration, from disinfection to heating, from cleaning to massage equipment - shortly, we are in your pool, outside, and in the engine room! You can trust us.

Polyester Laminated/Bobbin Wound and Plastic Body Sand Filters ➤ Self-priming Pool Pumps ➤ Multiport valves ➤ PVC Fittings ➤ Skimmers ➤ Underwater Lights ➤ Transformers ➤ Pool Ladders ➤ Diving Boards ➤ Automatic Disinfection Systems ➤ Salt-Water Chlorinators ➤ Return Inlets ➤ Main Drains ➤ Overflow Gratings ➤ Automatic Pool Cleaners and Accessories ➤ Olympic Pool Accessories ➤ Plastic Valves and Fittings ➤ Pool Chemicals ➤ Heaters ➤ Fountain Nozzles ➤ Stropool Fast Pool Systems.



GEMPAŞ PAZARLAMA LOJISTIK TICARET ANONIM ŞIRKETI

Headquarters: İTOB OSB Mah. İTOB Atatürk Cad. No:33 35477, Menderes/İzmir-TÜRKİYE

Tel:+90 232 799 0215 pbx Fax:+90 232 799 0245 E-mail:info@gemas.com.tr

Istanbul Branch Office: Ayazağa Mah. Çakırlar Sk. No:19 34396, Sarıyer/İstanbul-TÜRKİYE

Tel:+90 212 360 0693 - 360 0753 - 321 9332 - 294 7894 Fax:+90 212 321 9583

Antalya Branch Office: Varsak Karşıyaka Mah. Süleyman Demirel Bul. No:220 B1 Apt. No:91 Kepez/Antalya-TÜRKİYE Tel:+90 242 229 6691 - 92 Fax:+90 242 229 6693

Bodrum Branch Office: İslamhaneleri Mah. Cumhuriyet Bulvarı No:4/A No:6 Bodrum/Muğla-TÜRKİYE Tel:+90 252 358 6574 pbx Fax:+90 252 358 6576



GENERAL TERMS OF TRADING

Art.1. Price

Quoted prices are exclusive of VAT and of delivery. If delivery is to be organized by GEMAS, the Customer is liable to pay delivery charges to GEMAS.

Art. 2. Specifications

In order to improve the quality of our products, GEMAS shall not be under a liability in respect of specifications, illustrations or other matter in relation to goods contained in any material such as brochures, price list or trade publications, descriptive or advertising matter or delivery notes other than in respect of specifications expressly set out in GEMAS' acknowledgment order.

Art. 3. Orders

No liability shall be attached to GEMAS, its agent or employees in respect of any representation or statement made, whether before or after agreement is reached, unless confirmed in written by GEMAS. In case of cancellation of a special order, we reserve the right to invoice all the items included in the manufacturing of this product or order.

Art. 4 Payment

Subject to any special terms agreed in writing between GEMAS and the Customer, for the first order payment for the goods shall be made in cash net with order, and delivery shall not be made until payment has been received in full set by GEMAS. In the event of default in payment by the due date, GEMAS reserves the right to charge interest on all amounts overdue at the rate of 1% calculated on a monthly basis (a part of a month being treated as a full month for this purpose) until payment in full is made and to suspend delivery or terminate the contract in respect of any of the goods or services delivered to the Customer. If GEMAS takes any legal action against a customer for a non-payment, the Customer will have to pay 20% fees of the total due amount. The Customer accepts that the liabilities of GEMAS caused by the guarantee conditions cannot be an excuse for the Customer's delay in payment.

Art. 5. Delivery

Our goods are sold ex-works izmir - Turkey. GEMAS may organize the carriage of the goods to the Customer if it is specified so in the order acknowledgement. Notification of short deliveries or loss or damage to goods in transit must be made in writing to the transport company within three working days of the date when the goods have or should have been delivered. GEMAS shall bear no liability therefore unless such notification is made by the Customer and confirmed by GEMAS. Any date or time given by GEMAS to the Customer for the delivery of the goods is an estimate only. While GEMAS will always endeavor to meet dates or times given or specified by either party, no such dates or times shall be binding on GEMAS or form part of the contract. GEMAS will not accept any order cancellation, nor penalties in case of a late delivery. The Customer will bear the cost of any urgent courier dispatch.

Art. 6. Goods return

No goods shall be returned without our previous acceptance within 8 days. The Customer will bear the transport costs. If the return is accepted the Customer shall pay 15% of the invoiced value.

Art. 7. Guarantee

GEMAS warrants the goods to be of satisfactory quality from the dispatch date and takes effects after full payment of the goods. The guarantee expires once the goods have been modified out of factory. The guarantee is limited to the replacement or repair of the parts which have been proved defective, therefore no labor, no travelling expenses, no transport, no damage nor whatsoever compensation may be claimed to GEMAS. The guarantee applies only if the installation complies with professional standards. Guarantee liability of GEMAS is only to the Customer, and does not include the third parties, such as the customers of the Customer.

Art. 8. Title to the goods

Notwithstanding delivery and the passing of risk in the goods, or any other provision of these conditions, title in the goods remains vested in GEMAS and shall only pass from GEMAS to the Customer upon full payment being made by the Customer of all sums due, on whatever account or grounds to GEMAS. In the event of goods being sold by the Customer in such a manner as to pass to a third party a valid title to the goods, whilst any such sums are due to GEMAS, GEMAS' right under this condition shall attach to such part of the proceeds of sales as is equivalent to the sums due to GEMAS and the Customer shall place the relevant part of the proceeds of sale in a separate account. Until such time as title to the goods passes to the Customer, the Customer shall hold the goods as GEMAS' fiduciary agent and bailee, and shall keep the goods separate from those of the Customer and the third parties and properly stored, protected and insured and identified as GEMAS' property. Until that the time the Customer shall be entitled to resell or use the goods in the ordinary course of its business, but shall account to GEMAS for proceeds of sale or otherwise of the goods whether tangible or intangible, including insurance proceeds, and shall keep all such proceeds separate from any money or property of the Customer and third parties and this case of tangible proceeds properly stored, protected and insured. Until such time as title to the goods passes to the Customer (and provided goods are still in existence and have not been resold) GEMAS shall be entitled at any time to require the Customer to deliver up the goods to GEMAS and if the Customer fails to do so forthwith, to enter upon any premises of the Customer or any third parties where the goods are stored and repossess the goods.

Art. 9. Claims

The application of these provisions is exclusively governed by the Turkish laws. In case of any dispute arising from the execution of an order in all or part of its modalities or regarding the interpretation of these general terms, the only competent shall be the Turkish courts, even in the case of a plurality of defendants, appeals to guarantee or indivisible or connected requests.

BANK ACCOUNT

HALKBANK IBAN No:

TR29 0001 2009 7290 0058 0001 94 (€)

TR2I 000I 2009 7290 0053 000I 82 (\$)

SWIFT CODE: TRHBTR2AXXX

GARANTI BANK IBAN No:

TR73 0006 2000 4480 0009 0719 05 (€)

TR03 0006 2000 4480 0009 0719 04 (\$)

SWIFT CODE: TGBATRISXXX